D1 ENLARGED TYPICAL UNIT TYPE 'A1' - MECHANICAL

1/4" = 1'-0"

NATURAL VENTILATION CALC.
UNIT A1

UNIT FLOOR AREA:	732
MIN. VENTILATION AREA: (UNIT AREA * 4%)	29.2
ACTUAL VENTILATION AREA: (OPERABLE OPENING AREA)	69.5

NATURAL VENTILATION CALCULATIONS BASED ON FLORIDA MECHANICAL CODE CHAPTER 4, SECTION 402.

ALL AREAS CALCULATED IN SQUARE FEET

NATURAL VENTILATION CALC.
UNIT A1S

UNIT FLOOR AREA:	810
MIN. VENTILATION AREA: (UNIT AREA * 4%)	32.4
ACTUAL VENTILATION AREA: (OPERABLE OPENING AREA)	54.7

NATURAL VENTILATION CALCULATIONS BASED ON FLORIDA MECHANICAL CODE CHAPTER 4, SECTION 402.

ALL AREAS CALCULATED IN SQUARE FEET

NATURAL VENTILATION CALC.
UNIT S1

UNIT FLOOR AREA:	614
MIN. VENTILATION AREA: (UNIT AREA * 4%)	24.5
ACTUAL VENTILATION AREA: (OPERABLE OPENING AREA)	51.0

NATURAL VENTILATION CALCULATIONS BASED ON FLORIDA MECHANICAL CODE CHAPTER 4, SECTION 402.

ALL AREAS CALCULATED IN SQUARE FEET

DRYER VENT LENGTH CALC.
UNIT A1

HORIZONTAL LENGTH:	24
VERTICAL LENGTH:	7
90° (5 FT EACH):	5
45° (2.5 FT EACH):	0
TOTAL EQ. LENGTH (FT):	36

THIS DRYER VENT TOTAL EQUIVALENT LENGTH EXCEEDS THE CODE MAXIMUM OF 35 FEET, ANY CLOTHES DRYER CONNECTED TO THE DRYER EXHAUST SYSTEM IS REQUIRED TO HAVE A MANUFACTURERS SERVICE RATING THAT MEETS OR EXCEEDS THE OVERALL DRYER VENT LENGTH OF THIS SYSTEM AS CALCULATED PER THE DRYER MANUFACTURER REQUIREMENTS.

MECHANICAL CONTRACTOR TO PROVIDE PERMANENTLY AFFIXED LABEL IDENTIFYING THE TOTAL EQUIVALENT LENGTH OF THE UNIT DRYER EXHAUST SYSTEM AS LISTED ABOVE WITHIN 6 FEET OF THE DRYER EXHAUST DUCTWORK CONNECTION STATING "THIS DRYER VENT IS 36' LONG AND REQUIRES A DRYER CAPABLE OF MEETING THIS DRYER VENT LENGTH".

DRYER VENT LENGTH CALC.
UNIT A1S

HORIZONTAL LENGTH:	24
VERTICAL LENGTH:	7
90° (5 FT EACH):	5
45° (2.5 FT EACH):	0
TOTAL EQ. LENGTH (FT):	36

THIS DRYER VENT TOTAL EQUIVALENT LENGTH EXCEEDS THE CODE MAXIMUM OF 35 FEET, ANY CLOTHES DRYER CONNECTED TO THE DRYER EXHAUST SYSTEM IS REQUIRED TO HAVE A MANUFACTURERS SERVICE RATING THAT MEETS OR EXCEEDS THE OVERALL DRYER VENT LENGTH OF THIS SYSTEM AS CALCULATED PER THE DRYER MANUFACTURER REQUIREMENTS.

MECHANICAL CONTRACTOR TO PROVIDE PERMANENTLY AFFIXED LABEL IDENTIFYING THE TOTAL EQUIVALENT LENGTH OF THE UNIT DRYER EXHAUST SYSTEM AS LISTED ABOVE WITHIN 6 FEET OF THE DRYER EXHAUST DUCTWORK CONNECTION STATING "THIS DRYER VENT IS 36' LONG AND REQUIRES A DRYER CAPABLE OF MEETING THIS DRYER VENT LENGTH".

DRYER VENT LENGTH CALC.
UNIT S1

HORIZONTAL LENGTH:	14.5
VERTICAL LENGTH:	7
90° (5 FT EACH):	5
45° (2.5 FT EACH):	5
TOTAL EQ. LENGTH (FT):	31.5

THIS DRYER VENT SYSTEM IS LESS THAN THE CODE MAXIMUM LENGTH OF 35 FEET. A STANDARD SERVICE RATED DRYER MAY BE INSTALLED.

REFERENCE NOTES: (X)

1. MOUNT AHU PER CLOSET MOUNTED AHU DETAIL ON SHEET M6.02.
2. ROUTE REFRIGERANT LINES UP TO CONDENSING UNITS ON ROOF. ROUTE CONDENSATE DRAIN LINES WITHIN MECHANICAL CLOSET WALL. SEE PLUMBING PLANS FOR CONDENSATE LINE CONTINUATION. ROUTE REFRIGERANT LINES PER DIAGRAM M7.01.
3. INSTALL DRYER EXHAUST WALL CONNECTION BOX PER DETAIL SHEET M6.01.
4. ROUTE EXHAUST DUCT FROM WALL MOUNTED EXHAUST FAN THROUGH TRUSS SPACE TO BUILDING SIDEWALL PER DETAIL ON SHEET M6.01. TERMINATE DUCT AT EXTERIOR WALL CAP PER DIAGRAM SHEET M7.01.
5. ROUTE DRYER EXHAUST DUCT THROUGH TRUSS SPACE TO BUILDING SIDEWALL PER DETAIL SHEET M6.01 TERMINATE DUCT AT EXTERIOR WALL CAP PER DIAGRAM SHEET M7.01.
6. PROVIDE FACTORY WALL PANEL FOR RETURN AIR AND ACCESS.
7. DUCTLESS RANGE HOOD.

GENERAL NOTES:

1. PROVIDE 1" DOOR UNDER CUT IN ALL BEDROOMS IN ADDITION TO TRANSFER GRILLE.
2. ALL EXHAUST OUTLETS TO BE FARTHER THAN 3 FEET AWAY FROM ANY OPERABLE WINDOWS.

H1 ENLARGED TYPICAL UNIT TYPE 'A1S' - MECHANICAL

1/4" = 1'-0"

H5 ENLARGED TYPICAL UNIT TYPE 'S1' - MECHANICAL

1/4" = 1'-0"

Adam Barney
2018-01-17 15:52:51 -05:00

PERMIT REVIEW STAMP

ISSUE HISTORY

No.	Date	Description
1	1/18/2018	ISSUE FOR PERMIT

REVISION HISTORY

No.	Date	Description

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com BR3569

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 28730

JLC 17.0137.00

Adam Joseph Barney
P.E. #:69124

ADAM J BARNEY LICENSE No. 69124 STATE OF FLORIDA PROFESSIONAL ENGINEER

SUMMER BAY APTS. II
LAKE COUNTY, FL

Drawn:	MJR/KCM
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	11/10/2017
Project #:	5389

ENLARGED TYPICAL UNIT PLANS - MECHANICAL

M4.01

© 2015, These documents and their contents are the property of F.K.S. ENGINEERS, INC. and are issued only for the specific project cited on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of F.K.S. ENGINEERS, INC. is prohibited by law.