WINDOW SCHEDULE

TYPE	WINDOW UNIT			GLAZING				FRAME				REMARKS
	WIDTH	HEIGHT	HEAD HEIGHT	TYPE	THICKNESS	U VALUE	SHGC	MATERIAL	HEAD	JAMB	SILL	
A	3'-0"	5'-0"	8'-0"	LOW-E	3/4"	0.34	0.27	VINYL	D9/A7.02	F7,D9/A7.02	H9/A7.02	
B	2'-6"	5'-0"		LOW-E	3/4"	0.34	0.27	VINYL	D9/A7.02	F7,D9/A7.02	H9/A7.02	

WINDOW NOTES:

A. VERIFY ROUGH OPENING REQUIRED WITH WINDOW MANUFACTURER.

B. WINDOW MANUFACTURER SHALL PROVIDE CERTIFICATION, SIGNED AND SEAL BY A REGISTERED **FLORIDA** PROFESSIONAL THAT:

1- WINDOWS WILL BE ABLE TO WITHSTAND REQUIRED WIND LOADS AND PRESSURE.

2- TO SUPPLY TYPE AND NUMBER OF FASTENERS REQUIRED TO SECURE FRAME TO HEAD, JAMBS & SILL OF ALL WINDOW OPENINGS.

C. PROVIDE SEALANT AT ALL SCREW-HOLES PROVIDED FOR FASTENING PRIOR TO FASTENER INSTALLATION.

D. WINDOWS UNITS SHALL BE ANCHOR THROUGH THE JAMB, ANCHORS SHALL BE SECURELY FASTENED IN TO THE STRUCTURAL MATERIAL

E. PROVIDE TEMPERED GLASS AT ALL WINDOWS LOWER SASH IF SILL HEIGHT IS BELOW 2 FEET; WITHIN 3'-0" OF PATIO DOORS, OR AS OTHERWISE NOTED.

F. PROVIDE FLORIDA TESTED AND APPROVE IMPACT RESISTANT INSULATING GLASS IN COMPLIANCE WITH SPECIFICATION 085313 AND FBC 2014 SECTION 2411.

F1 WINDOW SILL ISOMETRIC (SIDING)
3" = 1'-0"

F3 WINDOW JAMB ISOMETRIC (SIDING)
3" = 1'-0"

D9 WINDOW HEAD DETAIL (SIDING)
3" = 1'-0"

F5 WINDOW SILL FLASHING DETAIL (SIDING)
6" = 1'-0"

F7 WINDOW JAMB DETAIL
3" = 1'-0"

F9 WINDOW JAMB (SIDING)
3" = 1'-0"

H9 WINDOW SILL DETAIL (SIDING)
3" = 1'-0"

PERMIT REVIEW STAMP

ISSUE HISTORY

No.	Date	Description
1	1/18/2018	ISSUE FOR PERMIT

REVISION HISTORY

No.	Date	Description

© 2017 These documents and their contents are the property of FUGLEBERG KOCH ARCHITECTS, and are issued only for the specific project noted on these drawings. Any reproductions, revisions or modifications of these documents without the expressed written consent of Fugleberg Koch, is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

MICHAEL E. GOVE
FLORIDA LICENSE # AR94111

Digitally signed by Michael Gove
Date: 2018.01.22 13:59:56 -05'00'

STATE OF FLORIDA MICHAEL E. GOVE AR94111 REGISTERED ARCHITECT

Drawn:	Author
Checked:	Checker
Approval:	Approver
Date:	Issue Date
Project #:	5389

SUMMER BAY APTS. II
LAKE COUNTY, FL

WINDOW SCHEDULE AND DETAILS

A7.02

PLOTTED: 1/22/2018 10:08:10 AM