

PROJECT SITE

OWNER/DEVELOPER

ROHDIE

SCHOOLHOUSE, LLC

ATTN: RON LEICHTNER

**52 VANDERBILT** 

NEW YORK, NEW YORK 10017

PHONE (212) 682-5784

A3.15 ELEVATOR

A4.01 BUILDING TYPE 1 - ELEVATIONS A4.02 BUILDING TYPE 2 - ELEVATIONS A4.03 BUILDING TYPE 3 - ELEVATIONS

A4.10 BUILDING TYPE 1 - SECTIONS A4.11 BUILDING TYPE 2 - SECTIONS

A4.04 ENLARGED PARTIAL ELEVS. & METER CENTER



## **PROJECT NARRATIVE:**

#### **EDIT AS REQUIRED:**

This project narrative is provided as a brief outline of the proposed scope of building improvements for this Project.

The Project consists of the construction of a new multi-unit residential rental apartment building in Fort Myers, FL accessed off of Veronica S. Shoemaker Boulevard. The program includes a total of 324 dwelling units of 6 unit types (1, 2, and 3 bedroom) with solarium, balconies, and

The dwelling units are distributed among 12 residential buildings of 3 separate building types. The residential buildings are designed to provide 3 floors of dwelling units. The buildings are classified as Type V (A) construction, and all are sprinklered to the requirements of NFPA 13R systems. The residential and amenity buildings are designed as wood frame structures that include engineered truss components for both framed floors and roofs. The buildings are placed on concrete slab on grade foundations with integral thickened edges and grade beams.

The Project program also includes a Clubhouse, Mail Kiosk and Trash enclosures, which are submitted under a seperate Cover.

CONTRACTOR

TBD

The Project scope includes site engineering and landscape improvements that are submitted under separate cover.

#### SYMBÖL KEY: NUMBERED BY TYPE NUMBERED BY TYPE SYMBOL REFER TO SCHEDULE WALL TYPE OR UL A,B,C, ETC. IN ONE DIRECTION TARGET 1,2,3, ETC. IN THE OTHER **DEFERRED SUBMITTALS: ROOM TAG** ? - ROOM NUMBER Deferral of any submittal items shall have the prior approval of the Building Official having jurisdiction.

DRAWING NUMBER TITLE → DIRECTION OF **ELEVATION** → SHEET NUMBER **REFERENCES** 

Name Elevation

6:12 SLOPE SLOPE DIRECTI

NOTE

XX - CHANGE IN

LOCATION OF

- AND PEIGNATIVENTER

LOCATION OF

ABPEGATIVALER

REV. LOCATION

SECTION REFERENCES

REFERENCES

INTERIOR

**ELEVATIONS** 

REFERENCE

**ROOF SLOPE** 

ARROW

ROOF SLOPE

NOTE TAG

EVEL CHANGE

N MARK

XX

 DIRECTION OF A) BUILDING RAILINGS & GUARDRAILS REVIEW BY ARCHITECT SHEET NUMBE ) FIRE ALARM SYSTEM REVIEW BY ARCHITECT λ**AREA** ) AUTOMATIC FIRE SUPPRESSION (SPRINKLER) SYSTEM REVIEW BY ARCHITECT

PRE-ENGINEERED (WOOD) FLOOR & ROOF TRUSS SHEET NUMBER X- VIEW REVIEW BY ARCHITECT NUMBER BUILDING IDENTIFICATION AND WAYFINDING SIGNAGE REVIEW BY OWNER SHEET NUMBER

SITE FENCING

REVIEW BY LANDSCAPE ARCHITECT

PERMIT REVIEW STAMP

Submittal documents for deferred submittal items shall be submitted to the Entity designated below for the project

who shall review them. These will then be forwarded by the

have been reviewed and that they have been found to be in

3) The deferred submittal items shall not be installed until

neir design and submittal documents have been approved.

Owner to the Building Official having jurisdiction with a

general compliance with the design of the project.

notation indicating that the deferred submittal documents

THIS PLAN REVIEWED FOR SUBSTANTIAL CODE

DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00851
PROPERTY ADDRESS: 3777 OLD BERRY POINT

**ISSUE HISTORY** 

11/22/19 SCHEMATIC DESIGN 12/06/19 DESIGN DEVELOPMENT 02/28/20 PERMIT REVIEW SET

**REVISION HISTORY** PERMIT COMMENT RESPONSES PERMIT COMMENT RESPONSES 2

# THE ROBERT FT. MYERS, FL

MECHANICAL / ELECTRICAL / PLUMBING LANDSCAPE ARCHITECT

**ARCHITECT FUGLEBERGKOCH** 

FUGLEBERG KOCH

ATTN: MICHAEL GOVE 2555 TEMPLE TRAIL WINTER PARK, FLORIDA 32789 PHONE (407) 629-0595 FAX (407) 628-1057

**CIVIL ENGINEER** BANKS ENGINEERING

10511 SIX MILE CYPRESS PARKWAY FORT MYERS, FLORIDA 33966 (239) 939-5490

STRUCTURAL

ASE ENGINEERING SERVICES, INC.

ENGINEERINGSERVICES, INC

10244 EAST COLONIAL DRIVE, SUITE 202 ORLANDO, FLORIDA 32817 PHONE (407) 677-5565 FAX (407) 730-2999

**INDEX OF DRAWINGS** 

SALAS O'BRIEN 3501 QUADRANGLE BOULEVARD, SUITE 100 ORLANDO, FLORIDA 32817

PHONE (407) 380-0400 FAX (407) 380-5900

SALAS O'BRIEN

ATTN: NAME ADDRESS CITY, FL 3xxxx (407) 123-4567

TBD

**INDEX OF DRAWINGS** 

ATTN: NAME **ADDRESS** CITY, FL 3xxxx (407) 123-4567

**INTERIOR DESIGN** 

TBD

ATTN: NAME ADDRESS CITY, FL 3xxxx (407) 123-4567

INDEX OF DRAWINGS					
SHT#	SHEET NAME	REV. No.	DATE		
00-ARGH Q		· · · · · · · · · · · · · · · · · · ·	~~~~		
A0.01	COVER SHEET	2	6/03/2020		
~\A0.02~\	CODE ANALYSIS	qui qui			
A0.10	LIFE SAFETY PLANS - BUILDING TYPE 1				
A0.11	LIFE SAFETY PLANS - BUILDING TYPE 2				
A0.12	LIFE SAFETY PLANS - BUILDING TYPE 3				
A0.30	UL REFERENCE DIRECTORY - WALL SYSTEMS				
A0.31	UL REFERENCE DIRECTORY - WALL SYSTEM				
A0.32	UL REFERENCE DIRECTORY - WALL SYSTEMS				
A0.33	UL REFERENCE DIRECTORY - FLOOR SYSTEM				
A0.34	UL REFERENCE DIRECTORY - FLOOR SYSTEM				
A0.35	UL REFERENCE DIRECTORY - ROOF SYSTEM				
A0.36	UL REFERENCE DIRECTORY - FLOOR PENETRATIONS				
A0.37	UL REFERENCE DIRECTORY - PENETRATIONS				
01-ARCHIT	ECTURAL				
A1.01	ARCHITECTURAL SITE PLAN				
A1.01	ARCHITECTURAL SITE PLAN				
02-ARCHIT	TCTLIDAI				
A2.01	BUILDING TYPE 1 - GROUND LEVEL				
A2.01	BUILDING TYPE 1 - GROUND LEVEL				
A2.02	BUILDING TYPE 1 - 2ND LEVEL				
A2.03 A2.04	BUILDING TYPE 1 - 3RD LEVEL BUILDING TYPE 1 - ROOF PLAN				
A2.04 A2.05	BUILDING TYPE 1 - ROOF PLAN  BUILDING TYPE 2 - GROUND LEVEL				
A2.05 A2.06	BUILDING TYPE 2 - GROUND LEVEL  BUILDING TYPE 2 - 2ND LEVEL				
A2.06 A2.07	BUILDING TYPE 2 - 2ND LEVEL BUILDING TYPE 2 - 3RD LEVEL				
	BUILDING TYPE 2 - 3RD LEVEL BUILDING TYPE 2 - ROOF PLAN				
A2.08					
A2.09	BUILDING TYPE 3 - GROUND LEVEL				
A2.10	BUILDING TYPE 3 - 2ND LEVEL				
A2.11	BUILDING TYPE 3 - 3RD LEVEL				
A2.12	BUILDING TYPE 3 - ROOF PLAN				
A2.13	ENLARGED GARAGE PLANS				
A2.14	ENLARGED PATIO PLANS				
A2.15	BREEZEWAY RCP - BLDG 1 AND 2				
A2.16	BREEZEWAY RCP - BLDG 3				
03-ARCHIT	ECTURAL				
A3.01	1 BR UNIT PLANS - S1				
A3.02	1 BR UNIT PLANS - A1				
A3.03	1 BR UNIT PLANS - A2S				
A3.04	2 BR UNIT PLANS - B1				
A3.05	2 BR UNIT PLANS - B2S				
A3.06	3 BR UNIT PLANS - C1				
A3.10	ENLARGED PLANS - KITCHEN/BATHROOM				
A3.11	ENLARGED PLANS - BATHROOM				
A3.11	KITCHEN, BATH, AND LAUNDRY REQ.				
A3.13	FINISH SCHEDULES				
A3.14	STAIRS				
7.00.17	STAIRS				

SHT#	SHEET NAME	REV. No.	DATI
A4.12	BUILDING TYPE 3 - SECTIONS		
05-ARCHIT	ECTURAL		
A5.01	WALL SECTION DETAILS		
A5.02	WALL SECTION DETAILS		
A5.03	ROOF SECTION DETAILS		
A5.04	MISC. SECTION DETAILS		
A5.05	MISC. DETAILS		
06-ARCHIT	ECTURAL PLAN DETAILS		
A6.01	PLAN DETAILS		
A6.02	PLAN DETAILS		
07-ARCHIT	ECTURAL		
A7.01	DOOR SCHEDULE AND DETAILS		
A7.02	DOOR DETAILS		
A7.03	WINDOW SCHEDULE AND DETAILS		
A7.04	WINDOW AND DOOR TAPING PROCEDURES		
10 - <u>AR</u> CHI	TECTURE ANCILLARY		
CH0.01	CLUBHOUSE CODE/ LIFE SAFETY PLAN		
CH2.01	CLUBHOUSE FLOOR PLAN		
CH2.03	CLUBHOUSE REFLECTED CEILING PLAN		
CH2.04	CLUBHOUSE ROOF PLAN		
CH3.01	CLUBHOUSE INTERIOR ELEVATIONS		
CH3.02	CLUBHOUSE - MAIL KIOSK INTERIOR ELEVATIONS		
CH4.01	CLUBHOUSE EXTERIOR ELEVATIONS		
CH4.02	CLUBHOUSE EXTERIOR ELEVATIONS		
CH4.03	CLUBHOUSE EXTERIOR ELEVATIONS		
CH5.01	CLUBHOUSE BUILDING SECTIONS		
CH6.01	CLUBHOUSE PLAN DETAILS		
CH6.02	CLUBHOUSE SECTION DETAILS		
CH7.01	DOOR SCHEDULE AND DETAILS		
CH7.02	CLUBHOUSE WINDOW DETAILS AND SCHEDULES		
CH10.01	TRASH ENCLOSURE & RECYCLE BIN		
11-STRUC			
S0.01	GENERAL NOTES FOR BLDG TYPES 1,2,3		
S0.02	SCHEDULES AND DETAILS FOR BUILDING TYPES 1,2,3		
S1.01	BUILDING TYPE 1 FOUNDATION PLAN		
S1.02	BUILDING TYPE 1 2ND FLOOR FRAMING PLAN		
S1.03	BUILDING TYPE 1 3RD FLOOR FRAMING PLAN		
S1.04	BUILDING TYPE 1 ROOF FRAMING PLAN		
S2.01	BUILDING TYPE 2 FOUNDATION PLAN		
S2.02	BUILDING TYPE 2 2ND FLOOR FRAMING PLAN		
S2.03	BUILDING TYPE 2 3RD FLOOR FRAMING PLAN		
S2.04	BUILDING TYPE 2 ROOF FRAMING PLAN		
S3.01	BUILDING TYPE 3 FOUNDATION PLAN		
S3.02	BUILDING TYPE 3 2ND FLOOR FRAMING PLAN		
S3.03	BUILDING TYPE 3 3RD FLOOR FRAMING PLAN		
S3.04	BUILDING TYPE 3 ROOF FRAMING PLAN		
S5.01	SECTIONS AND DETAILS FOR BUILDING TYPES 1,2,3		
S5.02	SECTIONS AND DETAILS FOR BUILDING TYPES 1,2,3		
S5.03	SECTIONS AND DETAILS FOR BUILDING TYPES 1,2,3		
S5.04	SECTIONS AND DETAILS FOR BUILDING TYPES 1,2,3	+	
	1		

SHT#	SHEET NAME	REV. No.	DATE
1.5-STRU	CTURAL		
CS1.01	GENERAL NOTES		
CS1.01	GENERAL NOTES AND SCHEDULES		
CS2.01	FOUNDATION PLAN		
CS3.01	ROOF FRAMING PLAN		
CS4.02	TRASH ENCLOSURE FOUNDATION PLAN		
CS5.01	SECTIONS AND DETAILS		
CS5.02	SECTIONS AND DETAILS		
CS5.03	SECTIONS AND DETAILS		
2-MECHA	NICAL		
M0.01	LEGENDS AND SCHEDULES - MECHANICAL	1	5/06/20
M2.01	BUILDING TYPE 1 - GROUND LEVEL - MECHANICAL	1	5/06/20
M2.02	BUILDING TYPE 1 - 2ND LEVEL - MECHANICAL		
M2.03	BUILDING TYPE 1 - 3RD LEVEL - MECHANICAL		
M2.05	BUILDING TYPE 2 - GROUND LEVEL - MECHANICAL	1	5/06/20
M2.06	BUILDING TYPE 2 - 2ND LEVEL - MECHANICAL	<del>                                     </del>	5,55,20
M2.07	BUILDING TYPE 2 - 2ND LEVEL - MECHANICAL  BUILDING TYPE 2 - 3RD LEVEL - MECHANICAL		
M2.07	BUILDING TYPE 2 - 3RD LEVEL - MECHANICAL  BUILDING TYPE 3 - GROUND LEVEL - MECHANICAL	1	5/06/20
			5/06/20
M2.10	BUILDING TYPE 3 - 2ND LEVEL - MECHANICAL		
M2.11	BUILDING TYPE 3 - 3RD LEVEL - MECHANICAL		
M3.01	UNIT PLANS - MECHANICAL		
M3.02 M6.01	UNIT PLANS - MECHANICAL  DETAILS - MECHANICAL		
	IANICAL	· · · · · · · · · · · · · · · · · · ·	~~~~
2,5-MECH CM2,01	CLUBHOUSE FLOOR PLAN - MECHANICAL	2	6/03/2020 5/06/20
2,5-MEC+		2	6/03/2020 5/06/20
2,5-MECH CM2,01	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL	2	$\sim$
2,5-MECk CM2,01 CM6.01	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL	2 1	$\sim$
S-ELECT	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL	2 2 2	5/06/20
5-MECK CM2,01 CM6.01 -ELECTY E0.01	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL		5/06/20
CM2,01 CM6.01 CM6.01 3-ELECT E0.01 E0.02	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
5-MECK QM2,01 CM6.01 ELECT E0.01 E0.02 E1.01	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL SITE PLAN -ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
2,5-MECK CM2,01 CM6.01 3-ELECT E0.01 E0.02 E1.01 E2.01	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL SITE PLAN -ELECTRICAL BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
2,5-MECK CM2,01 CM6.01 B-ELECT E0.01 E0.02 E1.01 E2.01 E2.02	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL SITE PLAN -ELECTRICAL BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
CM2,01 CM6.01 E0.01 E0.02 E1.01 E2.01 E2.02 E2.03	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL SITE PLAN -ELECTRICAL BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
ELECTION E0.02 E1.01 E2.02 E2.03 E2.05	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL SITE PLAN -ELECTRICAL BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
5-MECK CM2,01 CM6.01 E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL	2	5/06/20 6/03/2020 6/03/2020 6/03/2020
ELECTION E2.01 E2.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.09	CLUBHOUSE FLOOR PLAN - MECHANICAL DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL SITE PLAN -ELECTRICAL BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL	2	5/06/20 5/06/20 6/03/2020 6/03/2020
ELECTION E0.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL	2	5/06/20 6/03/2020 6/03/2020 6/03/2020
ELECTOR E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL	1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20
ELECTOR E0.01 E0.02 E1.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.10 E2.11 E2.13	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL	1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20
ELECTION EC. 101 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.10 E2.11 E2.13 E2.14	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL	2 2 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20
ELECT E0.01 E0.02 E1.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.10 E2.11 E2.13 E2.14 E3.01	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL	2 2 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20
ELECT E0.01 E0.02 E1.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - BLECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  UNIT PLANS AND TRASH ENCLOSURE - ELECTRICAL	2 2 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20
ELECTOR E0.01 E0.02 E1.01 E2.01 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - BLEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  UNIT PLANS AND TRASH ENCLOSURE - ELECTRICAL  SCHEDULES - ELECTRICAL	2 2 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20
ELECTION E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN - ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - BLECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL	2 2 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20
ELECTOR E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02 E4.03	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  RIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN - ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - BLECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  UNIT PLANS AND TRASH ENCLOSURE - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL	2 2 1 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20
ELECTOR E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02 E4.03 E4.04	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  RICAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  UNIT PLANS - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL	2 2 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 6/03/2020 6/03/2020
5-MECK CM2,01 CM6.01 E0.01 E0.02 E1.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02 E4.04 E5.01	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  RIGAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BUILDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - BUILD	2 2 1 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20
ELECTOR E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02 E4.03 E4.04 E5.01 E5.02	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  RIGAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BÜLDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS AND TRASH ENCLOSURE - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL  POWER RISER DIAGRAMS - ELECTRICAL	2 2 1 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20
ELECTION E0.01 E0.02 E1.01 E2.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02 E4.03 E4.04 E5.01 E5.02 E5.03	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  RIGAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN - ELECTRICAL  BÜLDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS AND TRASH ENCLOSURE - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL  POWER RISER DIAGRAMS - ELECTRICAL  POWER RISER DIAGRAMS - ELECTRICAL  POWER RISER DIAGRAMS - ELECTRICAL	2 2 1 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20
5-MECK CM2,01 CM6.01 E0.01 E0.02 E1.01 E2.02 E2.03 E2.05 E2.06 E2.07 E2.09 E2.10 E2.11 E2.13 E2.14 E3.01 E3.02 E4.01 E4.02 E4.03 E4.04 E5.01 E5.02	CLUBHOUSE FLOOR PLAN - MECHANICAL  DETAILS - MECHANICAL  RIGAL  SYMBOL LEGEND - ELECTRICAL  LIGHT FIXT. SCHED. AND GEN. NOTES - ELECTRICAL  SITE PLAN -ELECTRICAL  BÜLDING TYPE 1 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 1 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 2 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 2 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - GROUND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 2ND LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  BUILDING TYPE 3 - 3RD LEVEL - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  ENLARGED GARAGE PLANS - ELECTRICAL  UNIT PLANS AND TRASH ENCLOSURE - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL  SCHEDULES - ELECTRICAL  POWER RISER DIAGRAMS - ELECTRICAL	2 2 1 1 1 1 1 1 1	5/06/20 6/03/2020 6/03/2020 6/03/2020 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20 5/06/20

<b>HT</b> #	SHEET NAME	REV. No.	~ DATE ~
.02	DETAILS AND SYSTEM RISER - ELECTRICAL	2	6/03/2020
س			
j-ELEG	IRIÇAL	· · · · · · · · · · · · · · · · · · ·	~~~~~
CE2.01	CLUBHOUSE FLOOR PLAN - POWER AND SYSTEMS	$\frac{2}{\sqrt{2}}$	6/03/2020
CÉ2.02	CLUBHOUSE FLOOR PLAN-LIGHTING	4 0 p	5/06/20
-PLUMB	NG		
P0.01	LEGENDS, SCHEDULES AND NOTES - PLUMBING		
P2.01	BUILDING TYPE 1 - GROUND LEVEL - PLUMBING		
P2.02	BUILDING TYPE 1 - 2ND LEVEL - PLUMBING		
P2.03	BUILDING TYPE 1 - 3RD LEVEL - PLUMBING		
P2.05	BUILDING TYPE 2 - GROUND LEVEL - PLUMBING		
P2.06	BUILDING TYPE 2 - 2ND LEVEL - PLUMBING		
P2.07	BUILDING TYPE 2 - 3RD LEVEL - PLUMBING		
P2.09	BUILDING TYPE 3 - GROUND LEVEL - PLUMBING		
P2.10	BUILDING TYPE 3 - 2ND LEVEL - PLUMBING		
P2.11	BUILDING TYPE 3 - 3RD LEVEL - PLUMBING		
P3.01	UNIT PLANS - PLUMBING		
P3.02	UNIT PLANS AND TRASH ENCLOSURE - PLUMBING		
P5.01	RISER DIAGRAMS - PLUMBING		
P5.02	RISER DIAGRAMS - PLUMBING		
P5.03	RISER DIAGRAMS - PLUMBING		
P5.04	RISER DIAGRAMS - PLUMBING		
	DW 6		
1.5-PLUM			F (0.0.10.0
CP2.01	CLUBHOUSE BUILDINGS - PLUMBING	1	5/06/20
CP5.01	RISER DIAGRAMS - PLUMBING		
5-FIRE/PE	OTECTION	····	~~~~
FP0,01	LEGEND, SCHEDULES AND DETAILS - FIRE PROTECTION	<u>, , , , , , , , , , , , , , , , , , , </u>	6/03/2020
FP2.01	BUILDING TYPE 1 - GROUND LEVEL - FIRE PROTECTION	1	5/06/20
FP2.02	BUILDING TYPE 1 - 2ND LEVEL - FIRE PROTECTION		
FP2.03	BUILDING TYPE 1 - 3RD LEVEL - FIRE PROTECTION		
FP2.05	BUILDING TYPE 2 - GROUND LEVEL - FIRE PROTECTION		
FP2.06	BUILDING TYPE 2 - 2ND LEVEL - FIRE PROTECTION		
FP2.07	BUILDING TYPE 2 - 3RD LEVEL - FIRE PROTECTION		
—	BUILDING TYPE 3 - GROUND LEVEL - FIRE PROTECTION		
FP2.09		1	
	BUILDING TYPE 3 - 2ND LEVEL - FIRE PROTECTION		

FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www.fuglebergkoch.com

THE ROBERT FT. MYERS, FL **COVER SHEET** 

1 2	NO CODE COAZ EDITION	4	5	6	7	i	8	9
BUILDING CODE ANALYSIS - FLORIDA BUILDIN	NG CODE, 2017 EDITION	<u> </u>						
CODE SUMMARY  APPLICABLE CODES	FIRE-RESISTANCE RATING REQUIREMENTS (PER TABLE 601)	MEANS OF EGRESS - [FBC TA		I MAY				FT. MYERS, Florida - UNIT TABLE 8/2/2019
BUILDING CODE: 2017 FLORIDA BUILDING CODE      LIFE SAFETY CODE: 2017 NFPA 101	APARTMENTS - TYPE V(A)	OCCUPANCY CLASSIFICATION LOCATION		WABLE) TRAVEL REMARKS				5/2/2010
3. PLUMBING CODE: 2017 FLORIDA PLUMBING CODE	V(A)    REQ'D   PROV	R-2 - DWELLING BUILDING TYPE 1, 2	2, 3 75'	PRINK. (ACTUAL)  125 53'-0"				BUILDING TYPE 1 UNIT UNIT UNIT UNIT UNIT UNIT UNIT UNIT
4. ENERGY CODE: 2017 FLORIDA ENERGY CONSERVATION	STRUCTURAL FRAME: INCLUDING COLUMNS, GIRDERS, TRUSSE\$ 1 1	R-2 - EXIT ACCESS BUILDING TYPE 1, 2	2, 3 200'	250 127'-6"				TBR   TBR   ZBR   ZBR   3BR   GARAGE
CODE AND AMMENDMENTS	BEARING WALLS: EXTERIOR (PER TABLE 601/602/704.10)  1 1	See Life Safety Plans for specific information.     Section 1007.1.1 Two Exits:						2ND FLOOR         0         0         0         6         2         0         0         8           3RD FLOOR         0         4         0         2         2         0         0         8
5. FIRE CODE: 2017 FLORIDA FIRE PREVENTION CODE  6. ACCESSIBILITY CODE: REFERENCES: 2017 FLORIDA BUILDING CODE:	INTERIOR 1 1*	Exception 1: Where interior exit stairways are interior exit stairways are interior exit separation shall be seen as a second of the second of	be measured along the shortes	esistance-rated <i>corridor</i> conforming to the requirements of t direct line of travel within the <i>corridor</i> .				UNITS PER BUILDING 0 4 0 14 4 0 6 22
ACCESSIBILITY FHA - FAIR HOUSING ACCESSIBILITY GUIDELINES	NONBEARING WALLS AND PARTITIONS: EXTERIOR (PER TABLE 601/602) 0 0 INTERIOR (PER SECTION 601) 0 0	Exception 2: Where a building is equipped through the separation distance of the exit doors or exit diagonal dimension of the area served.	ghout with an automatic sprinkl access doorways shall not be l	der system in accordance with Section 903.3.1.1 or 903.3.1.2, less than one-third of the length of the maximum overall				UNITS PER (4) BUILDINGS 0 16 0 56 16 0 24 88
7. ELECTRICAL CODE: 2014 NATIONAL ELECTRIC CODE	FLOOR CONSTRUCTION NOT INCLUDING SUPPORTING BEAMS AND 1 1*	b) Table 1006.2.1 - Note a & 1016.2 - Note b						BUILDING TYPE 2
8. MECHANICAL CODE: 2017 FLORIDA MECHANICAL CODE  9. NFPA 101, STANDARD FOR PORTABLE FIRE EXTINGUISHERS, 2012 ED.	JOISTS PER EXCEPTION 2 of 7.12.4	occupancies where automatic sprinkler systems	c sprinkler system in accordance was are permitted in accordance was	se with section 903.3.1.1 or 903.3.1.2. See section 903 for with section 903.3.1.2.				1ST FLOOR         1         2         0         0         0         4         6         7           2ND FLOOR         2         2         2         0         0         4         0         10
10. NFPA 13R, STANDARD FOR INSTALLATION OF SPRINKLER SYSTEMS	SEPARATION DISTANCE (PER TABLE 602)							3RD FLOOR 2 6 2 0 0 0 0 10  UNITS PER BUILDING 5 10 4 0 0 8 6 27
IN RESIDENTIAL OCCUPANCIES UP TO, AND INCLUDING FOUR STORIES IN HEIGHT, 2012 EDITION.	10 ≤ X ≤ 30' '   ' '   ' '   ' '   ' '   ' '   ' '   ' '   '   ' '   '	MAXIMUM AREA OF EXTERION FROM TABLE 705.8 - [FBC 2017: BUILDING]	OR WALL OPENIN	GS:				BUILDING 5 10 4 0 0 8 6 27  UNITS PER (4) BUILDINGS 20 40 16 0 0 32 24 108
GENERAL CODE PARAMETERS	BALCONIES	ASSUMED PROPERTY LINE DISTANCE:	ı					BUILDING TYPE 3
APARTMENTS:  DESCRIPTION REQUIRED OR ALLOWABLE PROJECT REMARKS			ALLOWABLE ACTUAL (WORST CA	<u>=</u> <u>ASE)</u>				1ST FLOOR         0         2         0         2         0         4         10         8           2ND FLOOR         0         2         2         2         2         4         0         12
VIND SPEED 156 MPH 156 MPH SEC. 1609 ULTIMATE	Balconies and similar projections of combustible construction other than <i>fire-retardant-treated wood</i> shall be fire-resistance rated in accordance with Table 601 for floor construction or shall be of Type IV construction in accordance with Section	UNPROTECTED, SPRINKLERED (UP, S)  0 FT TO 3 FT	NP NP					3RD FLOOR 0 6 2 2 2 0 0 12
EISMIC ZONE N/A N/A SEC. 1613	602.4 The aggregate length shall not exceed 50 percent of the buildings perimeter on each floor.	OVER 3 FT TO 5 FT OVER 5 FT TO 10 FT	15% 25% 16%					UNITS PER BUILDING         0         10         4         6         4         8         10         32
NOW LOAD         N/A         N/A         SEC. 1608           ROST DEPTH         N/A         N/A         SEC 1805.2.1	Exceptions:  3. Balconies and similar projections on buildings of Type III, IV and V construction	OVER 10 FT TO 15 FT OVER 15 FT TO 20 FT OVER 20 FT TO 25 FT	45% 75% NI NI					UNITS PER (4) BUILDINGS 0 40 16 24 16 32 40 128
- COMPONENTS AND CLADDING PRESSURES:(NET, SEE PRESSURE	shall be permitted to be of Type V construction, and shall not be required to have a <i>fire-resistance rating</i> where sprinkler protection is extended to these	OVER 25 FT TO 30 FT OVER 30' FROM ASSUMED PROPERTY LINE	NL NL NR NR					12 TOTAL BUILDINGS 20 96 32 80 32 64 88 324  PERCENT OF TOTAL
ZONE DETAILS ON STRUCTURAL DRAWINGS - WIND SPEED WAS DETERMINED THRU LINEAR INTERPOLATION UNDER	<ul> <li>areas.</li> <li>4. Where sprinkler protection is extended to the balcony areas, the aggregate length of the balcony on each floor shall not be limited.</li> </ul>	FROM ASSUMED PROPERTY LINE						UNITS 6.17% 29.62% 9.88% 24.70% 9.88% 19.75% 100 100.00°
CATEGORY II LEE COUNTY WIND SPEED MAP.				ION REQUIREMENTS BY COMPON EVATION CODE 2017 - TABLE 402.1.				
BUILDING CODE PARAMETERS - [FBC 2017]		CLIMATE EENESTRATION SKYLIGHT	GLAZED CEILING FENESTRATION R-VALUE	WOOD FRAME ATTIC MASS FRAME FLO	OOR R- BAS	SEMENT SLAB R-VALUE		'S-1' 'A-1' 'A-2S' 'B-1' 'B-2S' 'C-1' 1 BR 1 BR 1 BR 2 BR 2 BR 3 BR GARAGE  STUDIO STD FND STD FND STD
DESCRIPTION  REQUIRED (Table 503)  REQUIREMENT  AREA THIS PROBLES  MODIFICATION BLDG TYPE 1 BLDG TYPE  BLDG TYPE 1 BLDG TYPE	DEFEDENCE	1A NR 0.75	SHGC         R-VALUE           0.25         30		13 WALL	0 0	0	STUDIO STD END STD
W/GARAGE W/GARA	RAGE W/GARAGE	PROVIDED 0.40 N/A	0.30 38	13 N/A N/A 1	19	N/A N/A	N/A	NSF AREA 566 774 866 1,024 1,115 1,197
CONSTRUCTION TYPE V(A) TYPE V(A) TYPE V(A) TYPE V YPE  USE / OCCUPANCY R-2/U R-2/U	TABLE 303		EL OBIDA BROD	OUCT APPROVAL CHECKLIST -				GSF AREA 594 901 901 1,158 1,158 1,335  NSF Area is the conditioned space within exterior and common walls - to face of
IRE RATING 1 HR 1 HR 1 HR 1 H		_	[FBC 2017] (APA					Definitions  Gypsum Board (Balcony Excluded)  GSF Area is the conditioned space including exterior and common walls - to
OCUPANCY 1 HR 1 HR 1 HR 1 H	HR 1 HR TABLE 508.3.3		CATEGORY / SUBCATEGORY	MANUFACTURER PRODUCT DESCRIPTION	DESIGN PRESSURE	APPROVAL EXP	RATION DATE	exterior face of exterior wall or common wall centerline - Balcony Included
SPRINKLER         NFPA 13R         NFPA 13R         NFPA 13R         NFPA 1           EVEL 1         12,000 SF         21,000 SF         8,178 SF         8,976		NOTES:	A. EXTERIOR DOORS	III/III III/III III III III III III III	+/-	NUMBER(S)		TABLE 402.4.2 AIR BARRIER AND INSULATION INSPECTION COMPONENT CRITERIA
EVEL 2 12,000 SF 21,000 SF 10,494 SF 11,372		1) OCCUPANCY SEPARATION AT DWELLING UNITS PER SECTION 439 -> 709 (VERTICAL-WALLS) & 712 (HORIZONTAL-	SWINGING - GLASS	THERMA-TRU CO. PROFILES	+/- 47	FL 20461 R4 1	2/31/2021	COMPONENT CRITERIA  Exterior thermal envelope insulation for framed walls is installed in substantial
EVEL 3 12,000 SF 21,000 SF 9,464 SF 9,636		FLOORS) = 1 HR	SWINGING - FLUSH	THERMA-TRU CO. PROFILES  CLOPAY BLDG WINDCODE WE CARACE DOOR	+/- 47		2/31/2021	Air barrier and thermal barrier  Contact and continuous alignment with building envelope air barrier.  Breaks or joints in the air barrier are filled or repaired.
GARAGE - (U) 3,000 SF 2,316 SF 2,396  OTAL BLDG AREA 36,000 SF 63,000 SF 30,452 SF 32,380	= 4,118 SF	2) HALLWAY = 0.2 x 40 OCCUPANTS = 8" < 44" (MIN. WIDTH) 1020.2 Exception 2:Thirty-six inches (914	SECTIONAL	PRODUCTS CO. WINDCODE W8 GARAGE DOOR	+46 / -50	FL 5684.6 1	2/31/2038	Air-permeable insulation is not used as a sealing material.  Air-permeable insulation is inside of an air barrier.  Air barrier in any dropped ceiling/soffit is substantially aligned with insulation
TOTAL BLDG AREA 36,000 SF 63,000 SF 30,452 SF 32,380 MEZZ/LOFT INCI NO NO		mm)- With a required occupant capacity of less than 50.	B. WINDOWS SINGLE HUNG	CUSTOM WINDOW 8100 SINGLE HUNG SH-3050E	+67/-75	FL 5823.1-R8 0	7/21/2020	Ceiling/attic and any gaps are sealed. Attic access (except unvented attic), knee wall door, or drop down stair is
IEIGHT LIMIT (S) 3 STORIES		STAIRS = 0.3 x 40 OCCUPANTS = 12" < 44" (MIN. WIDTH)	FIXED	SYSTEMS INC. 8100 SINGLE HUNG SH-3050E CUSTOM WINDOW SYSTEMS INC. 8150 PW	+/-80	FL5823 - R8 0	7/21/2020	Walls  Corners and headers are insulated.  Junction of foundation and sill plate is sealed.
IMIT/PROVIDED (FT)         50'-0"         38'-10"         39'-30'           OCCUPANT LOAD         200 GROSS         42 PERS.         48 PE		1011.2 Exception 1: Stairways serving an occupant load of less than 50 shall have a width of not less than 36 inches (914 mm).	C. PANEL WALL					Windows and doors Space between window/door jambs and framing is sealed.  Rim joists Rim joists are insulated and include an air barrier.
IIN No. OF EXITS 2 2 2	2 3 TABLE 1006.3.1	width of flot less than 50 fileties (914 film).	SOFFITS	JAMES HARDIE HARDIE SOFFIT  JAMES HARDIE HARDIE PLANK SIDING	N/A		5/01/2022	Floors Insulation is installed to maintain permanent contact with underside of subflood decking.
AIN. STAIR WIDTH 44 INCHES 44 INCHES 44 INC			SIDING - SIDING	JAMES HARDIE HARDIE PLANK SIDING  JAMES HARDIE HARDIE PANEL SIDING	N/A N/A		5/01/2022	floors)  Air barrier is installed at any exposed edge of insulation.  Insulation is permanently attached to walls.  Crawl space walls  Exposed earth in unvented crawl spaces is covered with Class I vapor retarder
BUILDING AREA MODIFICATION (SEE BUILDING AF APARTMENTS	REA SCHEDULE ABOVE)		D. ROOFING PRODUCTS					with overlapping joints taped.  Duct shafts, utility penetrations, knee walls and flue shafts opening to exterior
GROSS AREA TABULATION  Building Type 6 - Bldg 7: 21,000 sf = MAX FLOOR CHECK OK			UNDERLAYMENTS	POLYGLASS ICE AND WATER SHIELD	N/A	NOA 17-0614.22	09/13/21	Narrow cavities or unconditioned space are sealed.  Batts in narrow cavities are cut to fit, or narrow cavities are filled by sprayed/blown insulation.
F = 247' + 247' + 72' + 72' = 638' Increase due to Frontage (506.2.1 Frontage Increase)			ASPHALT SHINGLES UNDERLAYMENTS	CERTAINTEED LANDMARK  INTERWRAP RHINOROOF	N/A N/A		2/28/2022	Garage separation  Air sealing is provided between the garage and conditioned spaces.  Pages and light fixtures are air tight. IC rated, and spaled to drawell
W=(L1 x w1 + L2 x w2 + L3 x w3 + L4 w4)/F W=(247' x 30' + 247' x 30' + 72' x 30' + 72' x 17.5')/638'			OFF RIDGE VENT	FLAMCO STANDARD OFF RIDGE VENT	N/A		09/09/2026	Exception-fixtures in conditioned space.  Insulation is placed between outside and pipes. Batt insulation is cut to fit
W = 30 If = [(F/P)25] (30/30)			RIDGE VENT	CERTAINTEED STANDARD RIDGE VENT - 12" UNFILTERED	N/A	NOA 19-0621.01 0	9/23/2024	Plumbing and wiring around wiring and plumbing, or sprayed/blown insulation extends behind piping and wiring.  Showers and tubs on exterior walls have insulation and an air barrier separating.
= [(636'/636')25] (30/30) = [125] (30/30) = .75				<u> </u>				Shower/tub on exterior wall  Electrical/phone box on exterior walls  Air barrier extends behind boxes or air sealed-type boxes are installed.
Maximum Building Area Check								Common wall  Air barrier is installed in common wall between dwelling units.  HVAC register boots  HVAC register boots that penetrate building envelope are sealed to subfloor or
Aa= [At + (NS x If)								Fireplace Fireplace walls include an air barrier.
Aa=[12,000 + (12,000 x .75) =[12,000 + 9,000]								
= 21,000 allowed max building 21,000 * 3 stories = 63,000 allowed per building								
ARCHITECTURAL ABBREVIATIONS								
A BRK. BRICK C	CONTR. CONTRACTOR E F.E	.C. FIRE EXTINGUISHER GL GLAS	s	MAX. MAXIMUM	0			SHLV./SH SHELVING V
ABV ABOVE BTWN BETWEEN ( ACC.FL. ACCESS FLOOR B.U. BUILT-UP ( ACOUST. ACOUSTICAL B.W. BOTH WAYS	COOR. COORDINATE  CONT. CONTINUOUS E EAST FE  CPT. CARPET EA. EACH F.F.  CSMT. CASEMENT E.F. EACH FACE F.F.  C.T. CERAMIC TILE E.J. EXPANSION JOINT FIN	. FINISH FLOOR .C. FIRE HOSE CABINET H	SUM JAN. J.F. JNT.	JANITOR MECH. MECHANICAL JOINT FILLER MEMB. MEMBRANE JOINT MEZZ. MEZZANINE JOIST MFTR MANUFACTURER	OD OH. OPNG.	OVERHEAD OPENING	Q.T. QUARI QTY. QUANT R	SQ. SQUARE VCT VINYL COMPOSITION TILE SR SEMI RECESSED VER. VERIFY
A.D. AREA DRAIN CAB. CABINET  ADJ. ADJACENT CB. / TB. CORKBOARD/  ADJUST. ADJUSTABLE TACKBOARD  AFF ABOVE FINISHED C.B. CATCH BASIN	DBL. DOUBLE ELEV. ELEVATOR F.C	T         FIXTURE         H.B.         HOSE           .         FLOW LINE         H.C.         HOLLOW           R.         FLOOR         H/C         HAND           JOR         FLUORESCENT         HD.         HEAD           J.B.         FACE OF BRICK         HDW.         HARD	E BIBB K OW CORE KIT.	MGR. MANAGER M.H. MANHOLE KITCHEN MIN. MINIMUM MISC. MISCELLANEOUS MLDG. MOLDING	P PART.	PARTITION I		JS STAGG. STAGGERED V.I.F. VERIFY IN FIELD ER BASE STD. STANDARD ECTED CEILING STL. STEEL W STN. STAINED
CEM. CEMENT   FLOOR CER. CERAMIC   CER. CERAMIC   CER. CERAMIC   CER. CERAMIC   CER. CERAMIC   CER. CERCE   CE	DEG. DEGREE EMER. EMERGENCY F.C. DET. DETAIL ENCL. ENCLOSURE F.C. D.F. DRINKING FOUNTAINQ EQUAL F.C. DIA. DIAMETER EQUIP. EQUIPMENT F.F. DIAG DIAGONAL E.W. EACH WAY F.S. DIFF. DIFFUSER E.W.C. ELECTRIC WATER COOLER FT	C.C. FACE OF CONCRETE HDWD. HARD D.F. FACE OF FINISH H.M. HOLLO D.S. FACE OF STUD HORIZ. HORIZ D.S. FIRE RETARDANT H.P. HORS D.S. FULL SIZE HR HOUR D.S. FOOT OR FEET HT. HEIGH	OWOOD L. OW METAL LAB. ZONTAL LAM. SE POWER LAV. R LBL. HT L.H.	LONG OR LENGTH LABORATORY LAMINATE LAVATORY LABEL LEFT HAND  MLWK. MILLWORK MASONRY OPENING MARBLE LAVATORY MARBLE MAR	G PL. VE P.L. P.LAM.	PRE HUNG PLATE PROPERTY LINE PLASTIC LAMINATE PLASTER	RD ROOF RE: REFER REF. REFRIG REINF. REINF REQD. REQUI REV. REVISI	DRAIN         STOR.         STORAGE         W         WEST / WIDE           R TO         STRUCT.         STRUCTURAL         W/         WITH           IGERATOR         SUSP.         SUSPENDED         W.C.         WATER CLOSET           FORCED         SYST.         SYSTEM         W/D         WASHER/DRYER COMBO           WIRED         T         WD.         WOOD           SED / REVISION         WP.         WATER PROOF
ARCH. ARCHITECTURAL CL/ Y CENTER LINE IN CHARLES IN CLOSET IN CLOSET IN CLOSET IN CLEAR IN CONCRETE MASONRY IN CONCRETE MASONR	DIM. DIMENSION EXIST. EXISTING FT DISP. DISPOSAL EXP. JT EXPANSION JOINT FU DIV. DIVIDER EXT. EXTERIOR FU DN. DOWN EXTRU. EXTRUDED DR DOOR DRAP. DRAPERY F.A. FIRE ALARM GA	RR FURRING AND A	L.P.	LINEN LONG LEG VERTICAL MULLION LINE LOW POINT LIGHT LOUVER N.I.C. METAL MULLION NOTAL MULLION NOTAL MULLION M	POL. PR. PREC. PREFAB. PROJ.	POLISHED PAIR PRECAST PREFABRICATED PROJECT PROPERTY	RM ROOM S SOUTH	T & G TONGUE & GROOVE W/O WITHOUT OPENING TEMP GL. TEMPERED GLASS WNF WELDED WIRE FABRIC TER TERRAZZO

N/A N.I.C. NO.

NOM. NOMINAL N.T.S. NOT TO SCALE

NOT IN CONTRACT NUMBER

MASONRY

MATERIAL

SCHED. SECT. S.F.

FIBER BOARD

SOLID CORE

SQUARE FOOT / FEET

SCHEDULE

SECTION

P.T.

PTD. PVC

**PVRS** 

PROPERTY
PRESSURE TREATED
PAINTED

POLYVINYL CHLORIDE PAVERS

BLDG.

BM. BOT. B.O.

BUILDING

BLK/BLK'G BLOCK OR BLOCKING BM. BEAM

BOTTOM BOTTOM OF

CLEAR OPENING

COMMUNICATION

COLUMN

CONCRETE

CONNECTION

CONSTRUCTION

C.O. COL. COMM.

CONC.

CONN.

CONST.

DOWNSPOUT

DISHWASHER

DETAIL

DRAWING

DRAWER

DTL.

DWG.

DWR.

DW

FLOOR DRAIN FIRE DEPARTMENT

CONNECTION FOUNDATION FIRE EXTINGUISHER

F.D. F.D.C.

GALV.

G.B.

G.C.

GEN.

GENERAL

GALVANIZE

GRAB BAR

GENERAL CONTRACTOR

INCHES INSULATION

INTERIOR

INSUL.

MAS.

MATL.

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CODE COMPLIANCE WITH ALL APPLICABLE CODES. DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00851
PROPERTY ADDRESS: 3777 OLD BERRY POINT JOB DESCRIPTION: New construction of a 3 story apartment building that includes 22 units of 3 types and 6 direct entry garage units. The building provides 30,455 GSF

**ISSUE HISTORY** Date 1 11/22/19 SCHEMATIC DESIGN 2 12/06/19 DESIGN DEVELOPMENT 02/28/20 PERMIT REVIEW SET **REVISION HISTORY** No. Date Description

PERMIT REVIEW STAMP

FUGLEBERG KOCH

2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www. fuglebergkoch.com BR569

MICHAEL E. GOVE FLORIDA LICENSE #

THE ROBERT

FT. MYERS, FL

TYPICAL

TYP.


U.O.N.


UNLESS OTHERWISE NOTED


CODE ANALYSIS

A0.02

09/10/2019








#### Bearing Wall Rating — 2 Hr Finish Rating — 66 Min.

Finish Rating — 66 Min. This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as

Canada, a load restriction factor shall be used — See Guide BXUV. or BXUV7. \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or

cUL Certification (such as Canada), respectively



. **Nailheads** — Exposed or covered with joint compound.

2. Joints — Exposed joints covered with joint compound and paper tape. Joint compound and paper tape may be omitted when square edge boards are used. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with the joints reinforced with paper tape. 3. Nails — 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam, 1/4 in. diam heads, and 8d cement coated nails 2-3/8 in. long, 0.113 in. shank diam, 9/32 in. diam heads.

4. **Gypsum Board\*** — 5/8 in. thick, two layers applied either horizontally or vertically. Inner layer attached to studs with the 1-7/8 in. nails spaced 6 in. OC. Outer layer attached to studs over inner layer with the 2-3/8 in. long nails spaced 8 in. OC. Vertical joints located over studs. All joints in face layers staggered with joints in base layers. Joints of each base layer offset with joints of base layer on opposite side.

When used in widths other than 48 in., gypsum board to be installed horizontally When **Steel Framing Members**\* (Item 6, 6A, 6B, or 6C) are used, base layer attached to furring channels with 1 in. long Type S bugle-head steel screws spaced max 24 in. OC; face layer attached with 1-5/8 in, long Type S bugle-head steel screws spaced max 12 in, OC. **AMERICAN GYPSUM CO** — Types AGX-1, M-Glass, AG-C, AGX-11, LightRoc

BEIJING NEW BUILDING MATERIALS PUBLIC LTD CO — Type DBX-1 CABOT MANUFACTURING ULC — Type X, 5/8 Type X, Moisture Resistant Type X, Gypsum Sheathing Type X, Mold & Mildew Resistant Type X and Mold& Mildew Resistant AR Type X, Type Blueglass Exterior Sheathing

CERTAINTEED GYPSUM INC — Types EGRG, GlasRoc, GlasRoc-2, Type C, Type X, Type X-1 CGC INC — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULIX, ULX, USGX, WRC, WRX CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Types LGFC2A, LGFC6A, LGFC-C/A, LGFC-WD, LGLLX, CLLX

GEORGIA-PACIFIC GYPSUM L L C — Types 5, 6, 9, C, DAP, DD, DA, DAPC, DGG, DS, GPFS6. LS, TG-C, Type X, Veneer Plaster Base-Type X, Water Rated-Type X, Sheathing Type-X, Soffit-Type X, GreenGlass Type X, Type LWX, Veneer Plaster Base-Type LWX, Water Rated-Type LWX, Sheathing Type-LWX, Soffit-Type LWX, Type DGLW, Water Rated-Type DGLW, Sheathing Type-DGLW, Soffit-Type DGLW, Type LW2X, Veneer Plaster Base - Type LW2X, Water Rated - Type LW2X, Sheathing - Type LW2X, Soffit - Type LW2X, Type DGL2W, Water Rated - Type DGL2W, Sheathing - Type DGL2W

NATIONAL GYPSUM CO — Types eXP-C, FSK, FSK-C, FSK-G, FSW, FSW-3, FSW-5, FSW-6, FSW-8, FSW-C, FSW-G, FSMR-C, FSL **NATIONAL GYPSUM CO** — Riyadh, Saudi Arabia — Type FR, or WR.

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types C, PG-2, PG-3, PG-3W, PG-4, PG-5, PG-5W, PG-5WS, PG-9, PG-11, PG-C or PGS-WRS PANEL REY S A — Types PRC, PRC2, PRX, RHX, MDX, ETX, GREX, GRIX

SIAM GYPSUM INDUSTRY (SARABURI) CO LTD — Type EX-1 **THAI GYPSUM PRODUCTS PCL** — Type C or Type X UNITED STATES GYPSUM CO — Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULIX, ULX, USGX, WRC, WRX

USG BORAL DRYWALL SFZ LLC — Types C, SCX, USGX USG MEXICO S A DE C V — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX,

■ 4A. Gypsum Board\* — (As an alternate to Item 4) — Nom 3/4 in. thick, installed as described in Item 4. CGC INC — Types AR, IP-AR

UNITED STATES GYPSUM CO — Types AR, IP-AR

USG MEXICO S A DE C V — Types AR, IP-AR 4B. **Gypsum Board\*** — (As an alternate to Items 4 and 4A) — 5/8 in. thick, 2 ft wide, tongue and groove edge, applied horizontally as the outer layer to one side of the assembly. Secured as described in Item 4. Joint covering (Item 2) not required.

CGC INC — Type SHX UNITED STATES GYPSUM CO — Type SHX

USG MEXICO S A DE C V — Type SHX 4C. Gypsum Board\* — (As an alternate to Items 4, 4A or 4B — Not Shown) — For Direct Application to Studs Only- For use on one or both sides of the wall as the base layer or one or both sides of the wall as the face layer. Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field when applied as the base layer. When applied as the face layer screw length to be increased to 2-1/2 in. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 1-1/2 in. wide, max 10 ft long with a max thickness of 0.125 in. placed on the face of studs and attached to the stud with two 1 in. long Type S-12 pan head steel screws, F4j.one at the top of the strip and one at the bottom of the strip. Lead discs or tabs may be used in lieu of or in addition to the lead batten strips or optional at other locations. Max 3/4 in. diam by max 0.125 in. thick lead discs compression fitted

or adhered over steel screw heads or max 1/2 in. by 1-1/4 in. by max 0.125 in. thick lead tabs placed on gypsum boards underneath screw locations prior to the installation of the screws. Lead batten strips to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Fasteners for face layer gypsum panels (Items 4, 4A or 4B) when installed over lead backed board to be min 2-1/2 in. Type S-12 bugle head steel screws spaced as described in Item 4.

**RAY-BAR ENGINEERING CORP** — Type RB-LBG. 4D. **Gypsum Board\*** — As an Alternate to Item 4 — 5/8 in. thick applied either horizontally or vertically. Inner layers fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. Outer layers fastened to framing with 1-7/8 in. long Type W

coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. When used in widths other than 48 in., gypsum board to be installed horizontally. All joints in face layers staggered with joints in base layers. Joints of each base layer offset with joints of base layer on opposite side. AMERICAN GYPSUM CO — Types AGX-1, M-Glass, AG-C, LightRoc

applied vertically and secured as described in Item 4. **GEORGIA-PACIFIC GYPSUM L L C** — Type X ComfortGuard Sound Deadening Gypsum Board 4F. Gypsum Board\* — (As an alternate to Item 4) — Not to be used with item 6, 6A, 6B or 6C. 5/8 in. thick, 4 ft. wide, paper surfaced, applied vertically and secured as described in Item 4.

4E. **Gypsum Board\*** — (As an alternate to Items 4 through 4D) — 5/8 in. thick, 4 ft. wide, paper surfaced

NATIONAL GYPSUM CO — Type SBCB 4G. **Gypsum Board** \* — (As an alternate to Items 4 through 4F) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically and secured as described in Item 4.

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types QuietRock ES 4H. Gypsum Board\* — (As an alternate to Item 4) — Not to be used with item 6, 6A, 6B, or 6C. 5/8 in. thick, 4 ft. wide, paper surfaced, applied vertically or horizontally and secured as described in Item 4. **CERTAINTEED GYPSUM INC** — Type SilentFX

41. **Gypsum Board\*** — (As an alternate to item 4) — 5/8 in. thick, two layers applied either horizontally or vertically. Inner layer attached to studs with 1-1/4 in. long Type W steel screws spaced 8 in. OC. Outer layer attached to studs over inner layer with 2 in. long Type W steel screws spaced 8 in. OC offset 6 in. from base layer. Vertical joints located over studs. Vertical and horizontal joints between inner and outer layers staggered. Outer layer joints covered with joint tape and compound, screwheads covered with joint compound. As an alternate to the joint compound nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of

Classified veneer baseboard. Joints reinforced. Wallboard other than 48 in. wide must be applied horizontally. The SoundBreak XP Type X Gypsum Board is not to be used with Item 6, 6A, 6B, or 6C. NATIONAL GYPSUM CO — Types eXP-C, FSK, FSK-C, FSK-G, FSW, FSW-3, FSW-5, FSW-6, FSW-C, FSW-G, FSMR-C, SoundBreak XP Type X Gypsum Board ■ 4J. Gypsum Board\* — (As an alternate to Items 4) — For Direct Application to Studs Only- For use as the base

layer or as the face layer. Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field when applied as the base layer. When applied as the face layer screw length to be increased to 2-1/2 in. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 10 ft long with a max thickness of 0.140 in. placed on the face of studs and attached to the stud with two 1 in. long Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs, max 5/16 in. diam by max 0.140 in. thick. compression fitted or adhered over the screw heads. Lead batten strips and discs to have a purity of 99.5% meeting the Federal specification QQ-L-201f, Grades "B, C or D". Fasteners for face layer gypsum panels (Items 4, 4A or 4B) when installed over lead backed board to be min 2-1/2 in. Type S-12 bugle head steel screws

spaced as described in Item 4. MAYCO INDUSTRIES INC — "X-Ray Shielded Gypsum"

4K. **Gypsum Board\*** — For use with Item 7 — 5/8 in. thick, two layers applied vertically. Inner layer attached to resilient channels with 1 in. long steel screws spaced 8 in. OC. Outer layer attached to resilient channels over inner layer with 1-5/8 in. long steel screws spaced 8 in. OC. All joints in face layers staggered with joints in base layers. Joints of each base layer offset with joints of base layer on opposite side. Insulation, Items 8 or 9 is required. **AMERICAN GYPSUM CO** — Types AGX-1, M-Glass, AG-C, AGX-11

4L. **Gypsum Board\*** — (As an alternate to Items 4) — For Direct Application to Studs Only- For use as the base layer or as the face layer. Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field when applied as the base layer. When applied as the face layer screw length to be increased to 2-1/2 in. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 8 ft long with a max thickness of 0.14 in. placed on the face of studs and attached to the stud with construction adhesive and two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs, nominal 3/8 in. diam by max 0.085 in. thick. compression fitted or adhered over the screw heads. Lead batten strips and discs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Fasteners for face layer gypsum panels (Items 4, 4A or 4B) when installed over lead backed board to be min 2-1/2 in. Type S-12 bugle head steel screws spaced as described in Item

RADIATION PROTECTION PRODUCTS INC — Type RPP - Lead Lined Drywall 4M. **Gypsum Board\*** — (As an alternate to Item 4) — 5/8 in. thick, 4 ft. wide, two layers applied vertically with vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Secured as described in Item 4. **CERTAINTEED GYPSUM INC** — 5/8" Easi-Lite Type X 4N. **Gypsum Board\*** — (As an alternate to 5/8 in. Type FSW in Items 4 or 4I) — Nom. 5/16 in. thick gypsum panels applied vertically or horizontally. Two layers of 5/16 in. for every single layer of 5/8 in. gypsum board described in Item 4 or 4l. Horizontal joints on the same side need not be staggered. Inner layer of each double 5/16 in. layer attached

with fasteners, as described in item 4 or 4l, spaced 24 in. OC. Outer layer of each double 5/16 in. layer attached per Item 4 or 41. NATIONAL GYPSUM CO — Type FSW

40. Wall and Partition Facings and Accessories\* — (As an alternate to Items 4 through 4N) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically and secured as described in Item 4. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock 527

4P. **Gypsum Board\*** — (As an alternate to Item 4) — 5/8 in. thick, two layers applied either horizontally or vertically. Inner layer attached to studs with 1-1/4 in. long Type W steel screws spaced 10 in. OC with the last two screws 4 and 1 in. from the edges of the board. Outer layer attached to studs over inner layer with 1-7/8 in. long Type W steel screws spaced 10 in. OC offset 5 in. from base layer with the last two screws 4 and 1 in. from the edges of the board. Vertical joints located over studs. Vertical and horizontal joints between inner and outer layers staggered. Outer layer joints covered with joint tape and compound, screwheads covered with joint compound. When used in widths other

than 48 in.. gypsum panels are to be installed horizontally. CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC6A, Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type LGLLX

4Q. **Gypsum Board\*** — (As an alternate to Item 4. For use with Item 13) — Any 5/8 in. thick, 4 ft. wide, Gypsum Board UL Classified for Fire Resistance (CKNX) eligible for use in Design Nos. U305 and L501 or G512. Two layers, applied either horizontally or vertically, and screwed to studs with 1-5/8 in. long Type W coarse thread steel screws at 8 in. OC at perimeter and in the field with the last two screws 4 and 3/4 in. from the edges of the board when applied as the base layer. For the face layer, screw length to be increased to 2-1/2 in. All joints in face layers staggered with joints in base layers. When used in widths other than 48 in., gypsum panels are to be installed horizontally. 4R. **Gypsum Board\*** — As an Alternate to Item 4 — 5/8 in. thick applied either horizontally or vertically. Inner layers fastened to framing with 1-1/4 in, long Type W coarse thread gypsum panel steel screws spaced a max 8 in, OC, with last screw 1 in. from edge of board. Outer layers fastened to framing with 1-7/8 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. When used in widths other than 48 in., gypsum board to be installed horizontally. All joints in face layers staggered with joints in base layers. Joints of each base layer offset with joints of base layer on opposite side. CERTAINTEED GYPSUM INC — Types EGRG, GlasRoc, GlasRoc-2, Type C, Type X, Type X-1, Easi-Lite Type X,

4S. Gypsum Board\* — (As an alternate to Item 4. For use with Item 13A) — 5/8 in. thick, two layers applied vertically. Inner layer attached to studs with the 1-7/8 in. nails spaced 6 in. OC. Outer layer attached to studs over inner layer with the 2-3/8 in. long nails spaced 8 in. OC. Vertical joints located over studs. All joints in face layers staggered with joints in base layers. Joints of each base layer offset with joints of base layer on opposite side.

UNITED STATES GYPSUM CO — Type SCX 5. **Molded Plastic\*** — Not Shown, Optional — Solid vinyl siding mechanically secured over the outer layer to framing members in accordance with manufacturer's recommended installation details. ALSIDE, DIV OF ASSOCIATED MATERIALS INC

VYTEC CORP 6. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as described

GENTEK BUILDING PRODUCTS LTD

A. Furring Channels — Formed of No. 25 MSG galv steel. 2-9/16 in. or 2-23/32 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. As an alternate, ends of adjoining channels may be overlapped 6 in, and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Wallboard attached to furring channels as described in Item 4. B. Steel Framing Members\* — Used to attach furring channels (Item 6a) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center grommet. Furring channels are friction fitted into clips. RSIC-1 clip for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) clip for use with 2-23/32 in. wide furring channels. PAC INTERNATIONAL L C — Types RSIC-1, RSIC-1 (2.75)

6A. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as

described below: A. Furring Channels — Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. Gypsum board attached to furring channels as described in Item 4.

B. Steel Framing Members\* — Used to attach furring channels (Item 6Aa) to studs. Clips spaced 48 in. OC., and secured to studs with 2 in. coarse drywall screw with 1 in. diam washer through the center hole. Furring channels are friction fitted into clips.

**STUDCO BUILDING SYSTEMS** — RESILMOUNT Sound Isolation Clips - Type A237R 6B. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below

A. Furring Channels — Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to stude as described in Item 6Bb. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. Gypsum board attached to furring channels as described in Item 4. B. Steel Framing Members\* — Used to attach furring channels (Item 6Ba) to studs. Clips spaced 48 in.

OC., and secured to studs with 2-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips. **REGUPOL AMERICA** — Type SonusClip

6C. Steel Framing Members\* — (Optional, Not Shown) —Resilient channels and Steel Framing Members as

described below: a. Resilient Channels — Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and secured in place with two No. 8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 in. from the center of the overlap. Gypsum board attached to resilient channels as described in Item 4. b. Steel Framing Members\* — Used to attach resilient channels (Item 6Ca) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Resilient

channels are secured to clips with one No. 10 x 1/2 in. pan-head self-drilling screw. **KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip 7. Furring Channel — Optional — Not Shown — For use on one side of the wall with Item 4K — Resilient channels, 25 MSG galv steel, spaced vertically 24 in. OC, flange portion screw attached to one side of studs with 1-1/4 in. long diamond shaped point, double lead Phillips head steel screws. When resilient channels are used, insulation, Item 8 or

8. Batts and Blankets\* — Required for use with resilient channels, Item 7, min. 3 in. thick mineral wool batts, placed to fill interior of wall, attached to the nom 4 in. face of the studs with staples placed 24 in. OC. **ROCKWOOL** — Type SAFEnSOUND

**THERMAFIBER INC** — Type SAFB, SAFB FF 9. Batts and Blankets\* — (As an alternate to Item 8) — Min. 3 in. thick glass fiber batts bearing the UL Classification Marking as to Surface Burning and/or Fire Resistance, friction-fitted to fill the stud cavities. See Batts and Blankets (BKNV or BZJZ) Categories for names of Classified companies 9A. Fiber, Sprayed\* — (Optional) — As an alternate to Batts and Blankets (Item 8), Required for use with resilient

channels, Item 7, Not for use with Item 6, 6A, 6B, or 6C. — Spray applied mineral wool insulation. The fiber is applied with adhesive, at a minimum density of 4.0 pcf, to completely fill the enclosed cavity in accordance with the application instructions supplied with the product. See Fiber, Sprayed (CCAZ). AMERICAN ROCKWOOL MANUFACTURING, LLC — Type Rockwool Premium Plus

10. Wall and Partition Facings and Accessories\* — (Optional, Not Shown) — Nominal 1/2 in. thick, 4 ft wide panels, for optional use as an additional layer on one or both sides of the assembly. Panels attached in accordance with manufacturer's recommendations. When the QR-500 or QR-510 panel is installed between the wood framing and the UL Classified gypsum board, the required UL Classified gypsum board layer(s) is/are to be installed as indicated as to fastener type and spacing, except that the required fastener length shall be increased by a minimum of 1/2 in. Not evaluated or intended as a substitute for the required layer(s) of UL Classified Gypsum Board. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock QR-500 or QR-510 11. Cementitious Backer Units\* — (Optional Item Not Shown — For Use On Face Of 2 Hr Systems With All

cement board screws of adequate length to penetrate stud by a minimum of 3/8 in. for steel framing members, and a minimum of 3/4 in. for wood framing members spaced a max of 8 in. OC. NATIONAL GYPSUM CO — Type DuraBacker, PermaBase, DuraBacker Plus, or PermaBase Plus 12. Wall and Partition Facings and Accessories\* — (Optional, Not Shown) - When the Wall Assembly is used as an External Wall, on the External side of the wall one of the following Wall and Partition and Facing Accessories may

Standard Items Required) — 7/16 in., 1/2 in., 5/8 in., 3/4 in. or 1 in. thick, min. 32 in. wide. Applied horizontally or

vertically with vertical joints centered over studs. Face layer fastened over gypsum board to studs and runners with

be used, refer to items (A) to (C) below. A. Non Insulated system with metal channels — Install moisture barrier over the Gypsum Board Item 4 and Install Acry Metal Channels vertically at a horizontal spacing not greater than 24 inches OC., over the moisture barrier. Acry Metal Channels attached through the moisture barrier and the Gypsum Board to the Wood Studs using fasteners specified by the manufacturer and fasteners spaced max., 24 in. OC. Install Acrytec Panels on Acry Metal Channels using 1-1/4" long corrosion coated stainless steel screws spaced at a max spacing of 24 inches OC, along with manufacturer's approved adhesive (3M 540 or Tremco Vulcum 116). Adhesive to be applied in a zigzag pattern along every channel. Joint treatment in between panels shall be Tremco illmod 600 pre compressed polyurethane foam

B. Insulated system with metal channels — Install moisture barrier over the Gypsum Board Item 4. Install galvanized Z girt channels specified by the manufacturer over the moisture barrier and the Gypsum Board Item 4. Z girt channels to be installed horizontally at a max. spacing of 24" OC. Z girt channels attached through the Gypsum Board and the moisture barrier to the wood studs with screws provided by the manufacturer at a max spacing of 24 inches OC. Install mineral wool insulation between the Z girts. Maximum thickness of mineral wool insulation not to exceed 6 in. As per manufacturer's instructions install

Acry Metal Channels vertically over the Z girts at a max horizontal spacing of 24 in. OC. Acrytec Panels installed on Acry channel with 1-1/4" long corrosion coated stainless steel screws at a max spacing of 24 in. OC, along with manufacturers approved adhesive (3M 540 or Tremco Vulcum 116). Adhesive to be applied in a zigzag pattern along every channel. Joint treatment in between panels to be Tremco illmod 600 pre compressed polyurethane foam sealant. C. Non insulated wood strapping system — Install moisture barrier over the Gypsum Board Item 4 and

Install 1" x 3" wood strapping vertically at a horizontal spacing not greater than 24 inches OC., over the moisture barrier. 1" x 3" wood strapping attached through the moisture barrier and the Gypsum Board to the Wood studs using fasteners specified by the manufacturer and fasteners spaced max., 24 in. OC. Acrytec Panels to be installed on the 1" x 3" wood strapping using manufacturers approved stainless steel fasteners spaced at maximum 24 inches OC along with Tremco Vulcum 116 adhesive applied in a zigzag pattern along every wood strap. Joint treatment in between panels to be Tremco illmod 600 pre compressed polyurethane foam sealant.

D. Insulated Wood Strapping System — Install moisture barrier over the Gypsum Board Item 4. Install Extruded Polystyrene Insulation over moisture barrier and the Gypsum Board Item 4, max thickness of insulation not to exceed 4 inches. Install 1" x 3" wood strapping vertically at a horizontal spacing not greater than 24 inches OC. Wood strapping attached through the Insulation, the Gypsum Board and moisture barrier to the Wood Studs using fasteners specified by the manufacturer and fasteners spaced max. 24 in. OC. Acrytec Panels to be installed over the wood strapping using manufacturers approved stainless steel fasteners at a max spacing of 24 in. OC and Tremco Vulcum 116 adhesive applied in a zigzag pattern along every wood strap. Joint treatment in between panels to be Tremco illmod 600 pre compressed polyurethane foam sealant.

**ACRYTEC PANEL INDUSTRIES** — Nominal 5/8 inch thick Acrytec Panel. 13. Foamed Plastic\* — (Optional, Not Shown - For use with Item 4Q) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling stud cavity.

SES FOAM INC — Nexseal™ 2.0 or Nexseal™ 2.0 LE Spray Foam and Sucraseal Spray Foam. For use in Bearing and Non-Load Bearing Walls. 13A. Foamed Plastic\* — (Optional, Not Shown - For use with Item 4S) — Spray applied, foamed plastic insulation, to completely filling stud cavity. GACO WESTERN L L C — Types GacoEZSpray F4500, GacoProFill FR6500R, Gaco 052N, GacoOnePass F1850.

GacoOnePass Low GWP F1880, and Gaco WallFoam 183M. 14. Foamed Plastic\* — (Optional, Not Shown - For use over Gypsum Board, Item 4) - Polyisocyanurate foamed plastic boards, any thickness applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in accordance with the

"Xci Foil (Class A)", "Xci CG", "Xci Foil", "Xci CG NH", "Xci Foil NH" 15. Building Units\* — (Optional, Not Shown - For use over Gypsum Board, Item 4) Polyisocyanurate composite foamed plastic boards, any thickness, applied vertically with vertical joints located over studs. May be used with Molded Plastic, Item 5 or any exterior facing, as authorized by the Authority Having Jurisdiction and installed in

HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci Class A", "Xci 286",

manufacturer's installation instructions.

accordance with the manufacturer's installation instructions. HUNTER PANELS, A DIVISION OF CARLISLE CONSTRUCTION MATERIALS, LLC — "Xci NB", "Xci Ply"

Last Updated on 2020-02-04


### Design No. U341 February 05, 2020

Bearing Wall Rating — 1 Hr

Finish Rating — Min 20 min.

This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as Canada, a load restriction factor shall be used — See Guide BXUV or BXUV7

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or



HORIZONTAL SECTION

1. Wood Studs — Nom 2 by 4 in., spaced 24 in. OC max. Cross braced at mid-height and effectively firestopped at top and bottom of wall. No min. air space between stud rows except to accommodate

attachment of sheathing, where required. See items 4 and 5. 2. Gypsum Board\* — Any 5/8 in. thick UL Classified Gypsum Board that is eligible for use in Design Nos. L501, G512 or U305. Nom 5/8 in. thick 4 ft wide. Gypsum board applied horizontally or vertically, unless specified below, and nailed to studs and bearing plates 7 in. OC with 6d cement coated nails, 1-7/8 in. long, 0.0915 in. shank diam and 1/4 in. diam head. As an alternate, No. 6 bugle head drywall screws, 1-7/8 in. long, may be substituted for the 6d cement coated nails.

When Steel Framing Members\* (Item 6-6C) are used, wallboard attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC. When used in widths other than 48 in., gypsum board to be installed horizontally.

AMERICAN GYPSUM CO — CKNX.R14196 BEIJING NEW BUILDING MATERIALS PUBLIC LTD CO — CKNX.R19374 **CABOT MANUFACTURING ULC** — CKNX.R25370

**CERTAINTEED GYPSUM INC** — CKNX.R3660 CGC INC — CKNX.R19751 CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — CKNX.R18482 **GEORGIA-PACIFIC GYPSUM L L C** — CKNX.R2717 **LOADMASTER SYSTEMS INC** — CKNX.R11809

NATIONAL GYPSUM CO — CKNX.R3501 PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — CKNX.R7094 PANEL REY S A — CKNX.R21796 **SIAM GYPSUM INDUSTRY (SARABURI) CO LTD** — CKNX.R19262 **THAI GYPSUM PRODUCTS PCL** — CKNX.R27517 **UNITED STATES GYPSUM CO** — CKNX.R1319

**USG BORAL DRYWALL SFZ LLC** — CKNX.R38438

**USG BORAL DRYWALL SFZ LLC** — CKNX.R38438 **USG MEXICO S A DE C V** — CKNX.R16089 2A. **Gypsum Board\*** — (As an alternate to Item 2, not shown) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically to studs and bearing plates on one side of the assembly with 1-5/8 in. long Type S screws spaced 12 in. OC at perimeter of panels and 8 in. OC in the field. Horizontal joints of vertically applied panels need not be backed by studs. Panel joints covered with paper tape and two layers of joint compound. Screwheads covered with two layers of joint compound. Batts and Blankets placed in stud cavity as

described in Item 5C. Not evaluated for use with Steel Framing Members, Furring Channels or Fiber, PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock QR-530 (finish rating 2B. Gypsum Board\* — (As an alternate to Item 2, not shown) — Any 5/8 in. thick gypsum panels that are eligible for use in Design Nos. L501, G512 or U305, supplied by the Classified companies listed below shown in the Gypsum Board\* (CKNX) category. Applied horizontally or vertically and attached to studs and bearing plates with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. When used in widths other than 48 in., gypsum board to be installed horizontally. **UNITED STATES GYPSUM CO** 

USG MEXICO S A DE C V 2C. **Gypsum Board\*** — (As an alternate to Item 2, Not Shown) — 5/8 in. thick gypsum panels applied horizontally or

FSK-C, Type FSW-C, Type FSMR-C, Type FSW-6, Type FSL

**USG BORAL DRYWALL SFZ LLC** 

vertically and attached to studs and bearing plates with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. When used in widths other than 48 in., gypsum board to be installed horizontally AMERICAN GYPSUM CO — Types AGX-1, M-Glass, AG-C, LightRoc **CERTAINTEED GYPSUM INC** — Type C, Type X or Type X-1

NATIONAL GYPSUM CO — Type FSK, Type FSK-G, Type FSW, Type FSW-3, Type FSW-5, Type FSW-G, Type

**THAI GYPSUM PRODUCTS PCL** — Type C or Type X 2D. **Gypsum Board\*** — (As an alternate to Items 2, 2A, 2B and 2C) — 5/8 in. thick gypsum panels, with square edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last 2 screws 1 and 4 in. from edge of board or nailed as described in Item 2. When used in widths of other than 48 in., gypsum boards are to be installed horizontally. **GEORGIA-PACIFIC GYPSUM L L C** — GreenGlass Type X, Type DGG.

2E. **Gypsum Board\*** — (As an alternate to Items 2 through 2D) — 5/8 in. thick, 4 ft. wide, paper surfaced applied vertically only and secured as described in Item 2. **GEORGIA-PACIFIC GYPSUM L L C** — Type X ComfortGuard Sound Deadening Gypsum Board. 2F. Gypsum Board\* — (As an alternate to Items 2 through 2E) - Installed as described in Item 2. 5/8 in. thick, 4 ft.

wide, paper surfaced, applied vertically only and fastened to the studs and plates with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 1/4 in. diam heads, 7 in. OC. Not for use with item #6. NATIONAL GYPSUM CO — Type SBWB

2G. **Gypsum Board\*** — (As an alternate to Items 2 through 2F) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically and secured as described in Item 2.

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types QuietRock ES. 2H. **Gypsum Board\*** — (As an alternate to Items 2 through 2G) — Installed as described in Item 2. 5/8 in. thick, 4 ft. wide, paper surfaced, applied vertically or horizontally fastened to the studs and plates with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. **CERTAINTEED GYPSUM INC** — Type SilentFX

21. Wall and Partition Facings and Accessories\* — (As an alternate to Items 2 through 2H) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically and secured as described in Item 2. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock 527. 2J. Gypsum Board\* — (As an alternate to 5/8 in. Type FSW in Item 2) — 2 layers nom. 5/16 in. thick gypsum

panels applied vertically or horizontally. Horizontal joints on the same side need not be staggered. Inner layer attached with fasteners, as described in item 2, spaced 24 in. OC. Outer layer attached per Item 2. **NATIONAL GYPSUM CO** — Type FSW. 2K. **Gypsum Board\*** — (As an alternate to Item 2) — 5/8 in. thick gypsum panels, with beveled, square, or tapered

edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread dypsum panel steel screws spaced a maximum 10 in. OC with the last two screws 4 and 1 in. from the edges of the board. When used in widths other than 48 in., gypsum panels are to be installed horizontally. CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC6A (finish rating 21 min), Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type LGLLX

3. **Joints and Nailheads** — Gypsum board joints of outer layer covered with tape and joint compound. Nail heads of outer layer covered with joint compound. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with joints reinforced with paper tape. 4. Sheathing — (Optional) — Septum may be sheathed with min 7/16 in. thick wood structural panels min grade "C-D" or "Sheathing" or min 1/2 in. thick **Mineral and Fiber Boards\***.

See Mineral and Fiber Boards (CERZ) category for names of Classified companies. 5. Batts and Blankets\* — 3-1/2 in. max thickness glass or mineral fiber batt insulation. Optional when sheathing (Item 4) is used on both halves of wall.

See Batts and Blankets (BZJZ) category for list of Classified companies. 5A. Fiber, Sprayed\* — As an alternate to Batts and Blankets (Item 5) — Spray applied cellulose material. The fiber is applied with water to completely fill the enclosed cavity in accordance with the application instructions supplied with the product with a nominal dry density of 2.7 lb/ft3. Alternate Application Method: The fiber is applied without water or adhesive at a nominal dry density of 3.5 lb/ft<sup>3</sup>, in accordance with the application instructions supplied with the

**U S GREENFIBER L L C** — INS735, INS745 and INS750LD for use with wet or dry application. INS515LD, INS541LD, INS735, INS765LD, and INS773LD are to be used for dry application only. 5B. Fiber, Sprayed\* — As an alternate to Batts and Blankets (Item 5) when Sheathing (Item 4) is used on both halves of wall - Spray applied cellulose insulation material. The fiber is applied with water to interior surfaces in accordance with the application instructions supplied with the product. Applied to completely fill the enclosed cavity. Minimum dry density of 4.3 pounds per cubic ft.

**NU-WOOL CO INC** — Cellulose Insulation 5C. Batts and Blankets\* — (Required for use with Wall and Partition Facings and Accessories, Item 2A. Use of Sheathing, Item 4, does not nullify requirement of Item 5C for use with Item 2A) — Glass fiber insulation, nom 3-1/2 in. thick, min. density of 0.80 pcf, with a flame spread of 25 or less and a smoke developed of 50 or less, frictionfitted to completely fill the stud cavities. See Batts and Blankets Category (BKNV) for names of manufacturers. 5D. Fiber, Sprayed\* — As an alternate to Batts and Blankets (Item 5) and Item 5A when Sheathing (Item 4) is used on both halves of wall - Spray applied cellulose fiber. The fiber is applied with water to completely fill the enclosed cavity in accordance with the application instructions supplied with the product. The minimum dry density shall be

4.30 lbs/ft<sup>3</sup>. INTERNATIONAL CELLULOSE CORP — Celbar-RL

5E. Fiber, Sprayed\* — As an alternate to Batts and Blankets (Item 5) - Spray-applied cellulose material. The fiber is applied with water to completely fill the enclosed cavity in accordance with the application instructions supplied with the product. To facilitate the installation of the material, any thin, woven or non-woven netting may be attached by any means possible to the outer face the studs. The material shall reach equilibrium moisture content before the installation of materials on either face of the studs. The minimum dry density shall be 5.79 lbs/ft<sup>3</sup>.  ${\bf APPLEGATE\ HOLDINGS\ L\ L\ C} - {\bf Applegate\ Advanced\ Stabilized\ Cellulose\ Insulation}$ 

6. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below:

A. Furring Channels — Formed of No. 25 MSG galv steel. 2-9/16 in. or 2-23/32 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Wallboard attached to furring channels as described in Item

B. Steel Framing Members\* — Used to attach furring channels (Item a) to studs (Item 1) . Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center grommet. Furring channels are friction fitted into clips. RSIC-1 clip for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) clip for use with 2-23/32 in. wide furring channels. PAC INTERNATIONAL L L C — Types RSIC-1, RSIC-1 (2.75).

6A. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below:

a. Furring Channels — Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Gypsum board attached to furring channels as described in Item 2. b. **Steel Framing Members\*** — Used to attach furring channels (Item a) to studs. Clips spaced 48 in. OC. Genie clips secured to studs with No. 8 x 1-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips. PLITEQ INC — Type Genie Clip

6B. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below:

a. **Furring Channels** — Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. Gypsum board attached to furring channels as described in Item 2 b. **Steel Framing Members\*** — Used to attach furring channels (Item 6Ba) to studs. Clips spaced 48 in.

Furring channels are friction fitted into clips. STUDCO BUILDING SYSTEMS — RESILMOUNT Sound Isolation Clips - Type A237R 6C. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below:

A. Furring Channels — Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to study as described in Item 6Cb. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. Gypsum board attached to furring channels as described in Item 2. B. Steel Framing Members\* — Used to attach furring channels (Item 6CA) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Furring

OC., and secured to studs with 2 in. coarse drywall screw with 1 in. diam washer through the center hole.

**REGUPOL AMERICA** — Type SonusClip 6D. Steel Framing Members\* — (Optional, Not Shown) — Resilient channels and Steel Framing Members as

channels are friction fitted into clips

a. Resilient Channels — Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and secured in place with two No. 8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 in. from the center of the overlap. Gypsum board attached to resilient channels as described in Item 2. b. Steel Framing Members\* — Used to attach resilient channels (Item 6Da) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Resilient channels are secured to clips with one No. 10 x 1/2 in, pan-head self-drilling screw. **KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip

2B. 7. Wall and Partition Facings and Accessories\* — (Optional, Not shown) — Nominal 1/2 in. thick, 4 fi wide panels, for optional use as an additional layer on one or both sides of the assembly. Panels attached in accordance with manufacturer's recommendations. When the QR-500 or QR-510 panel is installed between the wood framing and the UL Classified gypsum board, the required UL Classified gypsum board layer(s) is/are to be installed as indicated as to fastener type and spacing, except that the required fastener length shall be increased by a minimum of 1/2 in. Not evaluated or intended as a substitute for the required layer(s)

of UL Classified Gypsum Board. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock QR-500 and QR-510 8. Mineral and Fiber Board\* — ((Optional, Not Shown) — For optional use as an additional layer on one or both sides of wall. Nom 1/2 in. thick, 4 ft wide with long dimension parallel and centered over studs. Attached to framing as described in Item 2. The required UL Classified gypsum board layer(s) is/are to be installed as indicated as to fastener type and spacing, except that the required fastener length shall be increased by a minimum of 1/2 in. Not evaluated or intended as a substitute for the required layer(s) of UL Classified

Gypsum Board. **HOMASOTE CO** — Homasote Type 440-32

9. Non-Bearing Wall Partition Intersection — (Optional) — Two nominal 2 by 4 in. stud or nominal 2 by 6 in. stud nailed together with two 3in. long 10d nails spaced a max. 16 in. OC. vertically and fastened to one side of the minimum 2 by 4 in. stud with 3 in. long 10d nails spaced a max 16 in. OC. vertically. Intersection between partition wood studs to be flush with the 2 by 4 in. studs. The wall partition wood studs are to be framed by with a second 2 by 4 in. wood stud fastened with 3 in. long 10d nails spaced a max. 16 in. OC. vertically. Maximum one non-bearing wall partition intersection per stud cavity. Non-bearing wall partition stud depth shall be at a minimum equal to the depth of the bearing wall.

(Optional, Not Shown) Alternate Construction For Use On One Side Of The Wall. 10. Mineral and Fiber Board\* — For use with Items 10A-10D) —Nom 1/2 in. thick, 4 ft wide with long

dimension parallel and centered over studs. Attached to framing with minimum 1-3/8 in. long ring shanked nails or 1-1/4 in. long Type W steel screws, spaced 12 in. OC along board edges and 24 in. OC in field of board along intermediate framing. Not evaluated or intended as a substitute for the required layer(s) of UL Classified Gypsum Board. **HOMASOTE CO** — Homasote Type 440-32

10A. Glass Fiber Insulation — (For use with Item 10) — 3-1/2 in. thick glass fiber batts bearing the UL Classification Marking as to Surface Burning and/or Fire Resistance, placed to fill the interior of the wall. See Batts and Blankets (BKNV or BZJZ) categories for names of Classified companies. 10B. Batts and Blankets\* — (As an alternate to Item 10B, For use with Item 10), 3 in. thick mineral wool batts, placed to fill interior of wall, attached to the 3-1/2 in. face of the studs with staples placed 24 in. OC. **THERMAFIBER INC** — Type SAFB, SAFB FF

10C. Adhesive — (For use with Item 10) — Construction grade adhesive applied in vertical, serpentine, nominal 3/8 in. wide beads down the length of both vertical edges of Mineral and Fiber Board (Item 14A). 10D. **Gypsum Board\*** — (For use with Item 10) — 5/8 in. thick, 4 ft wide, applied vertically over Mineral and Fiber Board (Item 14A) with vertical joints located anywhere over stud cavities. Secured to mineral and fiber boards with 1-1/2 in. Type G Screws spaced 8 in. OC along edges of each vertical joint and 12 in. OC in intermediate field of the Mineral and Fiber Board (Item 10). Secured to outermost studs and bearing plates with 2 in. long Type S screws spaced 8 in. OC. Gypsum Board joints covered with paper tape and joint compound. Screw heads covered with joint compound. Finish Rating 30 Min.

**AMERICAN GYPSUM CO** — Type AG-C CERTAINTEED GYPSUM INC — Type C CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC-C/A GEORGIA-PACIFIC GYPSUM L L C — Types 5, DAPC, TG-C NATIONAL GYPSUM CO — Types FSK-C, FSW-C

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type PG-C PANEL REY S A — Type PRC THAI GYPSUM PRODUCTS PCL — Type C UNITED STATES GYPSUM CO — Type CTypes C, IP-X2, IPC-AR

USG BORAL DRYWALL SFZ LLC — Type C

USG MEXICO S A DE C V — Types C, IP-X2, IPC-AR \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2020-02-05

ISSUE HISTORY Description 11/22/19 SCHEMATIC DESIGN 12/06/19 DESIGN DEVELOPMENT 02/28/20 PERMIT REVIEW SET REVISION HISTORY Date Description

PERMIT REVIEW STAMP

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO COMPLIANCE WITH ALL APPLICABLE CODES

PROPERTY ADDRESS: 3777 OLD BERRY POINT

OB DESCRIPTION: New construction of a 3 stor

units. The building provid 30,455 GSF

DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00851

FUGLEBERG KOCH

2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595

www.fuglebergkoch.com

MICHAEL E. GOVE

THE ROBERT FT. MYERS, FL

REFERENCE DIRECTORY - WALL SYSTEMS


Bearing Wall Rating — 1 Hr

Finish Rating — See Items 3, 3A, 3D, 3E, 3F, 3G, 3H, 3J and 3L.

STC Rating - 56 (See Item 9)

This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as Canada, a load restriction factor shall be used — See Guide BXUV or BXUV7

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.



1. Wood Studs — Nom 2 by 4 in. spaced 16 in. OC max, effectively firestopped. 2. **Joints and Nail-Heads** — Joints covered with joint compound and paper tape. Joint compound and paper tape may be omitted when square edge boards are used. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with the joints reinforced with paper tape. Nailheads exposed or

covered with joint compound. 3. **Gypsum Board\*** — 5/8 in. thick paper or vinyl surfaced, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. When used in widths other than 48 in., gypsum panels are to be installed horizontally. For an alternate method of attachment of gypsum panels, refer to Items 6 through 6F, Steel Framing

Members\*. When Items 6, 6B, 6C, 6D, 6E, or 6F, Steel Framing Members\*, are used, gypsum panels attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC.

When Item 6A, **Steel Framing Members\***, is used, two layers of gypsum panels attached to furring channels. Base layer attached to furring channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC. Face layer attached to furring channels with 1-5/8 in. long Type S bugle-head steel screws spaced 12 in. OC. All joints in face layers staggered with joints in base layers. One layer of gypsum board attached to opposite side of wood stud without furring channels as described in Item

When Item 7, resilient channels are used, 5/8 in. thick, 4 ft wide gypsum panels applied vertically. Screw attached furring channels with 1 in. long, self-drilling, selftapping Type S or S-12 steel screws spaced 8 in. OC, vertical joints located midway between studs

AMERICAN GYPSUM CO — Types AGX-1(finish rating 23 min.), M-Glass (finish rating 23 min.), Type AGX-11 (finish rating 26 min), Type AGX-12 (finish rating 22 min), Type LightRoc (finish rating 23 min.) or Type AG-C **BEIJING NEW BUILDING MATERIALS PUBLIC LTD CO** — Type DBX-1 (finish

CABOT MANUFACTURING ULC — Type X (finish rating 22 min), 5/8 Type X, Moisture Resistant Type X, Gypsum Sheathing Type X, Mold & Mildew Resistant Type X and Mold & Mildew Resistant AR Type X, Type Blueglass Exterior Sheathing **CERTAINTEED GYPSUM INC** — Type C, Type X or Type X-1 (finish rating 26 min); Type EGRG or GlasRoc (finish rating 23 min), GlasRoc-2, Type Habito (finish rating

CGC INC — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SCX (finish rating 24 min), Type SHX (finish rating 24 min), Type ULX (finish rating 22 min), Type WRC (finish rating 24 min), Type WRX (finish rating 24 min), Type ULIX (finish rating 20 min) CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC6A (finish rating 34 min), Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type

LGLLX (finish rating 21 min), Type CLLX (finish rating 24 min) **GEORGIA-PACIFIC GYPSUM L L C** — Type 5 (finish rating 26 min), Type 6 (finish rating 23 min), Type 9 (finish rating 26 min), Type C (finish rating 26 min), Type DGG (finish rating 20 min), Type GPFS1 (finish rating 20 min), Type GPFS2 (finish rating 20 min), Type GPFS6 (finish rating 26 min), Type DS, Type DAP, Type DD (finish rating 20 min), Type DA, Type DAPC, Type LS (finish rating 23 min), Type X, Veneer Plaster Base - Type X, Water Rated - Type X, Sheathing - Type X, Soffit - Type X, Type LWX (finish rating 22 min), Veneer Plaster Base-Type LWX (finish rating 22 min), Water Rated-Type LWX (finish rating 22 min), Sheathing Type-LWX (finish rating 22 min), Soffit-Type LWX (finish rating 22 min), Type DGLW (finish rating 22 min), Water Rated-Type DGLW (finish rating 22 min), Sheathing Type- DGLW (finish rating 22 min), Soffit-Type DGLW (finish rating 22 min), Type LWX (finish rating 22 min), Type LW2X (finish rating 22 min), Veneer Plaster Base - Type LW2X (finish rating 22 min), Water Rated - Type LW2X (finish rating 22 min), Sheathing - Type LW2X (finish rating 22 min), Soffit - Type LW2X (finish rating 22 min), Type DGL2W (finish rating 22 min), Water Rated - Type DGL2W (finish rating 22 min), Sheathing -

Type DGL2W (finish rating 22 min) **NATIONAL GYPSUM CO** — Type FSK (finish rating 20 min), Type FSK-G (finish rating 20 min), Type FSW (finish rating 20 min), Type FSW-2 (finish rating 24 min), Type FSW-3 (finish rating 20 min), Type FSW-5 (finish rating 22 min), Type FSW-G (finish rating 20 min), Type FSK-C (finish rating 20 min), Type FSW-C (finish rating 20 min), Type FSMR-C, Type FSW-6 (finish rating 20 min), Type FSL (finish rating 24 min), Type FSW-8, Type FSLX (finish rating 21 min).

NATIONAL GYPSUM CO — Riyadh, Saudi Arabia — Type FR, or WR. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types C, PG-2 (finish rating 20 min), PG-3 (finish rating 20 min), Types PG-3W, PG-5W (finish rating 20 min), Type PG-4 (finish rating 20 min), Type PG-6 (finish rating 23 min), Types PG-3WS, PG-5WS, PGS-WRS (finish rating 20 min), Types PG-5, PG-9 (finish rating 26 min), PG-11 PG-13 (Nails increased to 2 in.), or Type PG-C PANEL REY S A — Type GREX, GRIX, PRX, PRC, PRC2; Types RHX, Guard Rey,

MDX, ETX (finish rating 22 min) SIAM GYPSUM INDUSTRY (SARABURI) CO LTD — Type EX-1 (finish rating 26

**THAI GYPSUM PRODUCTS PCL** — Type C, Type X (finish rating 26 min) **UNITED STATES GYPSUM CO** — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type FRX-G (finish rating 29 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), Type SCX (finish rating 24 min), Type SGX (finish rating 24 min), Type ULX (finish rating 22 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type ULIX (finish rating 20

**USG BORAL DRYWALL SFZ LLC** — Type SGX (finish rating 24 min). **USG MEXICO S A DE C V** — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), SCX (finish rating 24 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type ULX (finish rating 22 min)

3A. **Gypsum Board\*** — (As an alternate to Item 3) — 5/8 in. thick gypsum panels, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. When used in widths of other than 48 in., gypsum boards are to be installed horizontally. AMERICAN GYPSUM CO — Types AGX-1 (finish rating 25 min.), M-Glass (finish rating 25 min.), AG-C (finish rating 25 min.), LighttRoc (finish rating 25 min.) **CERTAINTEED GYPSUM INC** — Type C, Type X or Type X-1 (finish rating 26 min)

CGC INC — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SCX (finish rating 24 min), Type SHX (finish rating 24 min), Type WRC (finish rating 24 min), Type WRX (finish rating 24 min) **NATIONAL GYPSUM CO** — Type FSW (finish rating 24 min) UNITED STATES GYPSUM CO — Type AR (finish rating 24 min), Type SCX (finish rating 24 min), Type SGX (finish rating 24 min), Type C (finish rating 24 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type IP-X1 (finish rating 24 min),

Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), Type FRX-G (finish rating 24 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min) **USG BORAL DRYWALL SFZ LLC** — Types C, SCX, SGX (finish rating 24 min). **USG MEXICO S A DE C V** — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), Type SCX, Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min)

3B. Gypsum Board\* — (As an alternate to Item 3) — Nom 3/4 in. thick, installed with 1-7/8 in. long cement coated nails as described in Item 3 or 1-3/8 in. long Type W coarse thread gypsum panel steel screws as described in Item 3A. CGC INC — Types AR, IP-AR

UNITED STATES GYPSUM CO — Types AR, IP-AR **USG MEXICO S A DE C V** — Types AR, IP-AR

3C. **Gypsum Board\*** — (As an alternate to Items 3, 3A and 3B) — 5/8 in. thick, 2 ft wide, tongue and groove edge, applied horizontally to one side of the assembly. Installed with 1-7/8 in. long cement coated nails as described in Item 3 or 1-1/4 in. long Type W coarse thread gypsum panel steel screws as described in Item 3A. Joint covering (Item 2) not required. **CGC INC** — Type SHX

**UNITED STATES GYPSUM CO** — Type SHX **USG MEXICO S A DE C V** — Type SHX

3D. **Gypsum Board\*** — (As an alternate to Items 3, 3A, 3B, or 3C — Not Shown) — For Direct Application to Studs Only- Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 1-1/2 in. wide, max 10 ft long with a max thickness of 0.125 in. placed on the face of studs and attached to the stud with two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs or tabs may be used in lieu of or in addition to the lead batten strips or optional at other locations. Max 3/4 in. diam by max 0.125 in. thick lead discs compression fitted or adhered over steel screw heads or max 1/2 in. by 1-1/4 in. by max 0.125 in. thick lead tabs placed on gypsum boards underneath screw locations prior to the installation of the screws. Lead batten strips to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". **RAY-BAR ENGINEERING CORP** — Type RB-LBG (finish rating 24 min) 3E. **Gypsum Board\*** — (As an alternate to Items 3, 3A, 3B, 3C, and 3D) — 5/8 in. thick gypsum panels, with square edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last 2 screws 1 and 4 in. from edge of board or nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. When used in widths of other than 48 in., gypsum boards are to be

installed horizontally. **GEORGIA-PACIFIC GYPSUM L L C** — Type DGG (finish rating 20 min), GreenGlass Type X (finish rating 23 min)

3F. **Gypsum Board\*** — (As an alternate to Items 3, 3A, 3B, 3C, 3D, and 3E) — 5/8 in. glass-mat faced with square edges, applied either horizontally or vertically. Gypsum panels nailed 7 in. OC around the perimeter and in the field with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. Nails shall be placed 1 inch and 3 inch from horizontal joints and 7 inch OC thereafter.

**CGC INC** — Type USGX (finish rating 22 min) **UNITED STATES GYPSUM CO** — Type USGX (finish rating 22 min.) **USG BORAL DRYWALL SFZ LLC** — , Type USGX (finish rating 22 min.) **USG MEXICO S A DE C V** — Type USGX (finish rating 22 min.)

3G. **Gypsum Board\*** — (As an alternate to Items 3 through 3F) — 5/8 in. thick paper surfaced applied vertically. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. **GEORGIA-PACIFIC GYPSUM L L C** — Type X ComfortGuard Sound Deadening

3H. **Gypsum Board\*** — (As an alternate to Items 3) — Not to be used with items 6 or 7. 5/8 in. thick paper surfaced applied vertically only. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads.

NATIONAL GYPSUM CO — Type SBWB 3I. **Gypsum Board\*** — (As an alternate to Items 3 through 3H, Not Shown) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically. Panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. Panel joints

covered with paper tape and two layers of joint compound. Nailheads covered with two layers of joint compound PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock ES (finish rating 20 min)

3J. **Gypsum Board\*** — (As an alternate to Item 3) — Not to be used with items 6 or 7. 5/8 in. thick paper surfaced applied vertically or horizontally. Gypsum panels secured per

**CERTAINTEED GYPSUM INC** — Type SilentFX 3K. **Gypsum Board\*** — (As an alternate to Item 3) — 5/8 in. thick gypsum panels, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a maximum 8 in. OC with the last screw 1 in. from the edge of the board. When used in widths other than 48 in., gypsum panels are to be installed horizontally. **NATIONAL GYPSUM CO** — Type FSK (finish rating 20 min), Type FSK-G (finish rating 20 min), Type FSW (finish rating 20 min), Type FSW-2 (finish rating 24 min), Type FSW-3 (finish rating 20 min), Type FSW-5 (finish rating 22 min), Type FSW-G (finish rating 20 min), Type FSK-C (finish rating 20 min), Type FSW-C (finish rating 20 min), Type FSMR-C, Type FSW-6 (finish rating 20 min), Type FSL (finish rating 24 min). 3L. **Gypsum Board\*** — (As an alternate to Item 3) — For Direct Application to Studs

Only — Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 10 ft long with a max thickness of 0.140 in. placed on the face of studs and attached to the stud with two 1 in. long Type S-8 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs, max 5/16 in. diam by max 0.140 in. thick. compression fitted or adhered over the screw heads. Lead batten strips to have a purity of 99.5% meeting the Federal specification QQ-L-201f, Grades "B, C or D". MAYCO INDUSTRIES INC — "X-Ray Shielded Gypsum"

3M. Gypsum Board\* — (As an alternate to Items 3) — For Direct Application to Studs Only — For use as the base layer or as the face layer. Nom 5/8 in. thick lead backed gypsum panels with beveled, square or tapered edges, applied vertically. Vertical joints centered over studs and staggered min 1 stud cavity on opposite sides of studs. Wallboard secured to studs with 1-5/8 in. long Type W coarse thread gypsum panel steel screws spaced 8 in. OC at perimeter and in the field when applied as the base layer. When applied as the face layer screw length to be increased to 2-1/2 in. Lead batten strips required behind vertical joints of lead backed gypsum wallboard and optional at remaining stud locations. Lead batten strips, min 2 in. wide, max 8 ft long with a max thickness of 0.14 in. placed on the face of studs and attached to the stud with construction adhesive and two 1 in. long Type S-12 pan head steel screws, one at the top of the strip and one at the bottom of the strip. Lead discs, nominal 3/8 in. diam by max 0.085 in. thick. Compression fitted or adhered over the screw heads. Lead batten strips and discs to have a purity of 99.9% meeting the Federal specification QQ-L-201f, Grade "C". Fasteners for face layer gypsum panels (Items 4, 4A or 4B) when installed over lead backed board to be min 2-1/2 in. Type S-12 bugle head steel screws spaced

as described in Item 4. **RADIATION PROTECTION PRODUCTS INC** — Type RPP - Lead Lined Drywall 3N. **Gypsum Board\*** — (As an alternate to Item 3) — 5/8 in. thick, 4 ft. wide, applied horizontally or vertically with vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Secured as described in Item 3 or 3A. **CERTAINTEED GYPSUM INC** — Easi-Lite Type X (finish rating 24 min), Easi-Lite Type

X-2 (finish rating 24 min) 3O. Wall and Partition Facings and Accessories\* — (As an alternate to Item 3, Not Shown) — Nominal 5/8 in. thick, 4 ft wide panels, applied vertically. Panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. Panel joints covered with paper tape and two layers of joint compound. Nailheads covered with two layers of joint compound.

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock 527 (finish rating 24 min).

3P. **Gypsum Board\*** — (As an alternate to Item 3, Not Shown) — Two layers nom. 5/16 in. thick gypsum panels applied vertically or horizontally. Horizontal edge joints and horizontal butt joints on opposite sides of studs need not be staggered or backed by wood studs. Horizontal joints on the same side between face and base layers need not be staggered. Base layer gypsum panels fastened to studs with 1-1/4 in. long drywall nails spaced 8 in. OC. Face layer gypsum panels fastened to study with 1-7/8 in. long drywall nails spaced 8 in. OC starting with a 4" stagger. NATIONAL GYPSUM CO — Type FSW (finish rating 25 min)

3Q. **Gypsum Board\*** — (As an alternate to Item 3) — 5/8 in. thick gypsum panels, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a maximum 10 in. OC with the last two screws 4 and 1 in. from the edges of the board. When used in widths other than 48 in., gypsum panels are to be installed horizontally. CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC6A (finish rating 21 min), Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type LGLLX

3R. Gypsum Board\* — (As an alternate to Item 3. For use with Item 5H) — Any 5/8 in. thick, 4 ft. wide, Gypsum Board listed in Item 3 above. Applied either horizontally or vertically, and screwed to panels with 1-5/8 in. long Type W coarse thread steel screws at 8 in. OC at perimeter and in the field with the last two screws 4 and 3/4 in. from the edges of the board when applied as the base layer. When used in widths other than 48 in., gypsum panels are to be installed horizontally.

3S. **Gypsum Board\*** — 3/4 in. thick paper or vinyl surfaced, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels secured as described in Item 3 with nail length increased to 2 in. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type

3T. Wall and Partition Facings and Accessories\* — (As an alternate to 5/8 in. thick board as outlined in Item 3) — Nominal 1-3/8 in. thick. 4 ft wide panels, applied vertically or horizontally. Fastened with #6 x 2 in. long drywall screws spaced 8 in. OC along the perimeter and 12 in. OC in the field. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type

3U. **Gypsum Board\*** — (As an alternate to Item 3 - For use with Item 5J) — 5/8 in. thick, 4 ft. wide, applied vertically with vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in, diam heads.

**UNITED STATES GYPSUM CO** — Type SCX 4. **Steel Corner Fasteners** — (Optional) — For use at wall corners. Channel shaped, 2 in. long by 1 in. high on the back side with two 1/8 in. wide cleats protruding into the 5/8 in. wide channel, fabricated from 24 gauge galv steel Fasteners applied only to the end or cut edge (not along tapered edges) of the gypsum board, no greater than 2 in. from corner of gypsum board, max spacing 16 in. OC. Nailed to adjacent stud through tab using one No. 6d cement coated nail per fastener. Corners of wall board shall be nailed to top and bottom plate using No. 6d cement coated nails.

5. Batts and Blankets\* — (Optional — Required when Item 6A is used (RC-1)) — Glass fiber or mineral wool insulation. Placed to completely or partially fill the stud cavities. When Item 6A is used, glass fiber or mineral wool insulation shall be friction-fitted to completely fill the stud cavities. **CERTAINTEED CORP** 

JOHNS MANVILLE **KNAUF INSULATION LLC** 

MANSON INSULATION INC **ROCKWOOL** — Types Acoustical Fire Batts and Type AFB, min. density 1.69 pcf / 27.0 kg/m<sup>3</sup>

**ROCKWOOL MALAYSIA SDN BHD** — Type Acoustical Fire Batts ROCK WOOL MANUFACTURING CO — Delta Board **THERMAFIBER INC** — Type SAFB, SAFB FF

5A. **Fiber**, **Sprayed\*** — (Not Shown — Not for use with Item 6) — As an alternate to Batts and Blankets (Item 5) — Spray applied cellulose material. The fiber is applied with water to completely fill the enclosed cavity in accordance with the application instructions supplied with the product with a nominal dry density of 2.7 lb/ft<sup>3</sup>. Alternate Application Method: The fiber is

applied without water or adhesive at a nominal dry density of 3.5 lb/ft<sup>3</sup>, in accordance with the application instructions supplied with the product. When Item 6B is used, Fiber, Sprayed shall be INS735, INS745, INS750LD, INS765LD or INS773LD.

U S GREENFIBER L L C — INS735, INS745 and INS750LD for use with wet or dry application. INS515LD, INS541LD, INS735, INS765LD, and INS773LD are to be used for dry application only 5B. **Fiber**, **Sprayed\*** — (Not Shown - Not for use with Item 6) — As an

alternate to Batts and Blankets (Item 5) - Spray applied cellulose insulation material. The fiber is applied with water to interior surfaces in accordance with the application instructions supplied with the product. Applied to completely fill the enclosed cavity. Minimum dry density of 4.3 pounds per cubic ft. **NU-WOOL CO INC** — Cellulose Insulation

5C. Batts and Blankets\* — Required for use with resilient channels, Item 7, 3 in. thick mineral wool batts, friction-fitted to fill interior of wall. **THERMAFIBER INC** — Type SAFB, SAFB FF

5D. **Glass Fiber Insulation** — (As an alternate to Item 5C) — 3 in. thick glass fiber batts bearing the UL Classification Marking as to Surface Burning and/or Fire Resistance, friction-fitted to fill the interior of the wall. See **Batts and** Blankets (BKNV or BZJZ) Categories for names of Classified companies. 5E. **Batts and Blankets\*** — (Required for use with Wall and Partition Facings and Accessories. Item 3D) — Glass fiber insulation, nom 3-1/2 in, thick, min. density of 0.80 pcf, with a flame spread of 25 or less and a smoke developed of 50 or less, friction-fitted to completely fill the stud cavities. See Batts and Blankets Category (BKNV) for names of manufacturers.

5F. **Fiber, Sprayed\*** — (Optional, Not Shown — Not for use with Items 6, 6A, 6B, 6C, or 6D) — As an alternate to Batts and Blankets (Item 5) and Item 5A -Spray applied granulated mineral fiber material. The fiber is applied with adhesive, at a minimum density of 4.0 pcf, to completely fill the enclosed cavity in accordance with the application instructions supplied with the

product. See **Fiber**, **Sprayed** (CCAZ). AMERICAN ROCKWOOL MANUFACTURING, LLC — Type Rockwool Premium Plus

5G. Fiber, Sprayed\* — (Optional, Not Shown — Not for use with Items 6, 6A, 6B, 6C, or 6D). — As an alternate to Batts and Blankets (Item 5) and Item 5A - Brown Colored Spray applied cellulose fiber. The fiber is applied with water to completely fill the enclosed stud cavity in accordance with the application instructions supplied with the product. The minimum dry density shall be 4.30

INTERNATIONAL CELLULOSE CORP — Celbar-RL 5H. **Foamed Plastic\*** — (Optional -For use with Item 3R) — Spray applied, foamed plastic insulation, at any thickness from partial fill to completely filling

**SES FOAM INC** — Nexseal<sup>™</sup> 2.0 or Nexseal<sup>™</sup> 2.0 LE Spray Foam and Sucraseal Spray Foam.

51. **Fiber, Sprayed\*** — (Not Shown — Not for use with Item 6) — As an alternate to Batts and Blankets (Item 5) - Spray-applied cellulose material. The fiber is applied with water to completely fill the enclosed cavity in accordance with the application instructions supplied with the product. To facilitate the installation of the material, any thin, woven or non-woven netting may be attached by any means possible to the outer face the studs. The material shall reach equilibrium moisture content before the installation of materials on either face of the studs. The minimum dry density shall be 5.79

APPLEGATE HOLDINGS L L C — Applegate Advanced Stabilized Cellulose 5J. **Foamed Plastic\*** — (Optional, Not Shown - For use with Item 3U) —

Spray applied, foamed plastic insulation, to completely filling stud cavity. GACO WESTERN L L C — Types GacoEZSpray F4500, GacoProFill FR6500R, Gaco 052N, GacoOnePass F1850, GacoOnePass Low GWP F1880, and Gaco WallFoam 183M

6. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below: a. Furring Channels — Formed of No. 25 MSG galv steel. 2-9/16 in. or 2-23/32 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to stude as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Gypsum board attached to furring channels as described in Item 3.

b. Steel Framing Members\* — Used to attach furring channels (Item 6a) to studs. Clips spaced 48 in. OC. RSIC-1 and RSIC-1 (2.75) clips secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center grommet. RSIC-V and RSIC-V (2.75) clips secured to studs with No. 8 x 1-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips. RSIC-1 and RSIC-V clips for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) and RSIC-V (2.75) clips for use with 2-23/32 in. wide furring channels. PAC INTERNATIONAL L L C — Types RSIC-1, RSIC-V, RSIC-1

(2.75), RSIC-V (2.75) 6A. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members on one side of studs as described below: a. Furring Channels — Formed of No. 25 MSG galv steel, spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. Batts and Blankets placed in stud cavity as described in

Item 5. Two layers of gypsum board attached to furring channels as described in Item 3. b. **Steel Framing Members\*** — Used to attach furring channels (Item 6Aa) to one side of studs only. Clips spaced 48 in. OC., and secured to studs with two No. 8 x 2-1/2 in. coarse drywall screws, one through the hole at each end of the clip. Furring channels are friction fitted into clips.

**KINETICS NOISE CONTROL INC** — Type Isomax 6B. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels and

Steel Framing Members as described below:

a. Furring Channels — Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to stude as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Gypsum board attached to furring channels as described in

b. **Steel Framing Members\*** — Used to attach furring channels (Item 6Ba) to studs. Clips spaced 48 in. OC. Genie clips secured to studs with No. 8 x 1-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips PLITEQ INC — Type Genie Clip

6C. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels

and Steel Framing Members as described below: a. Furring Channels — Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. Gypsum board attached to furring channels as described in Item 3. b. Steel Framing Members\* — Used to attach furring channels (Item

6Ca) to studs. Clips spaced 48 in. OC., and secured to studs with No. 2 in. coarse drywall screw with 1 in. diam washer through the center hole. Furring channels are friction fitted into clips. **STUDCO BUILDING SYSTEMS** — RESILMOUNT Sound Isolation

Clips - Type A237 or A237R 6D. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels

and Steel Framing Members as described below: a. Furring Channels — Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and secured in place with a double strand of No. 18 AWG twisted steel wire. Gypsum board attached to furring channels as described in Item 3. b. Steel Framing Members\* — Used to attach furring channels (Item 6Da) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Furring

**REGUPOL AMERICA** — Type SonusClip 6E. **Steel Framing Members\*** — (Optional, Not Shown) — Resilient channels

channels are friction fitted into clips.

and Steel Framing Members as described below: a. Resilient Channels — Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped 6 in. and secured in place with two No. 8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 in. from the center of the overlap. Gypsum board attached to resilient channels as described in Item 3. b. Steel Framing Members\* — Used to attach resilient channels (Item 6Ea) to studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Resilient

channels are secured to clips with one No. 10 x 1/2 in. pan-head self-**KEENE BUILDING PRODUCTS CO INC** - Type RC+ Assurance Clip

6F. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels and Steel Framing Members as described below: a. Furring Channels — Formed of No. 25 MSG galv steel. 2-23/32 in. wide by 7/8 in. or 1-1/2 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to stude as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Gypsum board attached to furring channels as described in

b. Steel Framing Members\* — Used to attach furring channels (Item 6Fa) to studs. Clips spaced 48 in. OC. Clips secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center grommet. Furring channels are friction fitted into clips. **CLARKDIETRICH BUILDING SYSTEMS** — Type ClarkDietrich Sound

7. **Furring Channel** — Optional — Not Shown — For use on one side of the wall - Resilient channels, 25 MSG galv steel, spaced vertically 24 in. OC, flange portion screw attached to one side of studs with 1-1/4 in. long diamond shaped point, double lead Phillips head steel screws. When resilient channels are used, insulation, Items 5C or 5D is required. 8. Caulking and Sealants — (Not Shown, Optional) — A bead of acoustical

9. **STC Rating** — The STC Rating of the wall assembly is 56 when it is constructed as described by Items 1 through 6, except: A. Item 2, above — Nailheads Shall be covered with joint compound. B. Item 2, above — Joints As described, shall be covered with fiber tape and

sealant applied around the partition perimeter for sound control.

joint compound. C. Item 5, above — Batts and Blankets\* The cavities formed by the studs shall be friction fit with R-19 unfaced fiberglass insulation batts measuring 6-1/4 in. thick and 15-1/4 in. wide.

D. Item 6, above — Steel Framing Members\* Type RSIC-1 clips shall be used to attach gypsum board to studs on either side of the wall assembly. E. Item 8, above — Caulking and Sealants (Not Shown) A bead of acoustical sealant shall be applied around the partition perimeter for sound control. F. Steel Corner Fasteners (Item 4), Fiber, Sprayed (Items 5A and 5B) and Steel Framing Members (Item 6A), not evaluated as alternatives for obtaining STC

10. Wall and Partition Facings and Accessories\* — (Optional, Not Shown) — Nominal 1/2 in. thick, 4 ft wide panels, for optional use as an additional layer on one or both sides of the assembly. Panels attached in accordance with manufacturer's recommendations. When the QR-500 or QR-510 panel is installed between the wood framing and the UL Classified gypsum board, the required UL Classified gypsum board layer(s) is/are to be installed as indicated as to fastener type and spacing, except that the required fastener length shall be increased by a minimum of 1/2 in. Not evaluated or intended as a substitute for

the required layer(s) of UL Classified Gypsum Board. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock QR-500 and QR-510

11. **Cementitious Backer Units\*** — (Optional Item Not Shown — For Use On Face Of 1 Hr Systems With All Standard Items Required) - 7/16 in., 1/2 in., 5/8 in., 3/4 in. or 1 in. thick, min. 32 in. wide. Applied vertically or horizontally with vertical joints centered over studs. Fastened to studs and runners with cement board screws of adequate length to penetrate stud by a minimum of 3/8 in. for steel framing members, and a minimum of 3/4 in. for wood framing members spaced a max of 8 in. OC. When 4 ft. wide boards are used, horizontal joints

need not be backed by framing **NATIONAL GYPSUM CO** — Type DuraBacker, PermaBase, DuraBacker Plus, or PermaBase Plus

12. Non-Bearing Wall Partition Intersection — (Optional) —Two nominal 2 by 4 in. studs or nominal 2 by 6 in. studs nailed together with two 3 in. long 10d nails spaced a max. 16 in. OC. vertically and fastened to one side of the minimum 2 by 4 in. stud with 3 in. long 10d nails spaced a max. 16 in. OC. vertically. Intersection between partition wood studs to be flush with the 2 by 4 in. studs. The wall partition wood studs are to be framed by with a second 2 by 4 in. wood stud fastened with 3 in. long 10d nails spaced a max. 16 in. OC. vertically. Maximum one non-bearing wall partition intersection per stud cavity. Nonbearing wall partition stud depth shall be at a minimum equal to the depth of the

13. **Mesh Netting** — (Not Shown) — Any thin, woven or non-woven fibrous netting material attached with staples to the outer face of one row of studs to facilitate the installation of the sprayed fiber from the opposite row. 14. Mineral and Fiber Board\* — (Optional, Not Shown) — For optional use as an additional layer on one side of wall. Nom 1/2 in. thick, 4 ft wide with long dimension parallel and centered over studs. Attached to framing with 2 in. long Type W steel screws, spaced 12 in, OC. The required UL Classified gypsum board layer(s) is/are to be installed as indicated as to fastener type and spacing except that the required fastener length shall be increased by a minimum of 1/2 in. Not evaluated or intended as a substitute for the required layer(s) of UL Classified Gypsum Board.

**HOMASOTE CO** — Homasote Type 440-32 14A. Mineral and Fiber Board\* — (Optional, Not Shown) — For use with Items 14B-14E) — For optional use as an additional layer on one side of wall. Nom 1/2 in. thick, 4 ft wide with long dimension parallel and centered over studs. Attached to framing with minimum 1-3/8 in. long ring shanked nails or 1-1/4 in. long Type W steel screws, spaced 12 in. OC along board edges and 24 in. OC in field of board along intermediate framing. Not evaluated or intended as a substitute for the required layer(s) of UL Classified Gypsum Board.

**HOMASOTE CO** — Homasote Type 440-32 14B. **Glass Fiber Insulation** — (For use with Item 14A) — 3-1/2 in. thick glass fiber batts bearing the UL Classification Marking as to Surface Burning and/or Fire Resistance, placed to fill the interior of the wall. See Batts and Blankets (BKNV or BZJZ) categories for names of Classified companies. 14C. **Batts and Blankets\*** — (As an alternate to Item 14B, For use with Item 14A), 3 in. thick mineral wool batts, placed to fill interior of wall, attached to the 3-

1/2 in. face of the studs with staples placed 24 in. OC. **THERMAFIBER INC** — Type SAFB, SAFB FF 14D. **Adhesive** — (For use with Item 14A) — Construction grade adhesive applied in vertical, serpentine, nominal 3/8 in, wide beads down the length of both vertical edges of Mineral and Fiber Board (Item 14A). 14E. **Gypsum Board\*** — (For use with Item 14A) — 5/8 in. thick, 4 ft wide, applied vertically over Mineral and Fiber Board (Item 14A) with vertical joints

located anywhere over stud cavities. Secured to mineral and fiber boards with 1-1/2 in. Type G Screws spaced 8 in. OC along edges of each vertical joint and 12 in. OC in intermediate field of the Mineral and Fiber Board (Item 14A). Secured to outermost studs and bearing plates with 2 in. long Type S screws spaced 8 in. OC. Gypsum Board joints covered with paper tape and joint compound. Screw heads covered with joint compound. Finish Rating 30 Min.

**AMERICAN GYPSUM CO** — Type AG-C **CERTAINTEED GYPSUM INC** — Type C CGC INC — Types C, IP-X2, IPC-AR CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type

I GFC-C/A **GEORGIA-PACIFIC GYPSUM L L C** — Types 5, DAPC, TG-C NATIONAL GYPSUM CO — Types FSK-C, FSW-C PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type PG-C PANEL REY S A — Type PRC

THAI GYPSUM PRODUCTS PCL — Type C UNITED STATES GYPSUM CO — Types C, IP-X2, IPC-AR USG BORAL DRYWALL SFZ LLC — Type C USG MEXICO S A DE C V — Types C, IP-X2, IPC-AR 14F. Mineral and Fiber Board — (Optional, Not Shown) — For optional use as an additional layer on one side of wall - Nom 1/2 in. thick, 4 ft wide, square edge fiber boards applied vertically to study on one side of the wall in between the

wood studs and the UL Classified Gypsum Board (Item 3). Fiber boards installed with 1-1/4 in. long, Type W, bugle head, coarse thread gypsum board screws spaced 12 in. OC max, with the last screws spaced 2 in. and 6 in. from edge of board. Gypsum board (Item 3) installed as indicated as to fastener type and spacing, except that the required fastener length shall be increased by a minimum of 1/2 in. Not evaluated or intended as a substitute for the required layer(s) of UL Classified Gypsum Board.

**BLUE RIDGE FIBERBOARD INC** — SoundStop

Last Updated on 2020-02-04

ISSUE HISTORY Date Description 11/22/19 SCHEMATIC DESIGN 12/06/19 DESIGN DEVELOPMENT 02/28/20 PERMIT REVIEW SET REVISION HISTORY Date Description

PERMIT REVIEW STAMP

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO COMPLIANCE WITH ALL APPLICABLE CODES

PROPERTY ADDRESS: 3777 OLD BERRY POINT

IOB DESCRIPTION: New construction of a 3 stor

units. The building provid 30,455 GSF

DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851

FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595

www.fuglebergkoch.com

THE ROBERT FT. MYERS, FL REFERENCE DIRECTORY

- WALL SYSTEM

A0.31

09/10/201


#### CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO Design No. U356 COMPLIANCE WITH ALL APPLICABLE CODES DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851 4A. Fiber, Sprayed\* — As an alternate to Batts and Blankets (Item 4) — Spray applied November 26, 2019 ROPERTY ADDRESS: 3777 OLD BERRY POINT 7D. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel Framing Members as cellulose material. The fiber is applied with water to completely fill the enclosed cavity in described below: accordance with the application instructions supplied with the product with a nominal dry OB DESCRIPTION: New construction of a 3 stor Bearing Wall Rating - 1 Hr Rating Exposed to Fire on Interior Face Only a. Furring Channels — Formed of No. 25 MSG galv steel. Spaced 24 in. OC perpendicular to density of 2.7 lb/ft<sup>3</sup>. Alternate Application Method: The fiber is applied without water or Bearing Wall Rating — 1 Hr Rating Exposed to Fire on Exterior Face (See Item 6E) studs. Channels secured to studs as described in Item 7Db. Ends of adjoining channels adhesive at a nominal dry density of 3.5 lb/ft<sup>3</sup>, in accordance with the application instructions Finish Rating — 23 Min or 25 Min (See Item 2C) overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire. units. The building provi 30,455 GSF supplied with the product. This design was evaluated using a load design method other than the Limit States Design Method (e.g., Gypsum board attached to furring channels as described in Item 2. **U S GREENFIBER L L C** — INS735 and INS745 for use with wet or dry application. Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as b. Steel Framing Members\* — Used to attach furring channels (Item 7Da) to studs. Clips spaced INS515LD, INS541LD, INS735, INS745, INS765LD, and INS773LD are to be used for dry Canada, a load restriction factor shall be used — See Guide BXUV or BXUV7 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips. 4B. Fiber, Sprayed\* — As an alternate to Item 4 and 4A — Spray applied cellulose material. \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or **REGUPOL AMERICA** — Type SonusClip The fiber is applied with water to completely fill the enclosed cavity in accordance with the cUL Certification (such as Canada), respectively. 7E. **Steel Framing Members\*** — (Optional, Not Shown) — Resilient channels and Steel Framing Members application instructions supplied with the product. Nominal dry density of 4.58 lb/ft<sup>3</sup>. as described below: **NU-WOOL CO INC** — Cellulose Insulation a. **Resilient Channels** — Formed of No. 25 MSG galv steel, spaced 24 in. OC, and perpendicular 4C. Fiber, Sprayed\* — As an alternate to Batts and Blankets (Item 4) — Spray applied to studs. Channels secured to studs as described in Item b. Ends of adjoining channels overlapped cellulose fiber. The fiber is applied with water to completely fill the enclosed cavity in 6 in. and secured in place with two No. 8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 accordance with the application instructions supplied with the product. The minimum dry in. from the center of the overlap. Gypsum board attached to resilient channels as described in density shall be 4.30 lbs/ft3. INTERNATIONAL CELLULOSE CORP — Celbar-RL b. Steel Framing Members\* — Used to attach resilient channels (Item 7Ea) to studs. Clips 4D. **Fiber**, **Sprayed\*** — As an alternate to Batts and Blankets (Item 4) — Spray applied. spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse drywall screw through the granulated mineral fiber material. The fiber is applied with adhesive, at a minimum density of center hole. Resilient channels are secured to clips with one No. 10 x 1/2 in. pan-head self-drilling 4.0 pcf, to completely fill the enclosed cavity in accordance with the application instructions supplied with the product. See Fiber, Sprayed (CCAZ). **KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip AMERICAN ROCKWOOL MANUFACTURING, LLC — Type Rockwool Premium Plus 8. Non-Bearing Wall Partition Intersection — (Optional) — Two nominal 2 by 4 in. stud or nominal 2 by 6 5. **Wood Structural Panel Sheathing** — Min 7/16 in. thick, 4 ft wide wood structural panels, HORIZONTAL SECTION in. stud nailed together with two 3in. long 10d nails spaced a max. 16 in. OC. vertically and fastened to one min grade "C-D" or "Sheathing". Installed with long dimension of sheet (strength axis) or face side of the minimum 2 by 4 in. stud with 3 in. long 10d nails spaced a max 16 in. OC. vertically. Intersection grain of plywood parallel with or perpendicular to studs. Vertical joints centered on studs. between partition wood studs to be flush with the 2 by 4 in. studs. The wall partition wood studs are to be Horizontal joints backed with nom 2 by 4 in. wood blocking. Attached to studs on exterior framed by with a second 2 by 4 in. wood stud fastened with 3 in. long 10d nails spaced a max. 16 in. OC. side of wall with 6d cement coated box nails spaced 6 in. OC at perimeter of panels and 12 vertically. Maximum one non-bearing wall partition intersection per stud cavity. Non-bearing wall partition in. OC along interior studs. stud depth shall be at a minimum equal to the depth of the bearing wall. 5A. Mineral and Fiber Boards\* — As an alternate to Item 5 - Min 1/2 in. thick, 4 ft wide sheathing, installed vertically to studs. Vertical joints centered on studs. Horizontal joints \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions backed with nom 2 by 4 in. wood blocking. Attached to studs on exterior side of wall with 1employing the UL or cUL Certification (such as Canada), respectively. 1/2 in. long galvanized roofing nails spaced 6 in. OC at perimeter of panels and 12 in. OC along interior studs. As an option a weather resistive barrier may be applied over the Mineral Last Updated on 2019-11-26 6. **Exterior Facings** — Installed in accordance with the manufacturer's installation instructions. One of the following exterior facings is to be applied over the sheathing: A. Vinyl Siding — Molded Plastic\* — Contoured rigid vinyl siding having a flame spread value of 20 or less. See Molded Plastic (BTAT) category in the Building Materials Directory for names of manufacturers. B. **Particle Board Siding** — Hardboard exterior sidings including patterned 1. Wood Studs — Nom 2 by 4 in. spaced 16 in. OC with two 2 by 4 in. top and one 2 by 4 in. bottom panel or lap siding. C. Wood Structural Panel or Lap Siding — APA Rated Siding, Exterior, plates. Studs laterally-braced by wood structural panel sheathing (Item 5). When Mineral and Fiber plywood, OSB or composite panels with veneer faces and structural wood Boards\* (Item 5A) are considered as bracing for the studs, the load is restricted to 76% of allowable core, per PS 1 or APA Standard PRP-108, including textured, rough sawn, axial load. Walls effectively fire stopped at top and bottom of wall. medium density overlay, brushed, grooved and lap siding. 2. Gypsum Board\* — Any 5/8 in. thick UL Classified Gypsum Board that is eligible for use in D. **Cementitious Stucco** — Portland cement or synthetic stucco systems **Design Nos. L501, G512 or U305.** Nom 5/8 in. thick, 4 ft wide, applied vertically and nailed to studs with self-furring metal lath or adhesive base coat. Thickness from 3/8 to 3/4 PERMIT REVIEW STAMP and bearing plates 7 in. OC with 6d cement-coated nails, 1-7/8 in. long with 1/4 in. diam head. in., depending on system. When Item 7, 7B, 7C, 7D or 7E **Steel Framing Members\***, is used, gypsum panels attached to furring E. **Brick Veneer** — Any type on nom 4 in. wide brick veneer. When brick channels with 1 in. long Type S bugle-head steel screws spaced 12 in. OC. veneer is used, the rating is applicable with exposure on either face. Brick When Item 7A Steel Framing Members\*, is used, two layers of gypsum panels attached to furring veneer fastened with corrugated metal wall ties attached over sheathing to channels. Base layer attached to furring channels with 1 in. long Type S bugle-head steel screws wood studs with 8d nail per tie: ties spaced not more than each sixth course spaced 12 in. OC. Face layer attached to furring channels with 1-5/8 in. long Type S bugle-head steel of brick and max 32 in. OC horizontally. One in. air space provided between screws spaced 12 in. OC. All joints in face layers staggered with joints in base layers. brick veneer and sheathing. AMERICAN GYPSUM CO — CKNX.R14196 F. Exterior Insulation and Finish System (EIFS) — Nom 1 in. Foamed **BEIJING NEW BUILDING MATERIALS PUBLIC LTD CO** — CKNX.R19374 Plastic\* insulation bearing the UL Classification Marking, attached over **CABOT MANUFACTURING ULC** — CKNX.R25370 sheathing and finished with coating system, or Portland cement or synthetic CERTAINTEED GYPSUM INC — CKNX.R3660 CGC INC — CKNX.R19751 stucco systems, in accordance with manufacturer's instructions. See CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — CKNX.R18482 Foamed Plastic (BRYX and CCVW) categories for names of Classified GEORGIA-PACIFIC GYPSUM L L C — CKNX.R2717 ISSUE HISTORY **LOADMASTER SYSTEMS INC** — CKNX.R11809 G. **Siding** — Aluminum or steel siding attached over sheathing to studs. Description H. **Fiber-Cement Siding** — Fiber-cement exterior sidings including smooth NATIONAL GYPSUM CO — CKNX.R3501 and patterned panel or lap siding. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — CKNX.R7094 11/22/19 SCHEMATIC DESIGN I. Wall and Partition Facings and Accessories\* — Stone veneer is mortar PANEL REY S A — CKNX.R21796 12/06/19 DESIGN DEVELOPMENT bonded to a lath, scratch coat and water resistant barrier applied to SIAM GYPSUM INDUSTRY (SARABURI) CO LTD — CKNX.R19262 02/28/20 PERMIT REVIEW SET sheathing, installed in accordance with the manufacturers installation THAI GYPSUM PRODUCTS PCL — CKNX.R27517 instructions, and meeting the requirements of local code agencies. UNITED STATES GYPSUM CO — CKNX.R1319 **ELDORADO STONE OPERATIONS L L C** — Type Eldorado Stone USG BORAL DRYWALL SFZ LLC — CKNX.R38438 REVISION HISTORY J. Cementitious Backer Units — 1/2 in. or 5/8 in., min. 32 in. wide.- Applied USG MEXICO S A DE C V — CKNX.R16089 Date Description vertically or horizontally with vertical joints centered over studs. Fastened to 2A. **Gypsum Board\*** — (As an alternate to Item 2, Not Shown) — Any 5/8 in. thick 4 ft wide gypsum studs and runners with cement board screws of adequate length to penetrate panels that are eligible for use in Design Nos. L501, G512 or U305, supplied by the Classified Companies listed below shown in the Gypsum Board\* (CKNX) category. Applied vertically and stud by a minimum 3/4 in., spaced a max of 8 in. OC. Horizontal joints need not be backed by framing. When Cementitious Backer Units are used, the attached to studs and bearing plates with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board for use as substrate for exterior finishes such as ceramic tile, slate, marble, natural stone, manufactured stone, thin brick, or Portland cement or synthetic UNITED STATES GYPSUM CO **USG BORAL DRYWALL SFZ LLC NATIONAL GYPSUM CO** — Type PermaBase USG MEXICO S A DE C V 6A. Building Units\* — As an alternate to Exterior Facing Item 6 — Insulated steel 2B. **Gypsum Board\*** — (As an alternate to Item 2, Not Shown) — 5/8 in. thick 4 ft wide gypsum panels panels, 12 through 42 in. wide. Attached over sheathing through retainer clips to studs or applied vertically and attached to studs and bearing plates with 1-1/4 in. long Type W coarse thread support steel with No. 14 hex head self-tapping screws located at each joint in the concealed gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. from edge of board. lip of the units and spaced in accordance with the structural design requirements. AMERICAN GYPSUM CO — Types AGX-1, M-Glass, AG-C, LightRoc KINGSPAN INSULATED PANELS INC — Types 200, 300, 400, 900, or KS series, 2 through CABOT MANUFACTURING ULC — Type X, 5/8 Type X, Type Blueglass Exterior Sheathing 6 in. thickness; CWP-V, H, 2 through 3 in. nominal thickness or Designwall 2000 or **CERTAINTEED GYPSUM INC** — Type C, Type X, Type X-1, Easi-Lite Type X-2 Designwall 4000, 2 and 3 in. nominal thickness. **GEORGIA-PACIFIC GYPSUM L L C** — Types X, Veneer Plaster Base-Type X, Water Rated-Type X, Sheathing Type-X, Soffit-Type X, Type X ComfortGuard Sound Deadening Gypsum Board. 7. **Steel Framing Members\*** — (Optional, Not Shown) — Furring Channels and Steel PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types PG-11, PGS-WRS. Framing Members as described below: **THAI GYPSUM PRODUCTS PCL** — Type C or Type X a. Furring Channels — Formed of No. 25 MSG galv steel. 2-9/16 in. or 2-23/32 2C. **Gypsum Board\*** — (As an alternate to Item 2, Not Shown) — For Use with Item 5A only - 5/8 in. in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to studs. Channels thick 4 ft wide gypsum panels applied horizontally and attached to studs and bearing plates with 1-1/4 FUGLEBERG KOCH secured to study as described in Item b. Ends of adjoining channels are in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screws 1 overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel in.and 4 in. from edges of board. Finish Rating is 25 min. wire near each end of overlap. As an alternate, ends of adjoining channels may be **CABOT MANUFACTURING ULC** — 5/8 Type X, Type Blueglass Exterior Sheathing overlapped 6 in. and secured together with two self-tapping #6 framing screws, **GEORGIA-PACIFIC GYPSUM L L C** — Type X, Veneer Plaster Base-Type X, Water Rated-Type X, 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 min. 7/16 in. long at the midpoint of the overlap, with one screw on each flange of Sheathing Type-X, Soffit-Type X www.fuglebergkoch.com PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types PG-11, PGS-WRS the channel. Gypsum board attached to furring channels as described in Item 2. b. **Steel Framing Members\*** — Used to attach furring channels (Item 7A) to 2D. **Gypsum Board\*** — (As an alternate to Item 2) — Not to be used with item 7. 5/8 in. thick, 4 ft. studs. Clips spaced 48 in. OC., and secured to studs with No. 8 x 2-1/2 in. coarse wide, paper surfaced, applied vertically only and fastened to the studs and plates with 6d cement drywall screw through the center grommet. Furring channels are friction fitted into coated nails 1-7/8 in. long, 0.0915 in. shank diam and 1/4 in. diam heads, 7 in. OC. clips. RSIC-1 clip for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) clip NATIONAL GYPSUM CO — Type SBWB for use with 2-23/32 in. wide furring channels. 2E **Gypsum Board\*** — (As an alternate to Items 2 through 2D) — Nominal 5/8 in. thick, 4 ft wide PAC INTERNATIONAL L C — Types RSIC-1, RSIC-1 (2.75). panels, secured as described in Item 2. 7A. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels and Steel PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock ES. Framing Members as described below: 2F. Gypsum Board\* — (As an alternate to Item 2) — Not to be used with item 7. 5/8 in. thick, 4 ft. a. Furring Channels — Formed of No. 25 MSG galv steel, spaced 24 in. OC wide, paper surfaced, applied vertically or horizontally and fastened to the studs and plates with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last screw 1 in. perpendicular to studs. Channels secured to studs as described in Item b. Ends of adjoining channels are overlapped 6 in. and tied together with double strand of No. from edge of board. 18 SWG galv steel wire near each end of overlap. Two layers of gypsum board CERTAINTEED GYPSUM INC — Type SilentFX attached to furring channels as described in Item 2. 2G. Wall and Partition Facings and Accessories\* — (As an alternate to Items 2 through 2F) b. Steel Framing Members\* — Used to attach furring channels (Item 7Aa) to Nominal 5/8 in. thick, 4 ft wide panels, secured as described in Item 2. MICHAEL E. GOVE interior side of studs. Clips spaced 48 in. OC., and secured to studs with two No. 8 PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type QuietRock 527. x 2-1/2 in. coarse drywall screws, one through the hole at each end of the clip. 2H. **Gypsum Board\*** — (As an alternate to Item 2) — 5/8 in. thick gypsum panels, with beveled, Furring channels are friction fitted into clips. square, or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing **KINETICS NOISE CONTROL INC** — Type Isomax. with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a maximum 10 in. OC with 7B. **Steel Framing Members\*** — (Optional, Not Shown) — Furring channels and Steel the last two screws 4 and 1 in. from the edges of the board. When used in widths other than 48 in., Framing Members as described below: gypsum panels are to be installed horizontally a. Furring Channels — Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC6A (finish rating 21 in. deep, spaced 24 in. OC perpendicular to studs. Channels secured to studs as min), Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type LGLLX described in Item b. Ends of adjoining channels are overlapped 6 in. and tied 21. **Gypsum Board\*** — (As an alternate to Item 2) — 5/8 in. thick gypsum panels, with beveled, together with double strand of No. 18 SWG galv steel wire near each end of square, or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing overlap. As an alternate, ends of adjoining channels may be overlapped 6 in. and with 1-1/4 in. long Type W coarse thread gypsum panel steel screws spaced a max 8 in. OC, with last secured together with two self-tapping #6 framing screws, min. 7/16 in. long at the screw 1 in. from edge of board. When used in widths of other than 48 in., gypsum boards are to be midpoint of the overlap, with one screw on each flange of the channel. Gypsum installed horizontally. board attached to furring channels as described in Item 2. AMERICAN GYPSUM CO — Types AGX-1 (finish rating 25 min.), M-Glass (finish rating 25 min.), AGb. **Steel Framing Members\*** — Used to attach furring channels (Item a) to studs. C (finish rating 25 min.), LightRoc (finish rating 25 min.) THE ROBERT Clips spaced 48 in. OC. Genie clips secured to studs with No. 8 x 1-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips. NATIONAL GYPSUM CO — Type FSK, Type FSK-G, Type FSW, Type FSW-3, Type FSW-5, Type PLITEQ INC — Type Genie Clip FSW-G, Type FSK-C, Type FSW-C, Type FSMR-C, Type FSW-6, Type FSL 09/10/2019 7C. Steel Framing Members\* — (Optional, Not Shown) — Furring channels and Steel 2J. **Gypsum Board\*** — (As an alternate to Item 2) - 5/8 in. thick gypsum panels, with beveled, square, FT. MYERS, FL Framing Members as described below: or tapered edges, applied either horizontally or vertically. Gypsum panels fastened to framing with 1-1/4 a. Furring Channels — Formed of No. 25 MSG galv steel. Spaced 24 in. OC in. long Type W coarse thread steel screws spaced a max 8 in. OC with the last screw 1 in. from edge perpendicular to studs. Channels secured to studs as described in Item b. Ends of of board. When used in widths other than 48 in., gypsum boards are to be installed horizontally. REFERENCE DIRECTORY adjoining channels overlapped 6 in. and tied together with double strand of No. 18 **CERTAINTEED GYPSUM INC** — Type C, Type X or Type X-1(finish rating 26 min), Easi-Lite Type X AWG galvanized steel wire. Gypsum board attached to furring channels as (finish rating 24 min), Easi-Lite Type X-2, Type EGRG or GlasRoc or GlasRoc Sheathing (finish rating - WALL SYSTEMS described in Item 2. b. **Steel Framing Members\*** — Used to attach furring channels (Item 7Ca) to 3. Joints and Fastener Heads — (Not Shown) — Gypsum board joints covered with tape and joint studs. Clips spaced 48 in. OC., and secured to studs with 2 in. coarse drywall compound. Fastener heads covered with joint compound. screw with 1 in. diam washer through the center hole. Furring channels are friction 4. Batts and Blankets\* — Mineral fiber or glass fiber insulation, 3-1/2 in. thick, pressure fit to fill wall cavities between studs and plates. Mineral fiber insulation to be unfaced and to have a min density of 3 STUDCO BUILDING SYSTEMS — RESILMOUNT Sound Isolation Clips - Type A237R pcf. Glass fiber insulation to be faced with aluminum foil or kraft paper and to have a min density of 0.9 A0.32 pcf (min R-13 thermal insulation rating). See Batts and Blankets\* (BKNV) Category in the Building Materials Directory and Batts and Blankets\* (BZJZ) Category in the Fire Resistance Directory for names of Classified Companies.

PLOTTED: 6/2/2 1:07:

#### Finish Rating - 22 Min.

This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as Canada, a load restriction factor shall be used — See Guide BXUV or

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.



1. **Flooring System** — The flooring system shall consist of one of the following:

System No. 1 Subflooring — Min 23/32 in. thick T & G wood structural panels, min grade "Underlayment" or "Single-Floor". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with end joints staggered 4 ft. Panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d

Svstem No. 2 Subflooring — Min 23/32 in, thick T & G wood structural panels, min grade "Underlayment" or "Single-Floor", Face grain of plywood or strength axis of panels to be perpendicular to the trusses with end joints staggered 4 ft. Panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in, long, 0.113 in, diameter, 0.272 in, round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d

**Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick. **Vapor Barrier** — (Optional) — Nom 0.010 in. thick commercial rosin-sized building paper. Finish Flooring — Min 3/4 in. thickness of lightweight insulating concrete with Perlite Aggregate\* or Vermiculite

**Aggregate\***, or gypsum concrete.

See Perlite Aggregate (CFFX) and Vermiculite Aggregate (CJZZ) categories for names of manufacturers. System No. 3

Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered.

Vapor Barrier — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick. Floor Mat Materials\* — (Optional)— Floor mat material nom 5/64 in. (2 mm) thick adhered to subfloor with Hacker Floor

Primer. Primer to be applied to the surface of the mat prior to the placement of a min 1 in. of floor-topping mixture. ECORE INTERNATIONAL INC — Type QTscu 4002 **HACKER INDUSTRIES INC** — Type Hacker Sound-Mat.

Alternate Floor Mat Materials — (Optional) — Floor mat material nom 1/4 in. (6 mm) thick adhered to subfloor with Hacker Floor Primer. Primer to be applied to the surface of the mat prior to the placement of a min 1-1/4 in. (32 mm) of

**ECORE INTERNATIONAL INC** — Type QTrbm 3006-3 **HACKER INDUSTRIES INC** — Type Hacker Sound-Mat II.

Alternate Floor Mat Materials — (Optional) — Floor mat material nom 1/8 in. (3 mm) thick loose laid over the subfloor. Floor topping thickness shall be a min of 3/4 in. (19 mm) **HACKER INDUSTRIES INC** — FIRM-FILL SCM 125

Alternate Floor Mat Materials — (Optional) — Floor mat material nom 1/4 in. (6 mm) thick loose laid over the subfloor. Floor topping thickness shall be a min of 1 in. (25 mm) HACKER INDUSTRIES INC — Type FIRM-FILL SCM 250, Quiet Qurl 55/025

Alternate Floor Mat Materials — (Optional) — Floor mat material nom 3/8 in. (10 mm) thick loose laid over the subfloor. Floor topping thickness shall be a min of 1-1/4 in. (32 mm)

HACKER INDUSTRIES INC — FIRM-FILL SCM 400, Quiet Qurl 60/040 Alternate Floor Mat Materials — (Optional) — Floor mat material nom 3/4 in. (19 mm) thick loose laid over the subfloor. Floor topping thickness shall be a min of 1-1/2 in. (38 mm)

HACKER INDUSTRIES INC — Type FIRM-FILL SCM 750, Quiet Qurl 65/075 Metal Lath — (Optional) — For use with 3/8 in. (10 mm) floor mat materials, 3/8 in. expanded steel diamond mesh, 3.4

lbs/sq yd placed over the floor mat material. Hacker Floor Primer to be applied prior to the placement of the metal lath. When metal lath is used, floor topping thickness a nom 1-1/4 in. over the floor mat. Finish Flooring — Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive strength of 1100 psi. Mixture shall consist of 6.8 gal of water to 80 lbs of floor topping mixture to 1.9 cu ft of sand. HACKER INDUSTRIES INC — Firm-Fill Gypsum Concrete, Firm-Fill 2010, Firm-Fill 3310, Firm-Fill 4010, Firm-Fill High

Strength, Gyp-Span Radiant **Subflooring** — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or

strength axis of panels to be perpendicular to the trusses with joints staggered. Vapor Barrier — (Optional) — Commercial asphalt saturated felt, 0.010 in. thick.

Finish Flooring — Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a minimum compressive strength of 1800 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. UNITED STATES GYPSUM CO — Types LRK, HSLRK, CSD

LATICRETE SUPERCAP L L C — Types LRK, HSLRK **USG MEXICO S A DE C V** — Types LRK, HSLRK, CSD Floor Mat Materials\* — (Optional) — Floor mat material loose laid over the subfloor. Refer to manufacturer's instruction regarding the minimum thickness of floor topping over each floor mat material.

UNITED STATES GYPSUM CO — Types SAM, LEVELROCK® Brand Sound Reduction Board, LEVELROCK® Brand Floor Underlayment SRM-25 Alternate Floor Mat Materials\* — (Optional) — Nom 3/8 in. thick floor mat material loose laid over the subfloor. Floor topping thickness shall be as specified under Floor Topping Mixture.

GRASSWORX L L C — Type SC50 Alternate Floor Mat Material\* — (Optional) - Floor mat material nominal 3/8 in. thick loose laid over the subfloor. Floor

topping shall be a min 3/4 in. thick.

Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered. **Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick.

Finish Flooring — Floor Topping Mixture\* — Min 1-1/2 in. thickness of floor topping mixture having a min compressive strength of 1000 psi and a cast density of 100 plus or minus 5 pcf. Foam concentrate mixed 40:1 by volume with water and expanded at 100 psi through nozzle. Mixture shall consist of 1.4 cu feet of preformed foam concentrate to 94 lbs Type I Portland cement, 300 lbs of sand with 5-1/2 gal of water. **ELASTIZELL CORP OF AMERICA** — Type FF

System No. 6 Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered.

**Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick. Finish Flooring — Floor Topping Mixture\* — Min 1-1/2 in. thickness of floor topping mixture having a min compressive strength of 1000 psi and a cast density of 100 plus or minus 5 pcf. Foam concentrate mixed 40:1 by volume with water and expanded at 100 psi through nozzle. Mixture shall consist of 1.2 cu feet of preformed foam concentrate to 94 lbs Type I Portland cement, 300 lbs of sand with 5-1/2 gal of water.

**AERIX INDUSTRIES** — Floor Topping Mixture System No. 7

System No. 8 Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered.

**Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick. Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a minimum compressive strength of 1500 psi. Refer to manufacturer's instructions regarding the minimum thickness of floor topping over each floor mat material.

**MAXXON CORP** — Types Maxxon Standard and Maxxon High Strength Floor Mat Materials\* — (Optional) - Floor mat material loose laid over the subfloor. Refer to manufacturer's instructions regarding the minimum thickness of floor topping over each floor mat material.

**MAXXON CORP** — Type Encapsulated Sound Mat. Floor Mat Reinforcement — (Optional) - Refer to manufacturer's instructions regarding minimum thickness of floor topping for use with floor mat reinforcement. Metal Lath — (Optional) - 3/8 in. expanded galvanized steel diamond mesh, 3.4 lbs/sq yd loose laid over the floor mat

Fiber Glass Reinforcement - (Optional, Not Shown) - 0.015 in. thick PVC coated non-woven fiberglass mesh, 0.368 lbs/sq yd loose laid over the floor mat material.

System No. 9 Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered.

**Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick. Finish Flooring — Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive strength of 1000 psi. Mixture shall consist of 5 to 8 gal of water to 80 lbs of floor topping mixture to 2.1 cu ft of sand. ULTRA QUIET FLOORS — UQF-A, UQF-Super Blend, UQF-Plus 200

System No. 10 Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered.

Vapor Barrier — (Optional) Commercial asphalt saturated felt, 0.030 in. thick. Finish Flooring — Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping having a min compressive strength of 1000 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. FORMULATED MATERIALS LLC — Types FR-25, FR-30, and SiteMix

Alternate Floor Mat Material\* — (Optional) Floor mat material nominal 2 - 9.5 mm thick loose laid over the subfloor. Floor topping shall be a min of 3/4 in.

FORMULATED MATERIALS LLC — Types M1, M2, M3, Elite, Duo, R1, and R2

Subflooring — Min 1 by 6 in. T & G lumber fastened diagonally to trusses, or min 15/32 in. thick plywood or min 7/16 in. thick oriented strand board (OSB) wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panel to be perpendicular to trusses with joints staggered.

Finish Floor - Mineral and Fiber Board\* — Min 1/2 in. thick, supplied in sizes ranging from 3 ft by 4 ft to 8 ft by 12 ft. All joints to be staggered a min of 12 in. with adjacent sub-floor joints. **HOMASOTE CO** — Type 440-32 Mineral and Fiber Board System No. 12

Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered. **Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick.

Finish Flooring — Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping having a min compressive strength of 1000 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. ACG MATERIALS — Accu-Crete types NexGen, Green, Prime, B, M, and PrePour, AccuRadiant, AccuLevel types G40,

Alternate Floor Mat Material\* — (Optional) — Floor mat material nominal 2 - 9.5 mm thick loose laid over the subfloor. Floor topping shall be a min of 3/4 in. ACG MATERIALS — AccuQuiet types P80, C40, D13, D-18, D25, DX38, EM.125, EM.125S, EM.250, EM.250S. EM.375.

EM.375S, EM.750, and EM.750S. System No. 13 Subflooring — Min 15/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the joists with joints staggered.

**Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick. **Vapor Barrier** — (Optional) — Nom 0.010 in. thick commercial rosin-sized building paper. Finish Flooring\* — Min 3/4 in, thickness of any Floor Topping Mixture bearing the UL Classification Marking as to Fire Resistance. See Floor- and Roof-Topping Mixtures (CCOX) category for names of Classified Companies.

Floor Mat Materials\* — (Optional) — Nom. 1/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in.

Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 3/8 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 60/040 and Quiet Qurl 60/040 N Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 3/4 in. thick loose laid over the subfloor.

KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 55/025 and Quiet Qurl 55/025 N

Floor topping thickness shall be a minimum of 1-1/2 in. **KEENE BUILDING PRODUCTS CO INC** — Type Quiet Qurl 65/075, Quiet Qurl 65/075 N Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 1/8 in. thick loose laid over the subfloor.

Floor topping thickness shall be a minimum of 3/4 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 52/013 and Quiet Qurl 52/013 N Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 1/4 in. entangled net core with a

compressible fabric attached to the bottom loose laid over the subfloor. Floor topping thickness shall be a minimum of KEENE BUILDING PRODUCTS CO INC — Quiet Qurl 55/025 MT and Quiet Qurl 55/025 N MT

System No. 14 Subflooring — Min 23/32 in. thick T&G wood structural panels, min grade "Underlayment" or "Single-Floor". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with end joints staggered 4 ft. Panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance

strength may be substituted for the 6d nails. **Gypsum Board\*** — One layer of nom 5/8 in. thick, 4 ft wide gypsum board, installed with long dimension perpendicular to joists. Gypsum board secured with 1 in. long No. 6 Type W bugle head steel screws spaced 12 in. OC and located a min of 1-1/2 in. from side and end joints. The joints of the gypsum board are to be staggered a minimum of 12 inches from the joints of the subfloor.

GEORGIA-PACIFIC GYPSUM L L C — Type DS Floor Mat Materials\* — (As an alternate to the single layer gypsum board) — Floor mat material loose laid over the

MAXXON CORP — Type Encapsulated Sound Mat. Gypsum Board\* — (For use when floor mat is used) Two layers of nom 5/8 in. thick, 4 ft wide gypsum board,

installed with long dimension perpendicular to joists on top of the floor mat material. Gypsum board secured to each other with 1 in. long No. 6 Type G bugle head steel screws spaced 12 in. OC and located a min of 1-1/2 in. from side and end joints. The joints of the gypsum board are to be staggered a minimum of 12 inches in between layers and from the joints of the subfloor. **GEORGIA-PACIFIC GYPSUM L L C** — Type DS

System No. 15 Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with joints staggered. **Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick.

Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping having a min compressive strength of 1000 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. **DEPENDABLE LLC** — GSL M3.4, GSL K2.6, GSL-CSD and GSL RH Floor Mat Materials\* — (Optional) — Nom. 1/4 in. thick loose laid over the subfloor. Floor topping thickness shall be

a minimum of 3/4 in. **KEENE BUILDING PRODUCTS CO INC** — Type Quiet Qurl 55/025 and Quiet Qurl 55/025 N Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 3/8 in. thick loose laid over the subfloor.

Floor topping thickness shall be a minimum of 1 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 60/040 and Quiet Qurl 60/040 N Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 3/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1-1/2 in.

KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 65/075, Quiet Qurl 65/075 N Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 1/8 in, thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 52/013 and Quiet Qurl 52/013 N

Alternate Floor Mat Materials\* — (Optional) — Floor mat material Nom. 1/4 in. entangled net core with a compressible fabric attached to the bottom loose laid over the subfloor. Floor topping thickness shall be a min. of 1 in.

KEENE BUILDING PRODUCTS CO INC — Quiet Qurl 55/025 MT and Quiet Qurl 55/025 N MT

Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the joists with joints staggered. **Vapor Barrier** — (Optional) — Commercial asphalt saturated felt, 0.030 in. thick.

**Vapor Barrier** — (Optional) — Nom 0.010 in. thick commercial rosin-sized building paper. Finish Flooring\* — Min 3/4 in. thickness of any Floor Topping Mixture bearing the UL Classification Marking as to Fire Resistance. See Floor- and Roof-Topping Mixtures (CCOX) category for names of Classified Companies. Floor Mat Materials\* — (Optional) — Nom 3/32 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in.

PLITEQ INC — Type GenieMat RST02 Floor Mat Materials\* — (Optional) — Nom 3/16 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in **PLITEQ INC** — Type GenieMat FF03NP Floor Mat Materials\* — (Optional) — Nom 1/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a

minimum of 3/4 in. PLITEQ INC — Type GenieMat FF06 Floor Mat Materials\* — (Optional) — Nom 3/8 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in.

PLITEQ INC — Type GenieMat FF10 Floor Mat Materials\* — (Optional) — Nom 3/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1-1/2 in.

PLITEQ INC — Type GenieMat FF17 Floor Mat Materials\* — (Optional) — Nom 1 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1-1/2 in.

PLITEQ INC — Type GenieMat FF25 **Subflooring** — Nom. 1-1/2 in. thick T & G laminated composite plywood sub-floor panels to be perpendicular to the trusses with end joints staggered 4 ft. End joints centered over top chord of trusses. Subfloor panels secured to trusses with construction adhesive and #8 by 3 in. wood screws spaced 12 in. OC in the field and 6 in. OC at the end

RSP INDUSTRIES INC — SAP board

**Subflooring** — Min 15/32 in. thick wood structural panels, min grade "Underlayment" or "Single-Floor". Panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. Wall and Partition Facings and Accessories\* - Sound Barrier (Optional) — Acoustic Sleeper pads stapled to the top of the subfloor and centered over wood trusses. Acoustic Sleeper pads are to be spaced appropriately so that the

finish floor panels are fastened through Acoustic Sleeper pads to the trusses.

STC ARCHITECTURAL PRODUCTS L L C DBA STC SOUND CONTROL — Acoustic Sleeper Finish Floor — Min 23/32 in. thick T & G wood structural panels, min grade "Underlayment" or "Single-Floor". Face grain of plywood or strength axis of panels to be perpendicular to the trusses with end joints staggered 4 ft. Butt joints of panels have the option of being sealed with any UL Classified caulk or sealant found under - Fill, Void or Cavity Materials\* (XHHW).

System No. 19 Structural Cement-Fiber Units\* — For use with UNITED STATES GYPSUM CO Types C. IP-X2. IPC-AR and ULIX gypsum boards only. Nom 3/4 in. thick, with long edges tongue and grooved. Long dimension of panels to be perpendicular to wood trusses with end joints staggered a min of 2 ft and centered over the trusses. Panels secured to wood trusses with 1-5/8 in. long, No. 8, self- countersinking wood screw spaced a max of 12 in. OC in the field with a screw located 1 in. and 2 in. from each edge, and 8 in. OC on the perimeter with a screw located 2 in. from each edge, located 1/2 in. from the end edges of the panel.

UNITED STATES GYPSUM CO — Types STRUCTO-CRETE, USGSP Subflooring — Min 23/32 in. thick T & G wood structural panels, min grade "Underlayment" or "Single-Floor". Face

grain of plywood or strength axis of panels to be perpendicular to the trusses with end joints staggered 4 ft. Panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails

Finish Flooring - Floor Topping Mixture\* — Min 1 in. thickness of floor topping mixture having a min compressive strength of 4500 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. SIKA DEUTSCHLAND GMBH — Type SCHONOX AP Rapid Plus

2. Trusses — Parallel chord trusses, spaced a max 24 in. OC, fabricated from nom 2 by 4 in. lumber with lumber oriented vertically or horizontally. Min truss depth is 12 in. when item 9 is not employed. Min truss depth is 18 in. when item 9 is employed. Truss members secured together with min No. 20 MSG galv steel truss plates. Plates have 5/16 in. long teeth projecting perpendicular to the plane of the plate. The teeth are in pairs facing each other (made by the same punch), forming a split-tooth-type plate. Each tooth has a chisel point on its outside edge. These points are diagonally opposite each other for each pair. The top half of each tooth has a twist for stiffness. The pairs are repeated

on approx 7/8 in. centers with four rows of teeth per in. of plate width. 3. Furring Channels — Furring channels, 7/8 in. deep by 2-9/16 in. or 2-11/16 in. or 2-23/32 in. wide at the base and 1-7/16 in. wide at the face, formed from No. 25 ga galv steel, spaced 24 in. OC perpendicular to trusses. Channels secured to trusses with double strand of No. 18 SWG galv steel wire spaced 48 in. OC. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. Two furring channels used at end joints of gypsum board (Item 4), each extending a min of 6 in. beyond both side edges of

3A. **Resilient Channels** — (Not Shown) — As an alternate to Item 3, resilient channel formed from No. 26 MSG galv steel, spaced 16 in. OC perpendicular to trusses. Channels secured to each truss with 1-1/4 in. long No. 6 Type S ugle head steel screw. Channels overlapped at splices 4 in. Two resilient channels used at end joints of gypsum board (Item 4), each extending a min of 6 in. beyond both side edges of the board.

2). Clips spaced 48 in. OC. RSIC-1 and RSIC-1 (2.75) clips secured to the bottom chord of alternating trusses with No. 8 x 2-1/2 in. coarse drywall screw through the center grommet. RSIC-V and RSIC-V (2.75) clips secured to the bottom friction fitted into clips. RSIC-1 and RSIC-V clips for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) and RSIC-V (2.75) clips for use with 2-23/32 in. wide furring channels. Adjoining channels are overlapped as described in Item 3. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two min 7/16 in. long No. 6 self-tapping framing screws, at the midpoint of the overlap, with one screw on each flange of the channel. Additional clips required to hold furring channel that supports the gypsum board butt joints, as described in Item 4. When Fiber, Sprayed (Item 6) is used, furring channel spacing reduced to 16 in. OC and two layers of nom 5/8 in.

thick, 4 ft wide gypsum board shall be installed as described in Item 4. PAC INTERNATIONAL L L C — Types RSIC-1, RSIC-V, RSIC-1 (2.75), RSIC-V (2.75). 3C. Steel Framing Members\* — (Optional, Not Shown) — Used as an alternate method to attach furring channels to trusses. Clips spaced 48 in. OC., and secured to the bottom chord to alternating trusses with two No. 8 x 2-1/2 in. coarse drywall screws, one through the hole at each end of the clip. Furring channels are friction fitted into clips. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap. Additional clips required to hold furring channel that supports the gypsum board butt joints, as described in Item 4. Two layers of gypsum board required as described in Item 4. Not evaluated for use with Item 6. When Item 3C is used and Batts and Blankets\* are added per Section III Item 18 Blanket Insulation in the General Information of this Directory (BXUV), clips spaced 48 in. OC, furring channels spaced 16 in. OC max, 3-1/2 in. max. Batts and Blankets\* secured to plywood subfloor with staples spaced 12 in. OC or to the trusses with 0.090 in. diam galv steel wires spaced 12 in. OC, and two layers of gypsum board required as described in Item 4A. When the Batts and Blankets\* are draped over the furring channel/gypsum panel ceiling membrane, the clip

spacing shall be reduced to 24 in. OC and secured to consecutive trusses, the furring channel spacing shall be reduced to 12 in. OC, and two layers of gypsum board required as described in Item 4A. **KINETICS NOISE CONTROL INC** — Type Isomax. 3D. Steel Framing Members\* — (Optional, Not Shown) — Used as an alternate method to attach furring channels to trusses. Clips spaced 48 in. OC. and secured to the bottom chord to alternating trusses with one No. 8 x 2-1/2 in. coarse drywall screw through the center hole. Furring channels are friction fitted into clips. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap.

Additional clips required to hold furring channel that supports the gypsum board butt joints, as described in Item 4. Not evaluated for use with Item 6. PLITEQ INC — Type Genie Clip 3E. Steel Framing Members\* — (Optional, Not Shown) — For use with Item 7B - Used as an alternate method to attach furring channels to trusses. Clips spaced at 48" OC and secured to the bottom of the trusses with one 2 in. Coarse Drywall Screw with 1 in. diam. washer through the center hole. Furring channels are then friction fitted into

clips. Ends of channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire Additional clips are required to hold the Gypsum Butt joints as described in item 4. Not evaluated for use with Item 6. STUDCO BUILDING SYSTEMS — RESILMOUNT Sound Isolation Clips - Type A237 or A237R 3F. Resilient Channels — For use with Item 4B and 7A - Resilient channels, formed from No. 25 MSG galv steel and shaped as shown, spaced 12 in. OC perpendicular to joist. Channels overlapped 4 in. at splices and secured to each joist with 1-1/4 in. Type S screws. Min end clearance of channels to wall to be 1/2 in. Additional resilient channels

positioned so as to coincide with end joints of gypsum board. 3G. Resilient Channels — For Use With Item 4C and 7C. Formed from min 25 MSG galv steel installed perpendicular to trusses and spaced 16 in. OC. Channels secured to each truss with 1-5/8 in. long Type S bugle head steel screws. truss involved with the butt joint. Channels overlapped 4 in. at splices. Two channels, spaced 6 in. OC, oriented opposite each gypsum panel end joint. Additional channels shall extend min 6 in. beyond each side edge of panel. Insulation, Item 7C is applied over the

resilient channel/gypsum panel ceiling membrane. 3H. Steel Framing Members\* — (Optional, Not Shown) — Used as an alternate method to attach furring channels to joints and spaced 8 in. OC along the end joints and in the field. Panels fastened to cross tees with 1 in. long, Type S 1 in. diam. washer through the center hole. Furring channels are then friction fitted into clips. Ends of channels are overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire .Additional clips are required to hold the Gypsum Butt joints as described in item 4. Not evaluated for use with Item 6.

**REGUPOL AMERICA** — Type SonusClip 31. Steel Framing Members — (Not Shown) — As an alternate to Item 3, main runners, cross tees, cross channels and wall angle as listed below. a. Main Runners — Nom 10 or 12 ft long, 15/16 in. or 1-1/2 in. wide face, spaced 4 ft. OC. Main runners suspended by min 12 SWG galv. steel hanger wires spaced 48 in. OC. Hanger wires to be located adjacent to main runner/cross

bottom face. b. Cross Tees or Channels — Nom 4 ft long cross tees, with 15/16 in. or 1-1/2 in. wide face, or nom 4 ft long cross

When Steel Framing Members (Item 3N) are used, nom 5/8 in. thick, 4 ft wide gypsum board, installed as described in channels, with 1-1/2 in. wide face, spaced 16 in. OC, installed perpendicular to the main runners. Additional cross tees

Item 4. Butt joints staggered minimum 24 in. OC. or channels used 8 in. from each side of butted gypsum board end joints. The cross tees or channels may be riveted or screw-attached to the wall angle or channel to facilitate the ceiling installation. c. Wall Angle or Channel — Painted or galv. steel angle with 1 in. legs or channel with 1 in. legs, 1-9/16 in. deep

screw-attachment of the gypsum panel.

**USG INTERIORS LLC** — Type DGL or RX

attached to walls at perimeter of ceiling with fasteners 16 in. OC. To support steel framing member ends and for CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC-C/A GEORGIA-PACIFIC GYPSUM L L C — Types 5, DAPC, TG-C NATIONAL GYPSUM CO — Types eXP-C, FSK-C, FSW-C, FSW-G

**AMERICAN GYPSUM CO** — Type AG-C

3J. Steel Framing Members\* — (Optional, Not Shown) — Used to attach resilient channels (Item 3A) to trusses (Item 2). Clips spaced 48 in. OC on adjacent trusses, and secured to trusses with one No. 8 x 2-1/2 in. coarse drywall screw through center grommet hole. Channels secured to clips with one #10 x 1/2 in. pan-head self-drilling screw. Ends of adjoining channels overlapped 6 in. and secured together with two #8 15 x 1/2 in. Philips Modified Truss screws spaced 2-1/2 in. from the center of the overlap. Gypsum board butt joints require additional resilient channels spaced 1-1/2 in. from the butt joint on either side. One edge of the extra channels will extend to an adjacent truss where it is secured with a clip.

**KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip 3K. Resilient Channels — For use with items 3L, 4F, and 7G — Formed from min 26 MSG galv steel installed perpendicular to trusses. When Item 7G is draped over channels, channels spaced a maximum 12 in. OC. Channels secured to each truss as described in Item 3L. Channel ends butted and centered under the joists and attached to the ioists with one screw at each end. Additional resilient channels positioned so as to coincide with end joints of gypsum board as shown in the above illustration. Additional channels shall extend min 3 in. beyond each side edge

3L. Steel Framing Members\* — (Optional, Not Shown) — Used as an alternate method to attach resilient channels to joists (Item 2). For use with items 3K, 4F and 7G. A resilient sound isolation accessory shall be used at each attachment point of the resilient channels and spaced max 24 in. O.C. Channel ends butted and centered under the joists and attached to the joists with one accessory at each end. Additional accessories used to hold resilient channels that support the gypsum board end joints, as described in Item 3K. The accessory envelops the mounting edge of the resilient channel. The accessory and resilient channel are fastened to the joists with the screws supplied with the accessory and per the accessory manufacturer's installation instructions. **ACOUSTIC PROPERTIES L L C** — Types RC-1 Boost

3M. Steel Framing Members\* — (Optional, Not Shown) — As an alternate to Item 3. a. Furring Channels — Formed of No. 25 MSG galv steel, nominal 2-1/2 in. wide by 7/8 in. deep, spaced 24 in. OC, perpendicular to trusses. located a min of 1/2 in. from side joints and 3 in. from the end joints. Finish Rating with this ceiling Channels secured to Cold Rolled Channels at every intersection with a 3/4 in. TEK screw through each furring channel leg. Ends of adjoining channels overlapped 12 in. and fastened together with two double strand No. 18 SWG galv steel wire ties, one at each end of overlap, or with two 3/4 in. TEK screws in each leg of the overlap section. Two furring channels used at end joints of gypsum board (Item 4), each extending a min of 6 in. beyond both side edges of the board. b. Cold Rolled Channels — 1-1/2 in. by 1/2 in., formed from No. 16 ga. galv steel, positioned vertically and parallel to trusses, friction-fitted into the channel caddy on the Steel Framing Members (Item 3Md) and secured with two 3/4 in. TEK screws. Adjoining lengths of cold rolled channels lapped min. 12 in. and secured along bottom legs with four 3/4 in. TEK screws and wire-tied together with two double strand 18 SWG galv steel wire ties, one at each end of overlap.c. **Blocking** — Where truss design does not permit direct, full contact of the hanger bracket, a piece of nominal 2 by 4 in. lumber (blocking), min. 12 in. long to permit full contact of the hanger bracket, to be secured vertically to the side of the trusses at the top and bottom of the blocking at each Steel Framing Member (Item 3Md) location with 16d nails or minimum 2-1/2 in. screws.d. Steel Framing Members\* — Spaced 48 in. OC. max along truss, and secured to the truss on alternating trusses with two, #10 x 1-1/2 in. screws through

mounting holes on the hanger bracket. PAC INTERNATIONAL L C — Type RSIC-SI-CRC EZ Clip 3N. Steel Framing Members\* — (Optional, Not Shown) — As an alternate to Item 3. a. Furring Channels — Formed of No. 25 MSG galv steel, nominal 2-1/2 in. wide by 7/8 in. deep, spaced 24 in. OC perpendicular to trusses and friction fit into Steel Framing Members (Item 3Nc). Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap or with two TEK screws along each leg of wide gypsum board is installed with long dimensions perpendicular to resilient channels. Gypsum the 6 in. overlap. Two furring channels used at end joints of gypsum board (Item 4). Butt joint channels held in place by strong back channels placed upside down, on top of, and running perpendicular to primary furring channels, extending 6 in. longer than length of gypsum side joint. Strong back channels spaced maximum 48 in. OC. Strong back channels secured to every intersection of primary furring channels with four 7/16 in. pan head screws, two along each of the legs at intersections. Butt joint channels run perpendicular to strong back channels and shall be minimum 6 in. longer than length of joint, secured to strong back channels with 7/16 in. pan head screws, two along each of the legs at intersection with strong back channels. b. Blocking — Where truss design does not permit direct, full contact of the hanger bracket, a piece of nominal 2 by 4 in. lumber (blocking), min. 12 in. long to permit full contact of the hanger bracket, to be secured vertically to the side of the trusses at the top and bottom of the blocking at each Steel Framing Member (Item 3Nc) location with 16d nails or minimum 2-1/2 in. screws. c. Steel Framing Members\* — Used to attach furring channels (Item 3Na) to trusses. Clips spaced 48 in. OC and secured along truss webs at each furring channel intersection with min. 3/4 in. long self-drilling #10 x 1-1/2 in. screws

through each of the provided hole locations. Furring channels are friction fitted into clips. PAC INTERNATIONAL L L

C — Type RSIC-S1-1 Ultra 4. **Gypsum Board\*** — One layer of nom 5/8 in. thick, 4 ft wide gypsum board, installed with long dimension perpendicular to furring or resilient channels. Gypsum board secured with 1 in. long No. 6 Type S bugle head steel screws spaced 12 in. OC and located a min of 1-1/2 in. from side and end joints. End joints secured to both resilient channels as shown in the end joint detail. When Steel Framing Members (Item 3B) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is installed with long dimension perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long No. 6 Type S bugle head screws spaced 12 in. OC in the field of the board. Gypsum board butt joints shall be staggered 2 ft within the assembly, and shall occur between the main furring channels. At the gypsum board butt joints, each end of each gypsum board shall be supported by a single length of furring channel equal to the width of the gypsum board plus 6 in. on each end. The two furring channels at each butt joint shall be spaced approximately 3-1/2 in. OC, and be attached to the bottom chord of the truss with one RSIC-1 clip at each end of the channel. Screw spacing along the gypsum board butt joint shall be 8 in. OC. When both Steel Framing Members (Item 3B) and Fiber, Sprayed (Items 6 or 6A) are used, furring channel spacing reduced to 16 in. OC and two layers of nom 5/8 in. thick, 4 ft wide gypsum board are installed with long dimension perpendicular to furring channels. Base layer secured to furring channels with nom 1 in. long No. 6 Type S bugle head screws spaced 12 in. OC in the field of the board. Gypsum board butt joints shall be staggered 2 ft within the assembly, and shall occur between the main furring channels. At the gypsum board butt joints, each end of each gypsum board shall be supported by a single length of furring channel equal to the width of the gypsum board plus 6 in. on each end. The two furring channels at each butt joint shall be spaced approximately 3-1/2 in. OC, and be attached to the bottom chord of the truss with one RSIC-1 clip at each end of the channel. Screw spacing along the gypsum board butt joint shall be 8 in. OC. Outer layer secured to furring channels using 1-5/8 in. long No. 6 Type S screws spaced 8 in. OC and 1-1/2 in. from the end joint. Butted end joints to be offset a min. of 8 in. from base layer end joints. Butted side joints of outer layer to be offset min. 18 in. from butted side joints of base layer. When Steel Framing Members (Item 3C) are used, two layers of nom 5/8 in. thick, 4 ft wide are installed with long dimensions perpendicular to 3B. Steel Framing Members\* — (Optional) — Used as an alternate method to attach furring channels to trusses (Item furring channels. Base layer attached to the furring channels using 1 in. long No. 6 Type S bugle-head steel screws spaced 12 in. OC in the field of the board. Butted end joints shall be staggered min 2 ft. within the assembly, and occur midway between the continuous furring channels. Each end of each gypsum board shall be supported by a single length of chord of alternating trusses with No. 8 x 1-1/2 in. coarse drywall screw through the center hole. Furring channels are furring channel equal to the width of the gypsum board plus 6 in. on each end. The two furring channels shall be spaced approximately 4 in. OC, and be attached to underside of the truss with one Isomax clip at each end of the channel. Screw spacing along the gypsum board butt joint shall be 8 in. OC. Outer layer attached to the furring channels using 1-5/8 in. long No. 6 Type S bugle-head steel screws spaced 12 in. OC in the field. The end of the outer layer boards at the butt joint shall be attached to the base layer boards with 1-5/8 in. long Type G screws spaced 8 in. OC and 1-1/2 in. from the end joint. Butted end joints to be offset a min of 8 in. from base layer end joints. Butted side joints of outer layer to be offset min 18 in. from butted side joints of base layer. When **Steel Framing Members** (Item 3D) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is

installed with long dimensions perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long No. 6 Type S bugle-head steel screws spaced 12 in. OC in the field of the board. Gypsum board butted end joints shall be staggered minimum 16 in. within the assembly. . At the gypsum board butt joints, each end of each gypsum board shall be supported by a single length of furring channel equal to the width of the gypsum board plus 6 in. on each end. These additional furring channels shall be attached to underside of the truss with Genie clips as described in Item 3D. Screw spacing along the gypsum board butt joint shall be 6 in. OC. When Steel Framing Members (Item 3E) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is installed with long dimensions perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long Type S bugle-head steel screws spaced 8 in. OC in the field of the board. Gypsum board butted end joints shall be staggered minimum 48 in. and centered over main furring channels. At the gypsum board butt joints, each end of each gypsum board shall be supported by a single length of furring channel equal to the width of the gypsum board plus 3 in. on each end. The two support furring channels shall be spaced approximately 3 in. in from joint. Screw spacing along the gypsum board butt joint and along both additional channels shall be 8 in. OC. Additional screws shall be placed in the adjacent section of gypsum board into the aforementioned 3 in. extension of the extra butt joint channels as well as into the main channel that runs between . Butt joint furring channels shall be attached with one RESILMOUNT Sound Isolation Clip at each end of the channel. When **Fiber, Sprayed** (Items 6 or 6A) is used, two layers of nom 5/8 in. thick, 4 ft wide gypsum board are installed with long dimensions perpendicular to furring channels. Base layer gypsum board secured with 1 in. long No. 6 Type S bugle head steel screws spaced 12 in. OC and located a min of 1-1/2 in. from side and end joints. End joints secured to both resilient channels as shown in the end joint detail. Outer layer gypsum board secured with 1-5/8 in. long No. 6 Type S bugle head steel screws spaced 12 in. OC and located a min of 1-1/2 in. from side and end joints. Outer layer shall be finished as described in Item 5. When **Foamed** Plastic insulation (Item 7E) is applied to the underside of the subflooring, screw spacing shall be reduced to 8 in. OC with minimum 1-1/4 in. long Type S screws to install gypsum to the resilient channels (Item 3A). Resilient channels (Item 3A) to be spaced maximum 12 in. OC. Butted end joints shall be staggered min. 2 ft within the assembly, and occur midway between the continuous furring channels. End joints secured to both resilient channels as shown in end joint detail.

When Steel Framing Members (Item 3E) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is installed with long dimensions perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long Type S bugle-head steel screws spaced 8 in. OC in the field of the board. Gypsum board butted end joints shall be staggered minimum 48 in. and centered over main furring channels. At the gypsum board butt joints, an additional single length of furring channel shall be installed and be spaced approximately 3 in. from the butt joint (6 in. from the continuous furring channels) to support the floating end of the gypsum board. Each of these shorter sections of furring channel shall extend one truss beyond the width of the gypsum panel and be attached to the adjacent trusses with one SonusClip at every

When Steel Framing Members\* (Item 3I) are used, one layer of 5/8 in. thick, 48 in. wide gypsum board, installed with long dimension perpendicular to cross channels with side joints centered along main runners. Gypsum board fastened to cross channels with 1 in. long No. 8 Type S bugle head steel screws located 1/2 in. from end joints and 1-3/4 in. from side RUSKIN COMPANY — Model CFD7T or CFDR7T trusses. Clips spaced at 48" OC and secured to the bottom of the trusses with one 2-1/2 in. Coarse Drywall Screw with bugle-head screws spaced in the field and 8 in. OC along end joints. Panels fastened to main runners with 1 in. long. Type 9B. Deleted. S bugle-head screws spaced midway between cross tees. Screws along sides and ends of panels spaced 3/8 to 1/2 in. from panel edge. Gypsum board sheets screw attached to leg of wall angle with 1 in. long No. 8 Type S bugle head steel screws spaced 12 in. OC. End joints of panels shall be staggered with spacing between joints on adjacent panels not less

When Steel Framing Members (Item 3J) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is installed with long dimensions perpendicular to resilient channels. Gypsum board secured to resilient channels with nom 1 in. long Type assembly installed in accordance with the manufacturers installation instructions. S bugle-head steel screws spaced 8 in. OC in the field of the board and located 3/4 in. from side joints and 1-1/2 in. from end joints. Gypsum board joints are to be staggered by a minimum of 24 in. tee intersections. Hanger wires wrapped and twist-tied on 16d nails driven in to side of trusses at least 5 in. above the When Steel Framing Members (Item 3M) are used, nom 5/8 in. thick, 4 ft wide gypsum board, installed as described in

Item 4. Adjacent butt joints staggered minimum 48 in. OC.

**CERTAINTEED GYPSUM INC** — Type C CGC INC — Types C, IP-X2, IPC-AR

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type C THAI GYPSUM PRODUCTS PCL — Type C UNITED STATES GYPSUM CO — Types C, IP-X2, IPC-AR

**USG BORAL DRYWALL SFZ LLC** — Type C **USG MEXICO S A DE C V** — Types C, IP-X2, IPC-AR 4A. Gypsum Board — For use when Item 3C is used and Batts and Blankets\* are secured to the plywood subfloor, to the trusses or draped over the furring channel/gypsum panel ceiling nembrane as described in Item 3C. For method of gypsum board installation, see Item 4. CGC INC — Types C, IP-X2, IPC-AR

UNITED STATES GYPSUM CO — Types C, IP-X2, IPC-AR **USG BORAL DRYWALL SFZ LLC** — Type C

**USG MEXICO S A DE C V** — Types C, IP-X2, IPC-AR

4B. Gypsum Board\* — For use when Batts and Blankets\* (Item 7A) and Resilient Channels (Item 3F) are used. Nom 5/8 in. thick, 4 ft wide gypsum board installed with long dimension perpendicular to resilient channels. Nom 1 in. long No. Type S bugle head screws are driven through channel spaced 8 in. OC. End joints of gypsum board similarly fastened to additional resilient channels positioned at end joint locations. **AMERICAN GYPSUM CO** — Type AG-C.

CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC-C/A PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type C 4C. Gypsum Board\* — For use with Items 3G and 7C or 3I and 7F, and 7C. Nom 5/8 in. thick,

48 in. wide gypsum panels installed with long dimension perpendicular to resilient channels. Gypsum panels secured with 1 in. long Type S bugle head steel screws spaced 8 in. OC and system is 20 min. CGC INC — Type ULIX

**UNITED STATES GYPSUM CO** — Type ULIX

4D. Gypsum Board\* — For use when Flooring System (Item 1) consists of both System No. 1 and min 15/32 in. plywood, min grade "Underlayment" or "Sturd-I-Floor" with T & G edges and conforming with PS1-83 specifications, or min 3/4 in. thickness of any Floor Topping Mixture (CCOX) bearing the UL Classification Marking as to Fire Resistance, min Truss depth (Item 2) is 18 in. and Batts and Blankets (Item 7D) and Resilient Channels (Item 3A) are used. One layer of nom 5/8 in. thick, 48 in. wide gypsum board installed with long dimension perpendicular to resilient channels. Gypsum board secured with 1 in. long Type S bugle head steel screws. Screws spaced 1 in, from side joints, and 12 in, OC in the rest of the field. Screws spaced 1-1/2 in. from the end joints. End joints secured to both resilient channels as shown in end joint detail. When batt insulation (Item 7D) is draped over the resilient channel/gypsum board ceiling membrane, the resilient channel (Item 3A) spacing shall be reduced to 12 in. OC., and gypsum board screws spaced 1 in. from side joints, and 8 in. OC in the rest of the field. For use only with Ceiling Damper described in Item 9R. PANEL REY S A — Type PRC2

4F. Gypsum Board\* — For use with Items 3K, 3L, and 7G— One layer of nom 5/8 in. thick, 4 ft board secured to resilient channels with min nom 1 in. long Type S bugle-head steel screws spaced 8 in. OC in the field of the board and located 3/4 in. from side joints and 1-1/2 in. from end joints. Gypsum board butt joints are to be staggered by a minimum of 24 in. PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Type C 5. Finishing System — (Not Shown) — Vinyl, dry or premixed joint compound, applied in two

coats to joints and screw-heads. Nom 2 in. wide paper tape embedded in first layer of compound

over all joints. As an alternate, nom 3/32 in. thick veneer plaster may be applied to the entire surface of gypsum board. 6. Fiber, Sprayed\* — (Dry Dense Packed 100% Borate Formulation) — (Not Shown, Optional) - The fiber is applied without water or adhesive at a nominal dry density of 3.5 lb/ft³, in accordance with the application instructions supplied with the product. When Item 6 (Fiber, Sprayed, Dry Dense Packed) is used, Furring Channels (Item 3F) or Resilient Channels (Item 3A) spacing shall be reduced to 12 in. OC. When Item 6 (Fiber, Sprayed, Dry Dense Packed) is used, two layers of gypsum board required as described in Item 4. Not evaluated for use with

US GREENFIBER LLC — INS735, INS745, INS750LD, INS765LD, INS773LD, and SANCTUARY to be used with dry application only.

6A. Fiber, Sprayed\* — (Loose Fill 100% Borate Formulation) — (Not Shown, Optional) — The finished rating when Fiber, Sprayed is used has not been determined. The fiber is applied without water or adhesive at a minimum dry density of 0.5 lb/ft<sup>3</sup> and at a max thickness of 3-1/2 in.. in accordance with the application instructions supplied with the product. When Item 6A (Fiber, Sprayed, Loose Fill) is used, Furring Channels (Item 3F) or Resilient Channels (Item 3A) spacing shall be reduced to 12 in. OC. When Item 6A (Fiber Sprayed, Loose Fill) is used, two layers of gypsum board required as described in Item 4. Not evaluated for use with Item 3C. US GREENFIBER LLC — INS735, INS745, INS750LD, INS765LD, INS773LD. & SANCTUARY to be used with dry application only.

7. Batts and Blankets\* — (Not Shown) — For use with Item 3D — Nom 3 in. thick mineral wool insulation held suspended in the concealed space with 0.090 in. diam galv steel wires attached to the wood trusses at 18 in. OC. 7A. Batts and Blankets\* — For Use With Items 3F and 4B — Glass fiber insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance having a\_\_

min. density of 0.5 pcf, draped over the resilient channel/gypsum panel ceiling membrane. No

7B. Batts and Blankets\* — (Not Shown) — For use with Item 3E — Nom 3-1/2 in. thick, min. 2 oct fiber glass insulation held suspended in the concealed space with nominal 0.090 in. dian steel wires attached to the wood trusses at nominally 16 in. OC. 7C. Batts and Blankets\* or Fiber, Sprayed\* — For Use with Item 4C (Not Shown) — Min. 3-1

in thick with no limit on maximum thickness fitted in the concealed space, draped over the resilient channel (Item 3G)/gypsum board (Item 4C) ceiling membrane. 7D. **Batts and Blankets\*** — For Use With Item 4D — Insulation may be secured to plywood subfloor with staples spaced 12 in. OC or to the trusses with 0.090 in. diam galv steel wires spaced 12 in. OC. Insulation may alternatively be draped over the resilient channels and gypsun board ceiling membrane, and the resilient channels and gypsum board attachment shall be modified as specified in Item 4D. Any glass fiber insulation bearing the UL Classification Marking

for Surface Burning Characteristics and/or Fire Resistance, and having a min density of 0.5 pcf

and max thickness of 3-1/2 in. may be used. 7E. **Foamed Plastic\*** — (As alternate to Item 6 and 6A, Not Shown) — Spray foam insulation applied directly to the underside of the plywood subflooring. Spray foam insulation installed to a maximum thickness of 10 in, at a nominal 0.5 lb/ft<sup>3</sup> or 2.0 lb/ft<sup>3</sup> density, depending on the product installed. Spray foam insulation is limited to use with minimum 18 in. deep trusses (Item 2). When spray foam insulation is installed, resilient channels (Item 3A) shall be installed maximum 12 in. OC, with channels adjacent to butt joints of gypsum board (Item 4) spaced maximum 3 in. away from gypsum butt joints. Gypsum board (Item 4) to be installed using minimum 1-1/4 in. long Type S screws, spaced maximum 8 in. OC, and butted end joints shall be staggered min. 2 ft within the assembly, and occur midway between the continuous furring channels. If used with a fire damper (Item 9) in the concealed space, minimum 1 in, clearance to be maintained between damper housing and spray foam insulation. Not evaluated for use with Items 3, 3B through 3F, 3G, 6, 6A, 7 through 7D. Not evaluated with Flooring System (Item 1) Configuration No. 1. BASF CORP — Enertite® NM, Enertite® G, FE178®, Spraytite® 178, Spraytite® 81206,

Walltite® 200, Walltite® US, Walltite® US-N, and Walltite® HP+ 7F. Batts and Blankets\* — (Not Shown) For Use with Item 3I and 4C — Glass fiber or mineral wool insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance. There is no limit in the overall thickness of insulation, and the insulation can be secured against the subflooring, held suspended in the concealed space or draped over the Steel Framing Members and gypsum panel membrane.

7G. Batts and Blankets\* — (Not Shown) For Use with Item 3L, 3K, and 4F — Glass fiber or mineral wool insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance. There is no limit in the overall thickness of insulation, and the insulation can be secured against the subflooring, held suspended in the concealed space or\_ draped over the Steel Framing Members and gypsum panel membrane. 8. Air Duct\* — (Optional) — Any UL Class 0 or Class 1 flexible air duct installed in accordance with the instructions provided by the damper manufacturer.

9. **Ceiling Damper\*** — (Optional. To be used with Air Duct Item 8.) — For use with min. 18 in. deep trusses. Not for use with flooring system 1 or 17. Max. nom area shall be 349 sq in. Max. overall length and width shall not exceed 18-11/16 in. by 18-11/16 in. with max. 16 in. by 16 in. register opening. Aggregate damper openings shall not exceed 175 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. An aluminum or steel grille (Item 10) shall be installed in accordance with installation instructions.

MIAMI TECH INC — Model Series RxCRD, RxCRDS or RxCRPD 9A. Ceiling Damper\* — (Optional. To be used with Air Duct Item 8.) — For use with min. 18 in. deep trusses. Not for use with flooring system 1 or 17. Max damper assembly size nom 18 in. long by 18 in. wide and 4-1/4 in. high, or 8 in. diam. fabricated from galv steel. Aggregate damper openings shall not exceed 162 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper.

9C. Ceiling Damper\* — (Optional. To be used with Air Duct Item 8.) — For use with min. 18 in. deep trusses. Not for use with flooring system 1 or 17. Max 12 in. diameter damper with insulated register box assembly. The maximum size of the register box assembly is nom. 20 in. long by 20 in. wide and 4 in. high fabricated from galv steel. Aggregate area of the register opening(s) through the ceiling membrane shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper

AIRE TECHNOLOGIES INC — Series 57 9D. Ceiling Damper\* — (Optional. To be used with Air Duct Item 8.) — For use with min. 18 in deep trusses. Not for use with flooring system 1 or 17. Max 20 in. long by 16 in. wide by 4 in. high rectangular damper with duct board plenum box assembly. The maximum outer dimensions of the plenum box assembly are 23-1/2 in. long by 19-1/2 in. wide and 17 in. high fabricated from 6pcf, 1-1/2 to 2 in. thick Knauf Air Duct Board M\*. Aggregate area of the register opening(s) through the ceiling membrane shall not exceed 160 sq in. per 100 sq ft ceiling area. Damper

assembly installed in accordance with the manufacturers installation instructions.

PERMIT REVIEW STAMP **ISSUE HISTORY** Date Description 11/22/19 SCHEMATIC DESIGN 12/06/19 DESIGN DEVELOPMENT 02/28/20 PERMIT REVIEW SET **REVISION HISTORY** Date Description

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO

ROPERTY ADDRESS: 3777 OLD BERRY POINT

DB DESCRIPTION: New construction of a 3 sto

units. The building provi 30,455 GSF

DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851

COMPLIANCE WITH ALL APPLICABLE CODES

FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595

www.fuglebergkoch.com



THE ROBER1 FT. MYERS, FL

REFERENCE DIRECTORY - FLOOR SYSTEM

w/ Box or 51 w/Box 9F. Ceiling Damper\* — (Optional. To be used with Air Duct Item 8). — For use with min 18 in. deep trusses Not for use with flooring system 1 or 17. Max plenum box size nom 19 in. long by 19 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper.

**LLOYD INDUSTRIES INC** — Model CRD 50-BT, CRD 50-EA-BT, CRD 55-BT, CRD 55 EA-BT UNITED ENERTECH CORP — Model C-S/R-WT-L, C-S/R-EA-L, C-S/R-BT, C-S/R-EA-BL 9G. Ceiling Damper\* — (Optional. To be used with Air Duct Item 8). For use with min 18 in. deep trusses Not for use with flooring system 1 or 17. Max plenum box size nom 13 in. long by 13 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 50 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers

installation instructions provided with the damper. LLOYD INDUSTRIES INC — Model CRD 50-BT-6, CRD 50-EA-BT-6, CRD 55-BT-6, CRD 55

9H. Alternate Ceiling Damper\* — (Optional. To be used with Air Duct Item 8). Ceiling damper & fan assembly for use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 103 sq in. with the length not to exceed 10-1/8 in. and the width not to exceed 10-1/8 in. Aggregate damper openings shall not exceed 52 sq in. per 100 sq ft of ceiling area. Damper shall be installed in combination with one of the fan models described in, and in

accordance with, the manufacturer's installation instructions provided with the damper. A plastic grille (Item 10) shall be installed in accordance with installation instructions. PANASONIC CORPORATION, PANASONIC CORPORATION OF NORTH AMERICA — Model

9l. **Alternate Ceiling Damper\*** — (Optional. To be used with Air Duct Item 8). Ceiling damper & fan assembly for use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 113 sq in. with the length not to exceed 10-1/8 in. and the width not to exceed 11-1/8 in. Aggregate damper openings shall not exceed 57 sq in. per 100 sq ft of ceiling area. ■ Damper shall be installed in combination with one of the fan models described in, and in accordance with, the manufacturer's installation instructions provided with the damper. A plastic grille (Item 10) shall be installed in accordance with installation instructions.

**BROAN-NUTONE L L C** — Model RDFUWT

9J. Alternate Ceiling Damper\* — (Optional. To be used with Air Duct Item 8). Ceiling damper & fan assembly for use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 79 sq in. with the length not to exceed 10 in. and the width not to exceed 7-15/16 in. Aggregate damper openings shall not exceed 40 sq in. per 100 sq ft of ceiling area. Damper shall be installed in combination with one of the fan models described in, and in accordance with, the manufacturer's installation instructions provided with the damper. A metallic grille (Item 10) shall be installed in accordance with installation instructions. **BROAN-NUTONE L L C** — Models RDJ1 and RDH

9K. Alternate Ceiling Damper\* — (Optional. To be used with Air Duct Item 8). For use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max plenum box size nom 19 in. long by 19 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. **METAL-FAB INC** — Models MSCD-HC and MRCD-HC

9L. Alternate Ceiling Damper\* — (Optional, To be used with Air Duct Item 8). Ceiling damper & ■ fan assembly for use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 87 sq in. with the length not to exceed 9 in. and the width not to exceed 9-11/16 in. Aggregate damper openings shall not exceed 44 sq in. per 100 sq ft of ceiling area. Damper shall be installed in combination with one of the fan models described in, and in accordance with, the manufacturer's installation instructions provided with the damper. A plastic grille (Item 10) shall be installed in accordance with installation instructions. **BROAN-NUTONE L L C** — Model RDMWT

9M. Alternate Ceiling Damper\* — Ceiling damper & fan assembly for use with min 18 in. deep trusses. Max nom area shall be 87 sq in. with the length not to exceed 9 in. and the width not to exceed 9-11/16 in. Aggregate damper openings shall not exceed 44 sq in. per 100 sq ft of ceiling area. Damper shall be installed in combination with one of the fan models described in, and in accordance with, the manufacturer's installation instructions provided with the damper. A plastic grille (Item 10) shall be installed in accordance with installation instructions.

**BROAN-NUTONE L L C** — Model RDMWT2 9N. Alternate Ceiling Damper\* — (Optional. To be used with Air Duct Item 8) — For use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom 21 in. long by 18 in. wide, fabricated from galvanized steel. Plenum box max size nom 21 in. long by 18 in. wide by 14

in. high (inner dimension) fabricated from either galvanized steel or min 1 in. thick Listed Duct Board bearing the UL Listing Marking having a min R-Value of 4.3. Installed in accordance with • the instructions provided by the manufacturer. Max damper openings not to exceed 180 sq in. per 100 sq ft of ceiling area.

GREENHECK FAN CORP — Model CRD-1WT 90. Alternate Ceiling Damper\* — (Optional. To be used with Air Duct Item 8) — For use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom 12 in. long by 12 in. wide with an 8 in, diameter damper, fabricated from galvanized steel. Installed in accordance with the instructions provided by the manufacturer. Max damper openings not to exceed 72 sq in. per

100 sq ft of ceiling area. **GREENHECK FAN CORP** — Model CRD-2WT 9P. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 324 sq in. with the length not to exceed 24 in. and the width not to exceed 20 in. Max height of damper shall be 14 in. Aggregate damper openings shall not exceed 162 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the

manufacturers installation instructions provided with the damper. A steel grille (Item 10) shall be installed in accordance with installation instructions. **C&S AIR PRODUCTS** — Model RD-521

POTTORFF — Model CFD-521 9Q. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses. Not for use with flooring

installed in accordance with installation instructions.

**C&S AIR PRODUCTS** — Models RD-521-IP, RD-521-NP

system 1 or 17. Max nom area shall be 196 sq in. with the length not to exceed 26 in. and the width not to exceed 14 in. Max height of damper shall be 7 in. Aggregate damper openings shall not exceed 98 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. A steel grille (Item 10) not to exceed 144 in.<sup>2</sup> shall be installed in accordance with installation instructions.

**C&S AIR PRODUCTS** — Model RD-521-BT **POTTORFF** — Model CFD-521-BT

9R. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 256 sq in. with the length not to exceed 24 in. and the width not to exceed 20 in. Max height of damper shall be 17 in. Aggregate damper openings shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. A steel grille (Item 10) shall be

**POTTORFF** — Models CFD-521-IP, CFD-521-NP 9S. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses. Not for use with flooring system 1 or 17. Max nom area shall be 144 sq in. with the length not to exceed 14 in. and the

width not to exceed 12 in. Max height of damper shall be 17-7/8 in. Aggregate damper openings shall not exceed 74 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. A steel grille (Item 10) shall be installed in accordance with installation instructions. **C&S AIR PRODUCTS** — Models RD-521-90, RD-521-NP90

POTTORFF — Models CFD-521-90, CFD-521-90NP 9T. Alternate Ceiling Damper\* — (Optional. To be used with Air Duct Item 8.) — For use with Item 4D only. Not for use with flooring system 1. Max nom 8 in. diameter by 3-1/8 in. high, fabricated from galvanized steel. Plenum box max size nom 12 in. long by 12 in. wide by 3 in. high fabricated from galvanized steel. Installed in accordance with the instructions provided by the manufacturer. Max damper openings not to exceed 72 sq in. per 100 sq ft of ceiling area.

NAILOR INDUSTRIES INC — Types 0755, 0755A SAFE AIR DOWCO — Types 0455, 0455A 9U. **Damper\*** — (Optional, to be used with Air Duct Item 8) For use with min 18 in. deep trusses. Max nom 11-1/8 in. long by 13-5/8 in. wide, fabricated from galvanized steel. Installed in accordance with the instructions provided by the manufacturer. Max damper openings not to exceed 76 sq in. per 100 sq ft of ceiling area.

GREENHECK FAN CORP — Model CRD-310WT 10. **Grille** — Aluminum or Steel grille, installed in accordance with the installation instructions provided with the ceiling damper.

11. Discrete Products Installed in Air-handling Spaces\* — Automatic Balancing Valve/Damper — (Not Shown - Optional) — For use with item 9A, Ruskin Company's Model CFD7T damper (CABS). Ceiling damper to be provided with plenum box per damper manufacturer's instructions with side outlet only. Entire assembly to be installed into any UL Class 0 or Class 1 flexible air duct in accordance with the instructions provided by the automatic balancing valve/damper manufacturer.

METAL INDUSTRIES INC — Model ABV-4, ABV-5, ABV-6 \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2020-02-18



## Design No. L563

#### February 18, 2020


Unrestrained Assembly Rating - 1/2 Hr, 1 Hr (See item 1, System 1)

Finish Rating - 25 Min (See Items 5 or 5A and 7), 20 Min. (See Items 6E and 7A)

This design was evaluated using a load design method other than the Limit States Design Method (e.g., Working Stress Design Method). For jurisdictions employing the Limit States Design Method, such as

Canada, a load restriction factor shall be used — See Guide <u>BXUV</u> or <u>BXUV7</u> \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL

or cUL Certification (such as Canada), respectively.



ALTERNATE INSULATION PLACEMENT . Flooring System — The flooring system shall consist of one of the following:

**Subflooring** — Nom 23/32 in. thick wood structural panels installed perpendicular to trusses with end joints staggered. Plywood panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 3/4 in. thick loose laid over the subfloor. Floor shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral

resistance strength may be substituted for the 6d nails. Vapor Barrier - (Optional) — Nom 0.030 in. thick commercial asphalt saturated felt. Finish Flooring — Min 1 by 4 in. T & G lumber fastened diagonally to trusses, or min 15/32 in. thick wood structural to trusses with joints staggered.

System No. 2 - Subflooring — Min 23/32 in. thick T & G wood structural panels installed perpendicular to trusses with | KEENE BUILDING PRODUCTS CO INC — Quiet Qurl 55/025 MT and Quiet Qurl 55/025 N MT end joints staggered 4 ft. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails.

Floor Mat Materials\* - (Optional) — Floor mat material nom 5/64 in. (2 mm) thick adhered to subfloor with Hacker Floor Primer. Primer to be applied to the surface of the mat prior to the placement of a min 1 in. of floor-topping mixture. | See Perlite Aggregate (CFFX) and Vermiculite Aggregate (CJZZ) categories for names of manufacturers. **ECORE INTERNATIONAL INC** — Type QTscu 4002 **HACKER INDUSTRIES INC** — Type Hacker Sound-Mat

Alternate Floor Mat Materials - (Optional) — Floor mat material nom 1/4 in. (6 mm) thick adhered to subfloor with floor-topping mixture. **ECORE INTERNATIONAL INC** — Type QTrbm 3006-3

**HACKER INDUSTRIES INC** — Type Hacker Sound-Mat II. Alternate Floor Mat Materials - (Optional)— Floor mat material nom 1/8 in. (3 mm) thick loose laid over the subfloor Floor topping thickness shall be a min of 3/4 in. (19 mm) HACKER INDUSTRIES INC — FIRM-FILL SCM 125

Alternate Floor Mat Materials - (Optional)— Floor mat material nom 1/4 in. (6 mm) thick loose laid over the subfloor. Floor topping thickness shall be a min of 1 in. (25 mm) HACKER INDUSTRIES INC — Type FIRM-FILL SCM 250, Quiet Qurl 55/025

Alternate Floor Mat Materials - (Optional)— Floor mat material nom 3/8 in. (10 mm) thick loose laid over the subfloor. | fabric attached to the bottom loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in. Floor topping thickness shall be a min of 1-1/4 in. (32 mm) HACKER INDUSTRIES INC — FIRM-FILL SCM 400, Quiet Qurl 60/040

Alternate Floor Mat Materials - (Optional) — Floor mat material nom 3/4 in. (19 mm) thick loose laid over the subfloor. Floor topping thickness shall be a min of 1-1/2 in. (38 mm) HACKER INDUSTRIES INC — Type FIRM-FILL SCM 750. Quiet Qurl 65/075

Metal Lath (Optional) — For use with 3/8 in. (10 mm) floor mat materials, 3/8 in. expanded steel diamond mesh, 3.4 lbs/sq yd placed over the floor mat material. Hacker Floor Primer to be applied prior to the placement of the metal lath. When metal lath is used, floor topping thickness a nom 1-1/4 in. over the floor mat. Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive

strength of 1100 psi. Mixture shall consist of 6.8 gal of water to 80 lbs of floor topping mixture to 1.9 cu ft of sand. HACKER INDUSTRIES INC -Firm-Fill Gyp Conc, Firm-Fill 2010, 3310,4010, Firm-Fill High Strength, Gyp-Span Radiant strength of 1000 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. end joints staggered 4 ft. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples

having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Finish Floor - Mineral and Fiber Board\* — Min 1/2 in. thick, supplied in sizes ranging from 3 ft by 4 ft to 8 ft by 12 ft. All joints to be staggered a min of 12 in. with adjacent sub-floor joints. **HOMASOTE CO** — Type 440-32 Mineral and Fiber Board

System No. 4 Subflooring — Min Nom 23/32 in. thick wood structural panels installed perpendicular to trusses with end joints staggered. Plywood or panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal | Vapor Barrier — (Optional) — Nom 0.030 in. thick commercial asphalt saturated felt. and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails.

**Vapor Barrier - (Optional)** — Nom 0.010 in. thick commercial asphalt saturated felt. Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a minimum compressive strength of 1800 psi. Refer to manufacturer's instruct. accompanying the material for specific mix design. UNITED STATES GYPSUM CO — Types LRK, HSLRK, CSD

LATICRETE SUPERCAP L L C — Types LRK, HSLRK USG MEXICO S A DE C V — Types LRK, HSLRK, CSD Floor Mat Materials\* — (Optional) - Floor mat material loose laid over the subfloor. Refer to manufacturer's instructions | KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 60/040 and Quiet Qurl 60/040 N regarding the minimum thickness of floor topping over each floor mat material. UNITED STATES GYPSUM CO — Types SAM, LEVELROCK® Brand Sound Reduction Board, LEVELROCK® Brand | topping thickness shall be a minimum of 1-1/2 in.

Floor Underlayment SRM-25 Alternate Floor Mat Materials\* - (Optional) — Nom 3/8 in. thick floor mat material loose laid over the subfloor. **GRASSWORX L L C** — Type SC50

end joints staggered 4 ft. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. **Vapor Barrier - (Optional)** — Nom 0.030 in. thick commercial asphalt saturated felt.

Finish Flooring - Floor Topping Mixture\* — Min 1-1/2 in. thickness of floor topping mixture having a min compressive strength of 1000 psi and a cast density of 100 plus or minus 5 pcf. Foam concentrate mixed 40:1 by volume with water and expanded at 100 psi through nozzle. Mixture shall consist of 1.4 cu feet of preformed foam concentrate to 94 lbs Type I Portland cement, 300 lbs of sand with 5-1/2 gal of water. **ELASTIZELL CORP OF AMERICA** — Type FF

System No. 6 Deleted. System No. 7 - Subflooring — Min 23/32 in. thick T & G wood structural panels installed perpendicular to trusses with | being sealed with any UL Classified caulk or sealant found under - Fill, Void or Cavity Materials\* (XHHW). end joints staggered 4 ft. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails.

**Vapor Barrier - (Optional)** — Nom 0.030 in. thick commercial asphalt saturated felt. Finish Flooring - Floor Topping Mixture\* — Min 1-1/2 in. thickness of floor topping mixture having a min compressive strength of 1000 psi and a cast density of 100 plus or minus 5 pcf. Foam concentrate mixed 40:1 by volume with water and expanded at 100 psi through nozzle. Mixture shall consist of 1.2 cu feet of preformed foam concentrate to 94 lbs Type I Portland cement, 300 lbs of sand with 5.5 gal of water. **AERIX INDUSTRIES** — Floor-Topping Mixture

System No. 8 - Subflooring — Min 23/32 in. thick T & G wood structural panels installed perpendicular to trusses with | ECTEK INTERNATIONAL INC — Type MegaBoard end joints staggered 4 ft. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. | Vapor Barrier - (Optional) — Nom 0.030 in. thick commercial asphalt saturated felt. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails.

Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive strength of 1000 psi. Mixture shall consist of 5 to 8 gal of water to 80 lbs of floor topping mixture to 2.1 cu ft of sand. ULTRA QUIET FLOORS — Types UQF-A, UQF-Super Blend, UQF-Plus 200

System No. 9 - Subflooring — Min 23/32 in. thick T & G wood structural panels installed perpendicular to trusses with joints staggered 4 ft. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ring shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 | located 1/2 in. from the end edges of the panel. in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or UNITED STATES GYPSUM CO — Types STRUCTO-CRETE, USGSP greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Vapor Barrier - (Optional) — Nom 0.030 in. thick commercial asphalt saturated felt.

Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a minimum compressive strength of 1500 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. **MAXXON CORP** — Type Maxxon Standard and Maxxon High Strength Floor Mat Materials\* - (Optional) — Floor mat material loose laid over the subfloor. Refer to manufacturer's instructions

recarding the minimum thickness of floor topping over each floor mat material. **MAXXON CORP** — Type Encapsulated Sound Mat. Floor Mat Reinforcement — (Optional) Refer to manufacturer's instructions regarding minimum thickness of floor topping | SIKA DEUTSCHLAND GMBH — Type SCHONOX AP Rapid Plus

for use with floor mat reinforcement. Metal Lath - (Optional) 3/8 in. expanded galvanized steel diamond mesh, 3.4 lbs/sq yd loose laid over the floor mat

Fiber Glass Reinforcement — (Optional) - 0.015 in. thick PVC coated non-woven fiberglass mesh, 0.368 lbs./sq. yd

loose laid over the floor mat material. System No. 10 - Subflooring — Min 23/32 in. thick plywood with T & G edges along the 8 ft sides and exterior glue, or non-veneer APA Rated "Sturd-I-Floor" T & G panels per APA specifications PRP-108. Plywood or non-veneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength | 4. Ceiling Damper\* (Optional). To be used with Air Duct Item 3. — For use with min 18 in. deep trusses Max plenum may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails.

Vapor Barrier — (Optional) Nom 0.030 in. thick commercial asphalt saturated felt. Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive strength of 1000 psi. Refer to manufacturer's instructions accompanying the material for specific mix design.

FORMULATED MATERIALS LLC — Types FR-25, FR-30, and SiteMix Floor Mat Material\* — (Optional) Floor mat material nominal 2 - 9.5 mm thick loose laid over the subfloor. Floor topping shall be a min of 3/4 in. FORMULATED MATERIALS LLC — Types M1, M2, M3, Elite, Duo, R1, and R2

System No. 11- Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of plywood or strength axis of panels to be perpendicular to the joists with joints staggered. **Vapor Barrier** — (Optional) - Commercial asphalt saturated felt, 0.030 in. thick.

**Vapor Barrier** — (Optional) - Nom 0.010 in. thick commercial rosin-sized building paper. Finish Flooring\* — Min 3/4 in. thickness of any Floor Topping Mixture bearing the UL Classification Marking as to Fire Resistance. See Floor- and Roof-Topping Mixtures (CCOX) category for names of Classified Companies. Floor Mat Materials\* — (Optional) - Nom. 1/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a

**KEENE BUILDING PRODUCTS CO INC** — Type Quiet Qurl 55/025 and Quiet Qurl 55/025 N Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 3/8 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 60/040 and Quiet Qurl 60/040 N

topping thickness shall be a minimum of 1-1/2 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 65/075, Quiet Qurl 65/075 N Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 1/8 in. thick loose laid over the subfloor. Floor

topping thickness shall be a minimum of 3/4 in. KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 52/013 and Quiet Qurl 52/013 N panels, min grade "Underlayment" or "Single Floor". Face grain of plywood or strength axis of panel to be perpendicular | Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 1/4 in. entangled net core with a compressible

fabric attached to the bottom loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in. System No. 12 - Subflooring — Min 23/32 in. thick wood structural panels, min grade "C-D" or "Sheathing". Face grain of 100 sq ft of ceiling area. Installed in accordance with the manufacturers installation instructions provided with the damper. plywood or strength axis of panels to be perpendicular to the joists with joints staggered.

**Vapor Barrier** — (Optional) - Nom 0.010 in. thick commercial rosin-sized building paper. Finish Flooring — Min 3/4 in. thickness of lightweight insulating concrete with Perlite Aggregate\* or Vermiculite Aggregate\*, or gypsum concrete.

**Vapor Barrier** — (Optional) - Commercial asphalt saturated felt, 0.030 in. thick.

Floor Mat Materials\* — (Optional) - Nom. 1/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a

KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 55/025 and Quiet Qurl 55/025 N Hacker Floor Primer. Primer to be applied to the surface of the mat prior to the placement of a min 1-1/4 in. (32 mm) of Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 3/8 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 60/040 and Quiet Qurl 60/040 N

Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 3/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 1-1/2 in KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 65/075, Quiet Qurl 65/075 N

Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 1/8 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in. **KEENE BUILDING PRODUCTS CO INC** — Type Quiet Qurl 52/013 and Quiet Qurl 52/013 N

Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 1/4 in. entangled net core with a compressible KEENE BUILDING PRODUCTS CO INC — Quiet Qurl 55/025 MT and Quiet Qurl 55/025 N MT

System No. 13 Subflooring — Min 23/32 in. thick plywood with T & G edges along the 8 ft sides and exterior glue, or nonveneer APA Rated "Sturd-I-Floor" T& G panels per APA specifications PRP-108. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal & lateral resistance strength may be substituted for 6d nails.

**Vapor Barrier** — (Optional) — Nom 0.030 in. thick commercial asphalt saturated felt. Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive System No. 3 - Subflooring — Min 23/32 in. thick T & G wood structural panels installed perpendicular to trusses with ACG MATERIALS — AccuCrete types NexGen, Green, Prime, B, M, and PrePour, AccuRadiant, AccuLevel types G40,

Floor Mat Material\* — (Optional) — Floor mat material nominal 2 - 9.5 mm thick loose laid over the subfloor. Floor topping shall be a min of 3/4 in.

EM.375S, EM.750, and EM.750S. System No. 14 - Subflooring — Min 23/32 in. thick plywood with T & G edges along the 8 ft sides and exterior glue, or nonveneer APA Rated "Sturd-I-Floor" T & G panels per APA specifications PRP-108. Plywood or nonveneer APA rated panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with

may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Finish Flooring - Floor Topping Mixture\* — Min 3/4 in. thickness of floor topping mixture having a min compressive strength of 1000 psi. Refer to manufacturer's instructions accompanying the material for specific mix design. **DEPENDABLE LLC** — GSL M3.4, GSL K2.6, GSL-CSD and GSL RH.

Floor Mat Materials\* — (Optional) - Nom. 1/4 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in. **KEENE BUILDING PRODUCTS CO INC** — Type Quiet Qurl 55/025 and Quiet Qurl 55/025 N Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 3/8 in. thick loose laid over the subfloor. Floor

topping thickness shall be a minimum of 1 in Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 3/4 in. thick loose laid over the subfloor. Floor KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 65/075, Quiet Qurl 65/075 N

Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 1/8 in. thick loose laid over the subfloor. Floor topping thickness shall be a minimum of 3/4 in System No. 5 - Subflooring — Min 23/32 in. thick T & G wood structural panels installed perpendicular to trusses with KEENE BUILDING PRODUCTS CO INC — Type Quiet Qurl 52/013 and Quiet Qurl 52/013 N Alternate Floor Mat Materials\* — (Optional) - Floor mat material Nom. 1/4 in. entangled net core with a compressible

> fabric attached to the bottom loose laid over the subfloor. Floor topping thickness shall be a minimum of 1 in. KEENE BUILDING PRODUCTS CO INC — Quiet Qurl 55/025 MT and Quiet Qurl 55/025 N MT System No. 15 - Subflooring — Min 15/32 in. thick wood structural panels, min grade "Underlayment" or "Single-Floor". Face grain of plywood or strength axis of panel to be perpendicular to joists with joints staggered. Plywood or non-veneer APA rated panels secured to trusses w/ const. adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. Wall and Partition Facings and Accessories\* - Sound Barrier (Optional) — Acoustic Sleeper pads stapled to the top of the subfloor and centered over wood trusses. Acoustic Sleeper pads are to be spaced appropriately so that the finish

> STC ARCHITECTURAL PRODUCTS L L C DBA STC SOUND CONTROL — Acoustic Sleeper Finish Floor — Min 15/32 in. thick wood structural panels, min grade "Underlayment" or "Single-Floor". Face grain of plywood or strength axis of panel to be perpendicular to joists with joints staggered. Butt joints of panels have the option of System No. 16 - Subflooring - Structural Cement-Fiber Units\* — Nominal 19 mm (3/4 in.) thick tongue and groove structural cement-fiber units. Long dimension of panels to be perpendicular to trusses with end joints staggered. Panels OC along the perimeter of each sheet and 12 in. OC in the field of each sheet. Screws shall be spaced 1/2 in. from end ioints and 1 in, from side ioints.

floor panels are fastened through Acoustic Sleeper pads to trusses

**ECTEK INTERNATIONAL INC** — Armoroc Panel Subflooring (Alternate) — Building Units\* — Nom 3/4 in. thick, tongue and grooved boards. Long dimension of boards | clips required to hold furring channel that supports the gypsum board butt joints, as described in Item 7. to be perpendicular to trusses with end joints staggered a min of 4 ft. and centered over the trusses. Boards secured to PAC INTERNATIONAL L L C — Types RSIC-1, RSIC-1 (2.75). trusses with 1-1/4 in. long self-drilling, self- tapping screws spaced a max of 12 in. OC in the field with screws located 1 in. 6D. Alternate Steel Framing Members\* — (Not Shown) As an alternate to items 6 to 6C, furring channels and Steel from long edge, and max 8 in. OC along the end joints with screws located 1/2 in. from end joint.

Finish Flooring — Min 1 by 4 in. T & G lumber fastened diagonally to trusses, or min 15/32 in. thick wood structural panels, min grade "Underlayment" or "Single Floor". Face grain of plywood or strength axis of panel to be perpendicular to trusses with joints staggered.

System No. 17 Structural Cement-Fiber Units\* — For use with UNITED STATES GYPSUM CO Types C, IP-X2, IPC-AR and ULIX gypsum boards only. Nom 3/4 in. thick, with long edges tongue and grooved. Long dimension of panels to be perpendicular to wood trusses with end joints staggered a min of 2 ft and centered over the trusses. Panels secured to wood trusses with 1-5/8 in. long, No. 8, self- countersinking wood screw spaced a max of 12 in. OC in the field with a screw located 1 in. and 2 in. from each edge, and 8 in. OC on the perimeter with a screw located 2 in. from each edge,

Subflooring — Nom 23/32 in. thick wood structural panels installed perpendicular to trusses with end joints staggered. Plywood panels secured to trusses with construction adhesive and No. 6d ringed shank nails spaced 12 in. OC along each truss. TetraGRIP™ nails measuring 2-3/8 in. long, 0.113 in. diameter, 0.272 in. round head, and helically threaded shank with barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails. Staples having equal or greater withdrawal and lateral resistance strength may be substituted for the 6d nails.

Finish Flooring - Floor Topping Mixture\* — Min 1 in. thickness of floor topping mixture having a min compressive strength of 4500 psi. Refer to manufacturer's instructions accompanying the material for specific mix design.

2. Trusses — Parallel chord trusses, spaced a max of 24 in. OC, fabricated from nom 2 by 4 lumber, with lumber oriented vertically or horizontally. Min truss depth is 12 in. when Ceiling Dampers\* are not used. Min truss depth is 18 in. when Ceiling Damper\* is used. Truss members secured together with min 0.036 0356 in. thick galvanized steel plates. Plates have 5/16 in. long teeth projecting perpendicular to the plane of the plate. The teeth are in pairs facing each other made by the same punch), forming a split tooth type plate. Each tool has a chisel point on its outside edge. These points are diagonally opposite each other for each pair. The top half of each tooth has a twist for stiffness. The pairs are repeated on approx. 7/8 in. centers with four rows of teeth per inch of plate width.

3. Air Duct\* (Optional) — Any UL Class 0 or Class 1 flexible air duct installed in accordance with the instructions provided by the damper manufacturer.

box size nom 19 in. long by 19 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper

AIRE TECHNOLOGIES INC — Models: CRD model 50 w/Boot, CRD model 50EA w/Boot, CRD model 55 w/Boot, CRD model 55 EA w/Boot. LLOYD INDUSTRIES INC — Model CRD 50-BT, CRD 50-EA-BT, CRD 55-BT, CRD 55 EA-BT

UNITED ENERTECH CORP — Model C-S/R-WT-L, C-S/R-EA-L, C-S/R-BT, C-S/R-EA-BL 4A. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses Max plenum box size nom 13 in. long by 13 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 50 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. LLOYD INDUSTRIES INC — Model CRD 50-BT-6, CRD 50-EA-BT-6, CRD 55-BT-6, CRD 55 EA-BT-6, CRD50-W X-BT-

4B. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses Max size ceiling outlet in plenum box nom 12 in. long by 12 in. wide. Plenum box fabricated from galv steel. Aggregate damper openings shall not exceed 72 sq in. per 100 sq ft of ceiling area. Installed in accordance with the manufacturers installation instructions provided with the damper. AIRE TECHNOLOGIES INC — Models: CRD model 50 w/Boot, CRD model 50EA w/Boot, CRD model 55 w/Boot, CRD

LLOYD INDUSTRIES INC — Model CRD 50-95BT, CRD 50-EA-95BT, CRD 55-95BT, CRD 55 EA-95BT 4C. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses. Max size ceiling outlet in plenum box nom 16 in. long by 16 in. wide. Aggregate damper openings shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. CROWN PRODUCTS CO INC — Models CRD50-FGPB-4.2-CP, -6.0-CP; CRD50-FGPB-4.2-EA-CP, -6.0-EA-CP.

**LLOYD INDUSTRIES INC** — Models CRD 50- FGPB-4.2, - 4.2 NI, -6.0, -6.0 NI; CRD50-EA-FGPB-4.2, -4.2 NI, -6.0, -4D. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses Max plenum box size nom 15 in. long by 15 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 72 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper.

**LLOYD INDUSTRIES INC** — Models 45-CRD-LT-BT and 45-CRD-LTD-BT 4E. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses Max size ceiling outlet in plenum box nom 10 in. long by 10 in. wide. Plenum box fabricated from galv steel. Aggregate damper openings shall not exceed 50 sq in. per

LLOYD INDUSTRIES INC — Model 45-LTD-95-BT-4 4F. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses Max plenum box size nom 19 in. long by 15 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 96 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. LLOYD INDUSTRIES INC — Model CRD50-w X-BT

4G. Alternate Ceiling Damper\* — For use with min. 18 in. deep trusses. Max. nom area shall be 349 sq in. Max. overall length and width shall not exceed 18-11/16 in. by 18-11/16 in. with max. 16 in. by 16 in. register opening. Aggregate damper openings shall not exceed 175 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper. An aluminum or steel grille (Item 9) shall be installed in accordance with installation instructions.

MIAMI TECH INC — Model Series RxCRD, RxCRDS or RxCRPD 4H. Alternate Ceiling Damper\* — For use with min 18 in. deep trusses Max plenum box size nom 19 in. long by 19 in. wide and 11-7/8 in. high fabricated from galv steel. Aggregate damper openings shall not exceed 128 sq in. per 100 sq ft of ceiling area. Damper installed in accordance with the manufacturers installation instructions provided with the damper **METAL-FAB INC** — Models MSCD-HC and MRCD-HC

5. Batts and Blankets\* — (Optional) - Glass fiber or mineral wool insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance. When no insulation is installed in the concealed space resilient channels (Item 6) are spaced 24 in. OC. When the resilient channels (Item 6) are spaced 16 in. OC, the insulation shall be a max of 3-1/2 in. thick, and shall be secured against the subflooring with staples at 12 in. OC or held suspended in the concealed space with 0.090 in. diam galv steel wires attached to the wood trusses at 12 in. OC. When the resilient channels are spaced a max of 12 in. OC or when the Steel Framing Members (Item 6A) are used, there is no limit in the overall thickness of insulation, and the insulation can be secured against the subflooring, held suspended in the concealed space or draped over the resilient channels (or Steel Framing Members) and gypsum panel membrane. The

finished rating has only been determined when the insulation is secured to the subflooring. 5A. Loose Fill Material\* — (Optional) - As an alternate to Item 5, when the resilient channels (Item 6) are spaced a ma of 12 in. OC, or when the Steel Framing Members (Item 6A) are used - Any loose fill material bearing the UL Classification Marking for Surface Burning Characteristics. There is no limit in the overall thickness of insulation. The

finished rating when loose fill material is used has not been determined 5B. Cavity Insulation - Batts and Blankets\* or Loose Fill Material\* - (Not Shown) — (As described above in Items 5 and 5A) — For Use with Item 7A — Min. 3-1/2 in thick with no limit on maximum thickness fitted in the concealed space. draped over the resilient channel (Item 6E)/gypsum board (Item 7A) ceiling membrane. 6. Resilient Channels — Formed from min 25 MSG galv steel installed perpendicular to the trusses. When insulation

(Item 5) is secured to the underside of the subfloor, the resilient channels are spaced 16 in. OC. When insulation (Items 5 or 5A) is applied over the resilient channel/gypsum panel ceiling membrane, the resilient channels are spaced 12 in. OC. Channels secured to each truss with 1-1/4 in. long Type S bugle head steel screws. Channels overlapped 4 in. at splices. ACG MATERIALS — AccuQuiet types P80, C40, D13, D-18, D25, DX38, EM.125, EM.125S, EM.250S, EM.375, Two channels, spaced 6 in. OC, oriented opposite each gypsum panel end joint as shown in the above illustration. Additional channels shall extend min 6 in. beyond each side edge of panel. 6A. Alternate Steel Framing Members — (Not Shown) - As an alternate to Items 6, main runners, cross tees, cross

channels and wall angle as listed below: A. Main Runners — Nom 10 or 12 ft long, 15/16 in. or 1-1/2 in. wide face, spaced 4 ft. OC. Main runners suspended by min 12 SWG galv steel hanger wires spaced 48 in. OC. Hanger wires to be located adjacent to main runner/cross tee barbed features on the helix meeting ASTM F1667 and having equal or greater withdrawal and lateral resistance strength intersections. Hanger wires wrapped and twist-tied on 16d nails driven in to side of trusses at least 5 in. above the bottom

> B. Cross Tees — Nom 4 ft long, 1-1/2 in. wide face, installed perpendicular to the main runners, spaced 16 in. OC. Additional cross tees or cross channels used at 8 in. from each side of butted gypsum panel end joints. The cross tees or cross channels may be riveted or screw attached to the wall angle or channel to facilitate the ceiling installation. C. Cross Channels — Nom 4 or 12 ft long, installed perpendicular to main runners, spaced 16 in. OC. D. Wall Angle or Channel — Painted or galv steel angle with 1 in. legs or channel with 1 in. legs, 1-9/16 in. deep attached to walls at perimeter of ceiling with fasteners 16 in. OC. To support steel framing member ends and for screwattachment of the gypsum panel.

**CGC INC** — Type DGL or RX. **USG INTERIORS LLC** — Type DGL or RX.

6B. **Steel Framing Members\*** — (Not Shown) — As an alternate to Items 6 and 6A. a. Furring Channels — Formed of No. 25 MSG galv steel, 2-3/8 in. wide by 7/8 in. deep, spaced 16 in. OC

panel ceiling membrane, the furring channel spacing shall be reduced to 12 in. OC. Channels secured to trusses as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galvanized steel wire near each end of overlap. b. Steel Framing Members\* — Used to attach furring channels (Item a) to trusses (Item 2). Clips spaced 48 in. OC, and secured to the bottom chord of alternating trusses with one No. 8 x 2-1/2 in. coarse drywall screw through center grommet. When insulation, Items 5 or 5A is applied over the furring channel/gypsum panel ceiling membrane, the clip

perpendicular to wood structural members. When insulation, Items 5 or 5A is applied over the furring channel/gypsum

spacing shall be reduced to 24 in. OC and secured to consecutive trusses. Furring channels are friction fitted into clips. Adjoining channels are overlapped as described in Item a. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping No. 6 framing screws, min 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Additional clips required to hold furring channel that supports the gypsum board butt joints, as described in Item 7. PLITEQ INC — Type Genie Clip

6C. Steel Framing Members\* — (Not Shown) - As an alternate to Items 6, 6A and 6B. a. Furring Channels — Formed of No. 25 MSG galv steel, 2-9/16 in. or 2-23/32 in. wide by 7/8 in. deep, spaced 16 in. OC perpendicular to wood structural members. When insulation, Items 5 or 5A is applied over the furring channel/gypsum panel ceiling membrane, the furring channel spacing shall be reduced to 12 in. OC. Channels secured to trusses as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No.

18 AWG galv steel wire near each end of overlap. b. Steel Framing Members\* — Used to attach furring channels (Item a) to trusses (Item 2). Clips spaced 48 in. OC. RSIC-1 and RSIC-1 (2.75) clips secured to alternating trusses with No. 8 x 2-1/2 in. course drywall screw through the fastened to the trusses with #10 self-drilling, self-tapping cement board screws 1-3/4 in. long. Screws shall be spaced 6 in. | center grommet. Furring channels are friction fitted into clips. RSIC-1 clips for use with 2-9/16 in. wide furring channels. RSIC-1 (2.75) clips for use with 2-23/32 in. wide furring channels. Adjoining channels are overlapped as described in Item a. As an alternate, ends of adjoining channels may be overlapped 6 in. and secured together with two self-tapping No. 6 framing screws, min 7/16 in. long at the midpoint of the overlap, with one screw on each flange of the channel. Additional

Framing Members as described below.

a. Furring Channels — Formed of No. 25 MSG galv steel, 2-5/8 in. wide by 7/8 in deep, spaced 16 in OC perpendicular to wood structural members. When insulation, Items 5 or 5A is applied over the furring channel/gypsum panel ceiling membrane, the furring channel spacing shall be reduced to 12 in. OC. Channels secured to trusses as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galv steel wire near each end of overlap.

b. Steel Framing Members\* — Used to attach furring channels (Item a) to the trusses (Item 2). Clips spaced at 48" OC and secured to the bottom of the trusses with one 2 in. Coarse Drywall Screw with 1 in. diam washer through the center hole. Furring channels are then friction fitted into clips. Ends of channels are overlapped 6" and tied together with double strand of No. 18 AWG galvanized steel wire. Additional clips are

required to hold the Gypsum Butt joints as described in item 7. STUDCO BUILDING SYSTEMS — RESILMOUNT Sound Isolation Clips - Type A237R

6E. Resilient Channels - (Not Shown) — For Use With Item 7A - Formed from min 25 MSG galv steel installed perpendicular to trusses and spaced 16 in. OC. Channels secured to each truss with 1-5/8 in. long Typ S bugle head steel screws. Channels overlapped 4 in. at splices. Two channels, spaced 6 in. OC, oriented opposite each gypsum panel end joint. Additional channels shall extend min 6 in. beyond each side edge of panel. Insulation, Item 5B is applied over the resilient channel/gypsum panel (Item 7A) ceiling membrane.

Steel Framing Members as described below.

a. Furring Channels — Formed of No. 25 MSG galv steel, 2-1/2 in. wide by 7/8 in deep, spaced 16 in OC, perpendicular to wood structural members. When insulation, Items 5 or 5A is applied over the furring channel/gypsum panel ceiling membrane, the furring channel spacing shall be reduced to 12 in. OC. Channels secured to trusses as described in Item b. Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 AWG galv steel wire near each end of overlap. b. Steel Framing Members\* — Used to attach furring channels (Item a) to the trusses (Item 2). Clips spaced at 48" OC and secured to the bottom of the trusses with one 2-1/2 in. Coarse Drywall Screw with 1 in. diam washer through the center hole. Furring channels are then friction fitted into clips. Ends of channels are overlapped 6" and tied together with double strand of No. 18 AWG galvanized steel wire. Additional clips are required to hold the Gypsum Butt joints as described in item 7.

6F. Alternate Steel Framing Members\* — (Not Shown) As an alternate to items 6 to 6E, furring channels and

**REGUPOL AMERICA** — Type SonusClip 6G. **Steel Framing Members\*** — — (Optional, Not Shown) — As an alternate to Item 6. a. Furring Channels — Formed of No. 25 MSG galv steel, nominal 2-1/2 in. wide by 7/8 in. deep, spaced as indicated in Item 6, perpendicular to the trusses. Channels secured to Cold Rolled Channels at every intersection with a 3/4 in. TEK screw through each furring channel leg. Ends of adjoining channels overlapped 12 in. and fastened together with two double strand No. 18 SWG galv steel wire ties, one at each end of overlap, or with two 3/4 in. TEK screws in each leg of the overlap section. Two furring channels used at end joints of gypsum board (Item 7), each extending a min of 6 in. beyond both side edges of the board. b. Cold Rolled Channels — 1-1/2 in. by 1/2 in., formed from No. 16 ga. galv steel, positioned vertically and parallel to trusses, friction-fitted into the channel caddy on the Steel Framing Members (Item 6Gd) and secured with two 3/4 in. TEK screws. Adjoining lengths of cold rolled channels lapped min. 12 in. and secured along bottom legs with four 3/4 in. TEK screws and wire-tied together with two double strand 18 SWG galv steel wire ties, one at each end of overlap.

c. **Blocking** — Where truss design does not permit direct, full contact of the hanger bracket, a piece of nominal 2 by 4 in. lumber (blocking), min. 12 in. long to permit full contact of the hanger bracket, to be secured vertically to the side of the trusses at the top and bottom of the blocking at each Steel Framing Member (Item 6Gd) location with 16d nails or minimum 2-1/2 in. screws. d. Steel Framing Members\* — Spaced 48 in. OC. max along truss, and secured to the truss on alternating

trusses with two, #10 x 1-1/2 in. screws through mounting holes on the hanger bracket. PAC INTERNATIONAL L L C — Type RSIC-SI-CRC EZ Clip 6H. Steel Framing Members\* — (Not Shown) — As an alternate to Item 6. a. Furring Channels — Formed of No. 25 MSG galv steel, nominal 2-1/2 in. wide by 7/8 in. deep, spaced as indicated in Item 6, perpendicular to trusses and friction fit into Steel Framing Members (Item 6Hc). Ends of adjoining channels overlapped 6 in. and tied together with double strand of No. 18 SWG galv steel wire near each end of overlap or with two TEK screws along each leg of the 6 in. overlap. Two furring channels used at end joints of gypsum board (Item 7). Butt joint channels held in place by strong back channels placed upside down, on top of, and running perpendicular to primary furring channels, extending 6 in. longer than length of gypsum side joint. Strong back channels spaced maximum 48 in. OC. Strong back channels secured to every intersection of primary furring channels with four 7/16 in. pan head screws, two along each of the legs at

at intersection with strong back channels. b. **Blocking** — Where truss design does not permit direct, full contact of the hanger bracket, a piece of nominal 2 by 4 in. lumber (blocking), min. 12 in. long to permit full contact of the hanger bracket, to be secured vertically to the side of the trusses at the top and bottom of the blocking at each Steel Framing Member (Item 6Hc) location with 16d nails or minimum 2-1/2 in. screws. c. Steel Framing Members\* — Used to attach furring channels (Item 6Ha) to trusses. Clips spaced 48 in. OC

intersections. Butt joint channels run perpendicular to strong back channels and shall be minimum 6 in. longer

than length of joint, secured to strong back channels with 7/16 in. pan head screws, two along each of the legs

and secured along truss webs at each furring channel intersection with min. 3/4 in. long self-drilling #10 x 1-1/2 in. screws through each of the provided hole locations. Furring channels are friction fitted into clips. PAC INTERNATIONAL L L C — Type RSIC-S1-1 Ultra 61. Steel Framing Members\* — (Optional - Not Shown) — Used to attach resilient channels (Item 6) to trusses (Item 2). Clips spaced 48 in. OC and secured to trusses with one No. 8 x 2-1/2 in. coarse drywall screw through center grommet hole. Channels secured to clips with one #10 x 1/2 in. pan-head self-drilling screw. Ends of adjoining channels overlapped 6 in. and secured together with two #8 15 x 1/2 in. Philips Modified screws spaced 2-1/2

in. from the center of the overlap. Gypsum board butt joints require additional resilient channels spaced 1-1/2 in. from the butt joint on either side. One edge of the extra channels will extend to an adjacent truss where it is secured w/ a cli **KEENE BUILDING PRODUCTS CO INC** — Type RC+ Assurance Clip 7. **Gypsum Board\*** — Nom 5/8 in. thick, 48 in. wide gypsum panels. When resilient channels (Item 6) are used, gypsum panels installed with long dimension perpendicular to resilient channels. Gypsum panels secured with 1 in. ong Type S bugle head steel screws spaced 12 in. OC and located a min of 1/2 in. from side joints and 3 in. from end joints. When insulation (Items 5 or 5A) is applied over the resilient channel/gypsum panel ceiling membrane the screw spacing shall be reduced to 8 in. OC. End joints secured to both resilient channels as shown in end joint detail. When Steel Framing Members (Item 6A) are used, gypsum panels installed with long dimension perpendicular to cross tees

with side joints centered along main runners and end joints centered along cross tees. Panels fastened to cross tees with 1 in. long Type S bugle-head screws spaced 8 in. OC in the field and along end joints. Panels fastened to main runners with 1 in. long Type S bugle-head screws spaced midway between cross tees. Screws along sides and ends of panels spaced 3/8 to 1/2 in. from board edge. End joints of panels shall be staggered with spacing between joints on adjacent panels not less than 2 ft OC. When **Steel Framing Members** (Item 6B) are used, one layer of nom 5/ in. thick, 4 ft wide gypsum board is installed with long dimensions perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long No. 6 Type S bugle-head steel screws spaced 12 in. OC in the field of the board. Screw spacing is reduced to 8 in. OC when insulation is applied over the furring channel/gypsum panel ceiling membrane. Gypsum board butted end joints shall be staggered minimum 16 in. within the assembly. At the gypsum board butt joints, each end of each gypsum board shall be supported by a single length of furring channel equal to the width of the gypsum board plus 6 in. on each end. These additional furring channels shall be attached to underside of the truss with Genie clips as described in Item 6B. Screw spacing along the gypsum board butt joint shall be 6 in. OC. When Steel Framing Members (Item 6C) are used, gypsum panels installed with long dimensions perpendicular to furring channels. Panels attached to the furring channels using 1 in. long Type S bugle-head steel screws spaced 8 in. OC along butted end joints and in the field of the panel. Butted end joints shall be staggered min. 2 ft within the assembly, and occur midway between the continuous furring channels. Each end of each gypsum panel shall be supported by a single length of furring channel equal to the width of the gypsum panel plus 6 in. on each end. The two support furring channels shall be spaced approximately 3-1/2 in. OC, and be attached to underside of the truss with one clip at each end of the channel. When Steel Framing Members (Item 6D) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is installed with long dimensions perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long Type S bugle-head steel screws spaced 8 in. OC in the field of the board. Gypsum board butted end joints shall be staggered minimum 48 in. and centered over main furring channels. At the gypsum board butt joints, each end of each gypsum board shall be supported by a single length of furring channel equal to the width of the gypsum board plus 3 in. on each end joint. The two support furring channels shall be spaced approximately 3 in. in from joint. Screw spacing along the gypsum board butt joint and along both additional channels shall be 8 in. OC. Additional screws shall be placed in the adjacent section of gypsum board into the aforementioned 3 in. extension of the extra butt joint channels as well as into the main channel that runs between. Butt joint furring channels shall be attached with one RESILMOUNT Sound Isolation Clip at each end of the channel. When Steel Framing Members (Item 6F) are used, one layer of nom 5/8 in. thick, 4 ft wide gypsum board is installed with long dimensions perpendicular to furring channels. Gypsum board secured to furring channels with nom 1 in. long \_ Type S bugle-head steel screws spaced 8 in. OC in the field of the board. Gypsum board butted end joints shall be staggered minimum 48 in. and centered over main furring channels. At the gypsum board butt joints, an additional single

extend one truss beyond the width of the gypsum panel and be attached to the adjacent trusses with one SonusClip at every truss involved with the butt joint. When Steel Framing Members (Item 6G) are used, nom 5/8 in. thick, 4 ft wide gypsum board, installed as

length of furring channel shall be installed and be spaced approximately 3 in. from the butt joint (6 in. from the continuous

furring channels) to support the floating end of the gypsum board. Each of these shorter sections of furring channel shall

described in Item 7. Adjacent butt joints staggered minimum 48 in. OC. When Steel Framing Members (Item 6H) are used, nom 5/8 in. thick, 4 ft wide gypsum board, installed as described in Item 7. Butt joints staggered minimum 24 in. OC. AMERICAN GYPSUM CO — Type AG-C

CGC INC — Types C, IP-X2, IPC-AR CONTINENTAL BUILDING PRODUCTS OPERATING CO, L L C — Type LGFC-C/A NATIONAL GYPSUM CO — Types eXP-C, FSW-G, FSW-C, FSK-G, FSK-C. **UNITED STATES GYPSUM CO** — Types C, IP-X2, IPC-AR

**USG BORAL DRYWALL SFZ LLC** — Type C 7A. **Gypsum Board\* - (Not Shown)** — For use with Items 5B and 6E. Nom 5/8 in. thick, 48 in. wide gypsum panels installed with long dimension perpendicular to resilient channels. Gypsum panels secured with 1 in. long Type S bugle head steel screws spaced 8 in. OC and located a min of 1/2 in. from side joints and 3 in. from the end joints. Finish Rating with this ceiling system is 20 min.

CGC INC — Type ULIX

UNITED STATES GYPSUM CO — Type ULIX 8. Finishing System - (Not Shown) — Vinyl, dry or premixed joint compound, applied in two coats to joints and screw-heads. Nom 2 in. wide paper tape embedded in first layer of compound over all joints. As an alternate, nom 3/32 in. thick veneer plaster may be applied to the entire surface of gypsum board. 9. **Grille** — Aluminum or Steel grille, installed in accordance with the installation instructions provided with the

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively. Last Updated on 2020-02-18

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO COMPLIANCE WITH ALL APPLICABLE CODES DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851 ROPERTY ADDRESS: 3777 OLD BERRY POINT OB DESCRIPTION: New construction of a 3 stor units. The building provi 30,455 GSF

PERMIT REVIEW STAMP

**ISSUE HISTORY** 

11/22/19 SCHEMATIC DESIGN

02/28/20 PERMIT REVIEW SET

12/06/19 DESIGN DEVELOPMENT

REVISION HISTORY

Description

Date


Date


FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www.fuglebergkoch.com

FT. MYERS, FL

JL REFERENCE DIRECTORY - FLOOR SYSTEM

09/10/201





1. Floor-Ceiling Assembly — The fire-rated wood joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in Design No. L505, L511 or L536 in the UL Fire Resistance Directory, as summarized below:

A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture\* as specified in the individual Floor-Ceiling Design. B. Wood Joists — Nom 2 by 10 in. lumber joists spaced 16 in. OC with nom 1 by 3 in. lumber bridging and with ends firestopped.

C. Furring Channels — (Not shown) — Resilient galv steel furring channels installed perpendicular to wood joists between first and second layers of wallboard (Item 1D) and spaced max 24 in. OC.


D. Gypsum Board\* — Nom 4 ft wide by 5/8 in. thick as specified in the individual Floor-Ceiling Design. First layer of wallboard nailed to wood joists. Second layer of wallboard screwattached to furring channels. Max diam of ceiling opening is 3/8 in. greater than the outside 2. **Through Penetrants** — One metallic pipe, conduit or tubing to be centered within the

ceiling. The following types and sizes of metallic pipes, conduits or tubing may be used: A. **Steel Pipe** — Nom 3 in. diam (or smaller) Schedule 5 (or heavier) steel pipe. B. **Conduit** — Nom 3 in. diam (or smaller) electrical metallic tubing or steel conduit. C. Copper Tubing — Nom 1-1/2 in. diam (or smaller) Type L (or heavier) copper tubing. 3. Fill, Void or Cavity Material\* — Sealant — Fill material forced into annular spaces to fill space to max extent possible. Sealant shall be installed flush with floor and ceiling. PRC-DESOTO INTERNATIONAL INC — Type PR-805 Sealant

firestop system. Pipe, conduit or tubing to be rigidly supported on both sides of floor and

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

<u>Last Updated</u> on 1992-12-04




#### System No. F-C-1006

April 03, 2007

F Rating — 1 Hr

T Ratings — 0 and 1 Hr (See Item 2) L Rating At Ambient — Less Than 1 CFM/sq ft



1. Floor-Ceiling Assembly — The 1 hr fire rated wood joist, wood truss or combination wood and steel truss Floor-Ceiling assembly shall be constructed of the materials and in the manner described in the individual L500-Series Design in the UL Fire Resistance Directory, as summarized below:

A. Joists or Trusses — Nom 2 by 10 in. (51 by 254 mm) lumber joists, min 12 in. (305 mm) deep parallel chord trusses fabricated from nom 2 by 4 in. (51 by 102 mm) lumber in conjunction with galv steel truss plates or Structural **Wood Members\*** with bridging as required.

B. Flooring — Nom 3/4 in. (19 mm) thick plywood flooring with or without Floor Topping Mixture\*. Diam of circular cutouts is 1/4 to 1/2 in. (6 to 13 mm) larger than outside diam of the pipe.

C. Furring Channels — Rigid or resilient galv steel furring channels installed perpendicular to bottom chord of trusse D. Gypsum Board\* — Nom 4 ft (1.2 m) wide by 5/8 in. (16 mm) thick, screw-attached to furring channels. Diam of circular cutouts is 1/4 to 1/2 in. (6 to 13 mm) larger than outside diam of the pipe.

rated single, double or staggered wood stud/gypsum wallboard chase wall constructed of the materials and in the manner specified in the individual U300 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

1.1 Chase Wall — (Optional, now shown) — The through penetrants (Item No. 2) may be routed through a 1 hr fire-

A. **Studs** — Nom 2 by 6 in. (51 by 152 mm) or double nom 2 by 4 in. (51 by 102 mm) lumber studs. B. Sole Plate — Nom 2 by 6 in. (51 by 152 mm) or parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Diam of circular cutouts is 1/4 to 1/2 in. (6 to 13 mm) larger than outside diam of the pipe.

C. Top Plate — The double top plate shall consist of two nom 2 by 6 in. (51 by 152 mm) or two sets of parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Diam of circular cutouts is 1/4 to 1/2 in. (6 to 13 mm) larger than outside diam of the pipe.

D. Gypsum Board\* — Thickness, type, number of layers and fasteners shall be as specified in individual Wall and Partition Design.

2. Through-Penetrant — Nom 10 in. (254 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe or cast iron pipe nom 4 in. (102 mm) diam (or smaller) steel conduit or steel EMT or nom 3 in. (76 mm) diam (or smaller) Type L (or A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture\* as heavier) copper tubing. Pipe to be installed approx midway between joists or trusses and centered in circular cutouts. | specified in the individual Floor-Ceiling Design. Max diam of opening shall be 127 mm (5 in.). Annular space between penetrant and periphery of opening shall be min 1/8 in. (3 mm) to max 1/4 in. (6 mm). Pipe to B. Wood Joists\* — Nom 254 mm (10 in.) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses be rigidly supported on both sides of Floor-Ceiling assembly.

than nom 4 in. (102 mm) diam.


3. Fill, Void or Cavity Materials\* — Caulk or Sealant — Min 3/4 in. (19 mm) thickness of fill material applied within the annulus, flush with top surface of floor or sole plate. Min 5/8 in. (16 mm) thickness of fill material applied within the 2. **Through Penetrants** — One nonmetallic pipe to be installed concentrically or eccentrically within the firestop system. annulus, flush with bottom surface of ceiling or top plate. An additional min 1/4 in. (6 mm) crown of fill material applied Annular space between pipe and edge of opening to be as specified in the table below. Pipe to be rigidly supported on to perimeter of penetrant at its egress from the top of flooring and underside of ceiling or from top of sole plate and both sides of floor-ceiling assembly. The following types and sizes of nonmetallic pipes may be used: underside of top plate.

3M COMPANY — CP 25 WB+ or FB-3000 WT \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

<u>Last Updated</u> on 2007-04-03 | closed (process or supply) piping systems.

**IPEX INC** — AquaRise

System No. F-C-2006 January 20, 2015 F Rating — 1 Hr FT Rating — 1 Hr



System tested with a pressure differential of 50 Pa between the exposed and the unexposed surfaces with the higher pressure on the exposed side.

SECTION A-A

1. Floor-Ceiling Assembly — The 1 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction features of the floor-ceiling assembly are summarized

A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture\* as specified in the individual Floor-Ceiling Design. Max diam of opening shall be 67 mm (2-5/8 in.). B. Wood Joists\* — Nom 254 mm (10 in.) deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or **Structural Wood Members\*** with bridging as required and with ends firestopped. C. Gypsum Board\* — Nom 16 mm (5/8 in.) thick, 1.2 m (4 ft) wide as specified in the individual Floor-Ceiling

2. **Through Penetrants** — One nonmetallic pipe to be installed concentrically or eccentrically within the firestop system. Annular space between pipe and edge of opening to be min 0 in. (point contact) and max 6 mm (1/4 in.). Pipe to be rigidly supported on both sides of floor-ceiling assembly. The following types and sizes of nonmetallic pipes may be used:

A. Polyvinyl Chloride (PVC) Pipe — Nom 51 mm (2 in.) diam (or smaller) Schedule 40 solid or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. B. Acrylonitrile Butadiene Styrene (ABS) Pipe — Nom 51 mm (2 in.) diam (or smaller) Schedule 40 solid or cellular core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. C. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 51 mm (2 in.) diam (or smaller) SDR13.5 CPVC pipe for use in closed (process or supply) piping systems.

D. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 51 mm (2 in.) drain (or smaller) SDR 11 CPVC for use in closed (process or supply) piping systems. IPEX INC — AquaRise

3. **Firestop System** — The firestop system shall consist of the following: A. Fill, Void or Cavity Material\* — Wrap Strip - Layers of intumescent wrap strip are continuously wrapped around the pipe with ends held in place with tape. Wrap strip butted tightly against bottom surface ceiling. Size of wrap strip and number of layers for a given size penetrant are shown in table below. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP648-E W25/1" or CP648-E W45/1-3/4" Firestop Wrap Strip

Product Number of Layers Nom. Wrap Strip Width mm (in.) Designation


CP648-E W25/1" CP648-E W45/1-3/4" 44 (1-3/4)

B. Steel Collar — Steel collar fabricated from coils of precut min 0.016 in. thick (No. 28 gauge) galv steel available from fill material manufacturer. Collar shall be nom 1 in. (for 1 in. wide wrap strip) or 1-/34 in. (for 1-3/4 in. wide wrap strip) deep with 1 in. wide by 2 in. long anchor tabs on 1-3/4 in. centers for securement to the underside of floor or both surfaces of wall. The opposite side incorporates retainer tabs, 1/2 in. wide by 3/16 in. long, prebent toward the pipe surface. Collar shall be tightly wrapped over the wrap strip, overlapping min. 1 in at seam. A nom 1/2 in. wide stainless steel hose clamp shall be secured to the collar at its mid-height. Every other anchor tab of collar secured to gypsum ceiling at every other tab with 1/4 in. diam by 1-1/2 in. long steel toggle bolts in conjunction with \( \frac{1}{4} \) in by \( \frac{3}{4} \) in diameter steel washers.


C. Fill, Void or Cavity Materials\*-Sealant — Min 16 mm (5/8 in.) thickness of fill material applied within the annulus, flush with the bottom surface of the gypsum board. Min 19 mm (3/4 in.) thickness of fill material applied within the annulus, flush with the top surface of the floor. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2015-01-20



System No. F-C-2007 January 20, 2015 F Rating — 1 Hr FT Rating — 3/4 and 1 Hr (See Item 2) FH Rating — 1 Hr



System tested with a pressure differential of 50 Pa between the exposed and the unexposed surfaces with the higher pressure on the exposed side. 1. **Floor-Ceiling Assembly** — The 1 hr fire-rated solid or trussed lumber joist floor-ceiling assembly shall be

constructed of the materials and in the manner specified in the individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction features of the floor-ceiling assembly are summarized below: or Structural Wood Members\* with bridging as required and with ends firestopped. T Rating is 1 hr for nom 4 in. (102 mm) diam (or smaller) penetrants. T Rating is 0 hr for all penetrants greater C. Gypsum Board\* — Nom 16 mm (5/8 in.) thick, 1.2 m (4 ft) wide as specified in the individual Floor-Ceiling Design. Max diam of opening shall be 127 mm (5 in.).

> A. Polyvinyl Chloride (PVC) Pipe — Nom 102 mm (4 in.) diam (or smaller) Schedule 40 solid or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. B. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 102 mm (4 in.) diam (or smaller) SDR11 or SDR13.5 CPVC pipe for use in closed (process or supply) piping systems. C. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 102 mm (4 in.) diam (or smaller) SDR 11 CPVC for use in

Min/Max Annular Space, mm (in.) T Rating - H

Nom Diam of Pipe, mm (in.)

0-6 (0-1/4)

0-13 (0-1/2)

51 (2) (or smaller)

102 (4) (or smaller)

3. **Firestop System** — The firestop system shall consist of the following: A. Fill, Void or Cavity Material\* — Wrap Strip - Layers of intumescent wrap strip are continuously wrapped around the pipe with ends held in place with tape. Wrap strip butted tightly against bottom surface of floor or both surfaces of wall. Size of wrap strip and number of layers for a given size penetrant are shown in table below. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP648-E W25/1" or CP648-E W45/1-3/4" Firestop Wrap

Designation Max Pipe Size mm (in.) Number of Layers Nom Wrap StripWidth mm (in.)

CP648-E W45/1-3/4" 76 (3) 25 (1) CP648-E W25/1" 102 (4) CP648-E W45/1-3/4" 102 (4)

Certification (such as Canada), respectively.

B. Steel Collar — Steel collar fabricated from coils of precut min 0.4 mm (0.016 in.) thick (No. 28 gauge) galv steel available from fill material manufacturer. Collar shall be nom 25 mm (1 in.) (for 1 in. wide wrap strip) or 44 mm (1-3/4 in.) for 1-3/4 in. wide wrap strip) deep with 25 mm (1 in.) wide by 51 mm (2 in.) long anchor tabs on 44 mm (1-3/4 in.) centers for securement to the underside of floor or both surfaces of wall. The opposite side incorporates retainer tabs, 12 mm (1/2 in.) wide by 5 mm (3/16 in.) long, prebent toward the pipe surface. Collar shall be tightly wrapped over the wrap strip, overlapping min. 1 in at seam. A nom 12 mm (1/2 in.) wide stainless steel hose clamp shall be secured to the collar at its mid-height. Every other anchor tab of collar secured to gypsum ceiling at every other tab with 6 mm (1/4 in.) diam by 38 mm (1-1/2 in.) long steel toggle bolts in conjunction with 6 mm ( $\frac{1}{4}$  in.) by 19 mm ( $\frac{3}{4}$  in.) diameter steel washers. C. Fill, Void or Cavity Materials\*-Sealant — Min 16 mm (5/8 in.) thickness of fill material applied within the annulus,

annulus, flush with the top surface of the floor. HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant or FS-ONE MAX Intumescent Sealant.

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL


flush with the bottom surface of the gypsum board ceiling. Min 16 mm (5/8 in.) thickness of fill material applied within the

Last Updated on 2015-01-20

System No. F-C-2008

May 20, 2005

F Rating — 1 Hr T Rating — 1 Hr L Rating At Ambient — 7 CFM/sq ft (See Item 3B) L Rating At 400 F — Less Than 1 CFM/sq ft (See Item 3B)



1. Floor Assembly — The fire rated wood truss or combination wood and steel truss Floor-Ceiling assembly shall be constructed of the materials and in the manner described in the individual L500 Series Design in the UL Fire Resistance Directory and shall include the following construction features:

A. Trusses — Min 12 in. (305 mm) deep parallel chord trusses fabricated from 2 by 4 in. (51 by 102 mm) lumber in conjunction with galv steel truss plates or **Structural Wood Members\*** with bridging as required. B. Flooring — Nom 3/4 in. (19 mm) thick plywood flooring with or without Floor Topping Mixture\*. Diam of hole-sawed opening in flooring to be 1/2 to 3/4 in. (13 to 19 mm) larger than diam of pipe. Max diam of opening in C. Furring Channels — Rigid or resilient galv steel furring channels installed perpendicular to bottom chord of

D. Gypsum Board\* — Nom 4 ft (1.22 m) wide by 5/8 in. (16 mm) thick, screw-attached to furring channels. Diam of hole-sawed opening in gypsum wallboard ceiling to be 1/2 to 3/4 in. (13 to 19 mm) larger than diam of pipe. Max diam of opening in ceiling is 3 in. (76 mm) 2. Nonmetallic Pipe — Nom 2 in. (51 mm) diam (or smaller) Schedule 40 polyvinyl chloride (PVC), SDR 13.5

chlorinated polyvinyl chloride (CPVC) or solid-core Schedule 40 acrylonitrile-butadiene-styrene (ABS) pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. One pipe to be installed approx midway between trusses and centered in circular openings in flooring and in ceiling. A nom 1/4 in. to 3/8 in. (6 to 10 mm) annular space is required in the firestop system. Pipe to be rigidly supported on both sides of Floor-

2A. Electrical Nonmetallic Tubing+ — Nom 1 in. (25 mm) diam (or smaller) corrugated wall ENT constructed of polyvinyl chloride. ENT to be installed as a complete system with all terminations in junction boxes, outlet boxes or other approved enclosures as specified in the National Electrical Code. Max one ENT per through opening. ENT to be centered in opening and rigidly supported on both sides of the Floor-Ceiling assembly. See Electrical Nonmetallic Tubing (FKHU) category in Electrical Construction Materials Directory for names of

3. **Firestop System** — The details of the firestop system shall be as follows: A. Fill, Void or Cavity Materials\* — Wrap Strip — Nom 1/4 in. (6 mm) thick intumescent elastomeric material faced on one side with aluminum foil, supplied to 2 in. (51 mm) wide strips. Nom 2 in. (51 mm) wide strip tightlywrapped around nonmetallic pipe (foil side exposed), secured with two steel tie wires and slid into hole-sawed opening in flooring (Item 1B) and in gypsum wallboard ceiling (Item 1D). Bottom edge of wrap strip to project 9/16 to 11/16 in. (14 to 17.5 mm) below bottom surface of flooring and below bottom (ceiling) surface of gypsum

**3M COMPANY** — Type FS-195+ B. Fill, Void or Cavity Materials\* — Caulk, Sealant or Putty — Nom 1/4 in. (6 mm) thickness of caulk or putty to be applied to the exposed edge of the wrap strip layer (top of flooring and bottom of gypsum board ceiling). Generous application of caulk or putty to be applied to fill all gaps at the wrap strip/flooring and wrap strip/gypsum board ceiling interfaces.


**3M COMPANY** — CP 25WB+ Caulk, FB-3000 WT Sealant, MP+ Stix Putty (Note: L Ratings apply only when Type CP 25WB+ caulk or FB-3000 WT sealant is used. CP 25WB+ not suitable for use with CPVC pipes.) \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2005-05-20

November 26, 1997 F Rating — 1 Hr

System No. F-C-2037

T Rating — 1 Hr



1. Floor-Ceiling Assembly — The fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction details of the floor-ceiling assembly are summarized below: A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture\* as specified in the individual Floor-Ceiling Design. Max diam of opening is 5 in.

B. Wood Joists — Nom 2 by 10 in. lumber joists spaced 16 in. OC with nom 1 by 3 in. lumber bridging and with ends firestopped. As an alternate to lumber joists, nom 10 in. deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or **Structural Wood Members**\* with bridging as required with ends firestopped. C. Furring Channels — Resilient galv steel furring installed perpendicular to wood joists (Item 1B) between wallboard (Item 1D) and wood joists as required in the individual Floor-Ceiling Design. D. Gypsum Board\* — Nom 4 ft wide by 5/8 in. thick as specified in the individual Floor-Ceiling Design. Wallboard

secured to wood joists as specified in the individual Floor-Ceiling Design. 2. Drain Piping — Nom 4 in. diam (or smaller) Schedule 40 polyvinyl chloride (PVC) or acrylonitrile butadiene styrene (ABS) drain piping and fittings. Diam of circular opening hole through flooring (Item 1A) to be max 1/2 in. larger than outside diam of pipe. Short length of pipe with 90 degree elbow fitting cemented into bottom socket of closet flange (Item 5). Drain piping cemented to elbow.


3. **Firestop System** — The firestop system shall consist of the following: A. Fill, Void or Cavity Materials\* — Wrap Strip — Nom 1/4 in. thick intumescent material faced on both sides with a plastic film, supplied in 1-1/2 in. wide strips. Nom 1-1/2 in. wode strips tightly-wrapped around nonmetallic pipe with the edges butted against the underside of flooring and around the entire perimeter of the hole-sawed opening. Two layers of wrap strip are required. Each layer of wrap strip to be installed with butted seam, butted seams in successive layers staggered or aligned. Wrap strip layer(s) temporarily held in position using aluminum foil tape.

SPECIFIED TECHNOLOGIES INC — SpecSeal RED Strip B. Steel Collar — Collar fabricated from coils of precut 0.016 in. thick (30 MSG) galv sheet steel available from wra strip manufacturer. Collar shall be nom 1-1/2 in. deep with min four 1 in. wide by 2 in. long anchor tabs for securement to top surface of flooring. Retainer tabs, 3/4 in. wide tapering down to 1/4 in. wide and located opposite the anchor tabs, are folded 90 degrees toward through-penetrant surface to maintain the annular space around the through-penetrant and to retain the wrap strips. Steel collar wrapped around wrap strips and through-penetrant with a 1 in. wide overlap along its perimeter joint and secured together by means of a min 1/2 in. wide by 0.028 in. thick stainless steel hose clamp at mid-height of the steel collar. As an alternate to the steel hose clamp, the steel collar can be secured together by means of three No. 8 by 3/8 in. long steel sheet metal screws. Anchor tabs of collar bent outwards and secured to top surface of flooring or underside of floor using min 3/4 in. long steel wood screws in conjunction with 1/4 in., by 1-1/4 in. diam steel fender washers.

4. Closet Flange — PVC or ABS closet stub sized to accommodate drain pipe. Closet flange installed in hole-sawed opening in flooring system with flange secured to top of flooring with steel screws. 5. Water Closet — (Not Shown) — Floor mounted vitreous china water closet.

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 1997-11-26



System No. F-C-3007

August 18, 2011

F Rating — 1 Hr

T Rating — 1 Hr

1. Floor Assembly — The 1 hr fire rated wood truss or combination wood and steel truss Floor-Ceiling assembly shall be constructed of the materials and in the manner described in the individual L500 Series Design in the UL Fire Resistance Directory, as summarized below:

A. Trusses — Min 12 in. (305 mm) deep parallel chord trusses fabricated from nom 2 by 4 in. (51 by 102 mm) lumber in conjunction with galv steel truss plates or Structural Wood Members\* with bridging as required. B. Flooring — Nom 3/4 in. (19 mm) thick plywood flooring with or without Floor Topping Mixture\*. Max diam of opening is 1-1/4 in. (32 mm).

C. Furring Channels — Rigid or resilient galv steel furring channels installed perpendicular to bottom chord of D. **Gypsum Board\*** — Nom 4 ft (1.22 m) wide by 5/8 in. (16 mm) thick, screw-attached to furring channels.

Max diam of opening is 1-1/4 in. (32 mm). 1.1 Chase Wall — (Optional, Not Shown) — The through penetrants (Item No. 2) may be routed through a 1 hr fire-rated single, double or staggered wood stud/gypsum board chase wall constructed of the materials and in the manner specified in the individual U300 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. **Studs** — Nom 2 by 6 in. (51 by 152 mm) or double nom 2 by 4 in. (51 by 102 mm) lumber studs. B. Sole Plate — Nom 2 by 6 in. (51 by 152 mm) or parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly

C. Top Plate — The double top plate shall consist of two nom 2 by 6 in. (51 by 152 mm) or two sets of parallel 2 by 4 in. (51 by 102 mm) lumber plates, tightly butted. Max diam of opening is 1-1/2 in. (38 mm) D. Gypsum Board\* — Thickness, type, number of layers and fasteners shall be as specified in individual Wall and Partition Design.

2. Cables — One cable to be installed eccentrically or concentrically in opening with annular space between the cable and the periphery of the opening of min 0 in. (0 mm, point contact) to max 1-1/4 in. (32 mm). Cable to be rigidly supported on both sides of Floor-Ceiling assembly. The following types of cables may be used. A. Max seven conductor No. 12 AWG (or smaller) power/control cables with polyvinyl chloride insulation and iacket materials.

B. Max 100 pair No. 22 AWG (or smaller) telecommunication cables with polyvinyl chloride insulation and iacket materials. C. Max four conductor with ground No. 2/0 AWG (or smaller) aluminum SER cables with polyvinyl chloride

insulation and jacket materials. 2A. Through Penetrating Product\* — Max one through-penetrating product to be installed eccentrically or concentrically in opening with annular space between the through-penetrating product and the periphery of the opening of min 0 in. (0 mm, point contact) to max 1-1/4 in. (32 mm). Through-penetrating product to be rigidly supported on both sides of floor or wall assembly. The following types of through-penetrating products may be

A. Max four copper conductors No. 2/0 AWG (or smaller) aluminum or steel Armored Cable# or Metal-Clad

AFC CABLE SYSTEMS INC

B. Two or more twisted copper conductor No. 6 AWG (or smaller) Power Limited Circuit Cable+ with or without a jacket under a metal armor. AFC CABLE SYSTEMS INC

C. I wo or more twisted copper conductor No. 10 AWG (or smaller) Power Limited Fire Alarm Cable+ with c without a jacket under a metal armor. AFC CABLE SYSTEMS INC

D. Two or more twisted copper conductor No. 12 AWG (or smaller) Non Power Limited Fire Alarm Cable+ with or without a jacket under a metal armor.

AFC CABLE SYSTEMS INC 3. Fill, Void or Cavity Materials\* — Caulk, Sealant or Putty — Min 3/4 in. (19 mm) thickness of fill material applied within the annulus, flush with top surface of floor or sole plate. Min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with bottom surface of ceiling or top plate. An additional min 1/4 in. (6 mm) crown of fill material applied to perimeter of penetrant at its egress from the top of flooring and underside of ceiling or from top of sole plate and underside of top plate.

**3M COMPANY** — CP 25WB+ caulk, MP+ Stix putty or FB-3000 WT sealant \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively. +Bearing the UL Listing Mark

Last Updated on 2011-08-18

ISSUE HISTORY Date Description 11/22/19 SCHEMATIC DESIGN 12/06/19 DESIGN DEVELOPMENT 3 02/28/20 PERMIT REVIEW SET REVISION HISTORY Date Description

PERMIT REVIEW STAMP

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO COMPLIANCE WITH ALL APPLICABLE CODES

ROPERTY ADDRESS: 3777 OLD BERRY POINT


OB DESCRIPTION: New construction of a 3 sto

units. The building prov 30,455 GSF

DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851

FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595

www.fuglebergkoch.com



THE ROBERT FT. MYERS, FL REFERENCE DIRECTORY - FLOOR PENETRATIONS

. Floor-Ceiling Assembly — The fire-rated solid or trussed lumber joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in individual L500 Series Floor-Ceiling Designs in the UL Fire Resistance Directory. The general construction details of the floor-ceiling assembly are summarized

A. Flooring System — Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture\* as specified in the individual Floor Ceiling Design. Rectangular cutout in flooring to accommodate the bathtub drain piping (Item 2) to be max 8 by 12 in.

B. Wood Joists — Nom 2 by 10 in. lumber joists spaced 16 in. OC with nom 1 by 3 in. lumber bridging and with

ends firestopped. As an alternate to lumber joists, nom 10 in. deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or Structural Wood Members\* with bridging as required with ends firestopped. C. Furring Channels — Resilient galv steel furring installed perpendicular to wood joists (Item 1B) between wallboard (Item 1D) and wood joists as required in the individual Floor-Ceiling Design. D. Gypsum Board\* — Nom 4 ft wide by 5/8 in. thick as specified in the individual Floor-Ceiling Design.

Wallboard secured to wood joists as specified in the individual Floor-Ceiling Design. Two pieces of gypsum wallboard, each min 4 in. longer and wider than the cutout in the flooring, screw-attached to bottom of flooring concentric with cutout. Diam of opening hole-sawed through both layers of the gypsum wallboard patch to be 1/2 to 5/8 in. larger than outside diam of bathtub drain piping (Item 2).

2. **Drain Piping** — Nom 1-1/2 in. diam Schedule 40 polyvinyl chloride (PVC) or acrylonitrile butadiene styrene (ABS) pipes and drain fittings cemented together and provided with PVC or ABS bathtub waste/overflow fittings,

3. **Firestop System** — The firestop system shall consist of the following:

A. Fill, Void or Cavity Materials\* — Wrap Strip — Nom 1/4 in. thick intumescent material faced on both sides with a plastic film, supplied in 1-1/2 in. Nom 1-1/2 in. wide strips tightly-wrapped around drain piping secured together with 1-1/2 in. wide aluminum foil tape and slid into hole-sawed opening in gypsum wallboard patch (Item 1D). Top edge of wrap strip to extend a nom 1/2 in. below above top surface of gypsum wallboard patch **SPECIFIED TECHNOLOGIES INC** — SpecSeal RED Strip

B. Fill, Void or Cavity Materials\* — Sealant — Nom 1/4 in. thickness of fill material to be applied to perimeter of wrap strip at its egress from the underside of the gypsum wallboard patch. Nom 1/4 in. thickness of fill material to be applied to the exposed edge of the wrap strip layer and to fill all gaps between the wrap strip layer and the tee of the drain fitting on the top surface of the gypsum wallboard patch. SPECIFIED TECHNOLOGIES INC — SpecSeal Series SSS Sealant or SpecSeal LCI Sealant

\*Bearing the UL Classification Mark


Last Updated on 2008-12-08



System No. W-L-8011

December 10, 2008

F Ratings — 1 & 2 Hr. (See Item 1B)



1. Wall Assembly — The 1 or 2 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described in the individual U300 or U400 Series Wall or Partition Design in the UL Fire Resistance Directory and shall include the following construction features:

SECTION A-A

A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. lumber spaced 16 in. O.C. with nom 2 by 4 in. lumber end plates and cross braces. Steel studs to be min 3-5/8 in. wide and spaced max 24 in. O.C.

B. Gypsum Board\* — 5/8 in. thick, 4 ft wide with square or tapered edges. The gypsum board type, thickness number of layers, fastener type and sheet orientation shall be as specified in the individual U300 or U400 Series Design in the UL Fire Resistance Directory. Max diam of opening is 3-1/2 in.

The hourly F Rating of the firestop system is equal to the hourly fire rating of the wall assembly in which it is 2. Through Penetrant — A max of two pipes or tubing to be installed within the opening. Of the two pipes, or tubing, only one of the pipes or tubing shall have a nom diam greater than 1/2 in. The annular space between

pipes or tubing and periphery of opening shall be min 0 in. (point contact) to max 1/2 in. Pipes or tubing to be rigidly supported on both sides of wall assembly. The following types and sizes of metallic pipes or tubing may

A. Steel Pipe — Nom 1 in. diam (or smaller) Schedule 10 (or heavier) steel pipe. B. Iron Pipe — Nom 1 in. diam (or smaller) cast or ductile iron pipe.

C. **Copper Tubing** — Nom 1 in. diam (or smaller) Type L (or heavier) copper tubing. D. Copper Pipe — Nom 1 in. diam (or smaller) Regular (or heavier) copper pipe.

3. Tube Insulation — Plastics+ — Nom 3/4 in. thick acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexib foam furnished in the form of tubing. The tube insulation may be installed on a max of one pipe or tubing. The annular space between penetrating item and periphery of opening shall be min 1/2 into max 3/4 in. The space between pipes or tubing shall be 0 in. (point contact)


See Plastics+ (QMFZ2) category in the Recognized Component Directory for names for manufacturers. Any Recognized Component tube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used.

4. Cables — One 4 pair No. 18 AWG (or smaller) thermostat cable with polyvinyl chloride (PVC) insulation and jacket materials. Cable to be spaced a min 0 in. (point contact) to max 1/2 in. from the other penetrants. The space between the cable and the periphery of the opening shall be a min 0 in. (point contact) to max 1/2 in. Cable to be rigidly supported on both sides of wall assembly. 5. Fill, Void or Cavity Material\* — Sealant — Min 5/8 in thickness of fill material applied within annulus, flush

with both surfaces of wall. Additional fill material to be to be forced into intersties within groups of penetrating items to max extent possible and installed such that a min 1/4 in. thick crown is formed around the penetrating items and lapping 1/4 in. beyond the periphery of the opening. **SPECIFIED TECHNOLOGIES INC** — SpecSeal Series SSS Sealant or SpecSeal LCI Sealant

+Bearing the UL Recognized Component Mark \*Bearing the UL Classification Mark

Last Updated on 2008-12-10




System No. W-L-2059

November 26, 2012

F Ratings — 1 and 2 Hr (See Items 2 and 3)

T Ratings — 3/4, 1, 1-1/2 and 2 Hr (See Items 2 and 3)

L Rating At Ambient — 1 CFM/sq ft



1. Wall Assembly — The 1 or 2 h fire rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described in the individual U300, U400 and V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features: A. Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC. B. Gypsum Board\* — 5/8 in. (16 mm) thick, 4 ft (1219 mm) wide with square or tapered edges. The gypsum

board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300, U400 or V400 Series Design in the UL Fire Resistance Directory. Max diam of opening is 5 in. 2. **Through-Penetrants** — One nonmetallic pipe or conduit to be centered within the firestop system. The

annular space shall be max 1/4 in. (6 mm). Pipe or conduit to be rigidly supported on both sides of the wall assembly. The following types and sizes of nonmetallic pipes or conduits may be used: A. Polyvinyl Chloride (PVC) Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 or 80 solid or cellular core PVC pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. When Schedule 80 PVC pipe is used, the F and T Ratings are 1 hr. When Scheduled 80 PVC pipe is used in closed (process or supply) piping systems, the F and T Ratings are equal to the assembly rating of the

wall in which it is installed. B. Rigid Nonmetallic Conduit+ — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 or 80 PVC conduit installed in accordance with Article 347 of the National Electrical Code (NFPA No. 70). When Schedule 80 PVC conduit is used, the F and T Ratings are 1 hr. C. Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 4 in. (102 mm) diam (or smaller) SDR 13.5 CPVC

pipe for use in closed (process or supply) piping systems. D. Acrylonitrile Butadiene Styrene (ABS) Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 solid or foamed core ABS pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. E. Fire Retardant Polypropylene (FRPP) Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 FRPP pipe for use in closed (process or supply) or vented (drain, waste or vent) piping systems. F. Polyvinylidene Fluoride (PVDF) Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 PVDF pipe for

use in closed (process or supply) or vented (drain, waste or vent) piping systems. G. Fiberglass Reinforced Pipe (FRP) Pipe — Nom 4 in. (102 mm) diam (or smaller) glass fiber reinforced thermosetting resin pipe for use in closed (process or control) or vented (drain, waste or vent) piping systems. When FRP pipe is used, T Rating is 3/4 hr. H. High Density Polyethylene (HDPE) Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 HDPE pipe

for use in closed (process or supply) piping systems. 3. **Firestop System** — The firestop system shall consist of the following: A. Fill, Void or Cavity Material\* — Sealant — Fill material forced into annular space to max extent possible. Caulk shall be installed flush with both surfaces of wall assembly

SPECIFIED TECHNOLOGIES INC — SpecSeal 100, 101, 102, 105, 120 or 129 Sealant, SpecSeal LCI Sealant, Pensil 300 Sealant or SpecSeal Series SIL300 Sealant

B. Fill, Void or Cavity Material — Wrap Strip — Nom 1/8 or 3/16 in. (3.2 or 4.8 mm) thick intumescent material faced on both sides with a plastic film, supplied in 2 in. (51 mm) wide strips or nom 1/4 in. (6 mm) thick intumescent material faced on both sides with a plastic film, supplied in 1-1/2 in, (38 mm) wide strips. The layers of wrap strips are individually wrapped around the through-penetrant with ends butted and held in place with masking tape. Butted ends in successive layers shall be aligned. Except as noted in Item 2, the F and T Rating of the firestop system is dependent upon the fire rating of wall,

diam of through penetrant and the number of wrap strips as tabulated below:


Fire Rating of Wall Hr	Max Diam of Through Penetrant In. (mm)	No. of Wrap Strip Layers	F Rating Hr	T Rating Hr
1	1-1/2 (38)	1	1	1
2	1-1/2 (38)	1	2	1-1/2
1	2 (51)	1	1	1
2	2 (51)	1	2	1-1/2
1	3 (76)	2	1	1
2	3 (76)	2	2	2
1	4 (102)	3	1	1
2	4 (102)	.3	2	2

SPECIFIED TECHNOLOGIES INC — SpecSeal BLU Wrap Strip, SpecSeal BLU2 Wrap Strip or SpecSeal RED C. **Steel Collar** — Collar fabricated from coils of precut 0.016 in. (0.4 mm) thick (30 MSG) galv sheet steel available from wrap strip manufacturer. Collar shall be min 1-1/2 in. (38 mm) deep with 1 in. (25 mm) wide by 2 in. (51 mm) long anchor tabs for securement to the concrete floor or wall. Retainer tabs, 3/4 in. (19 mm) wide tapering down to 1/4 in. (6 mm) wide and located opposite the anchor tabs, are folded 90 degree toward pipe surface to maintain the annular space around the pipe and to retain the wrap strips. Steel collar wrapped around wrap strips and pipe with a 1 in. (25 mm) wide overlap along its perimeter joint and secured together by means of a min 1/2 in. (13 mm) wide by 0.028 in. (0.7 mm) thick stainless steel hose clamp installed at mid-depth of the steel collar. As an alternate to the steel hose clamp, the steel collar may be secured together by means of three No. 8 by 1/4 in. (6 mm) long steel sheet metal screws when more than one layer of wrap strip is used. Wrap strip/collar assembly is slid along the through-penetrant until abuts the surface of the wall. Collar secured to wall by 1/8 in. (3.2 mm) diam by 1-3/4 in. (44 mm) long steel molly bolts in conjunction with 1-1/4 in. (32 mm) diam steel fender washers. The number of molly bolts used is dependent upon the nom diam of the through penetrant. Two molly bolts, symmetrically located, are required for nom 1-1/2 in. (38 mm) and 2 in. (51 mm) diam through penetrants. Three molly bolts, symmetrically located, are required for nom 2-1/2 in. (64 mm) and 3 in. (76 mm) diam through penetrants. Four molly bolts, symmetrically located, are required for nom 3-1/2 in. (89 mm) and 4 in. (102 mm) diam through penetrants. Steel collars are installed on each side of wall. D. Firestop Device\* — (Optional, Not Shown) - As an alternate to Item 3B and 3C, galv steel collar lined with an intumescent material sized to fit the specific diam of the through-penetrant. Device shall be installed around through-penetrant in accordance with accompanying installation instructions. Device incorporates anchor tabs for securement to each surface of wall assembly by means of 1/8 in. (3 mm) diam by 1-3/4 in. (45 mm) long steel molly bolts in conjunction with 1/4 in. (6 mm) diam by 1-1/2 in. (38 mm) diam steel fender washers. SPECIFIED TECHNOLOGIES INC — SpecSeal Firestop Collar, SpecSeal LCC Collar or SpecSeal SSC Collar . When SpecSeal LCC Collar or SpecSeal SSC Collar are used, the max annular space shall be 1/8 in. (3 mm) for max 2-1/2 in. (64 mm) diam pipe and shall be max 1/4 in. (6 mm) for pipe larger than 2-1/2 in. (64 mm) diam.

\*Bearing the UL Classification Mark

Last Updated on 2012-11-26

System No. F-C-5007 December 10, 2001 F Rating — 1 Hr T Ratings — 3/4 & 1 Hr



SECTION A-A

1. Floor-Ceiling Assembly — The fire-rated wood joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in Design Nos. L512, L513 or L514 in the UL Fire Resistance Directory, and shall include the following construction features

A. Flooring System — Lumber or min 1/2 in. plywood subfloor with lumber or min 3/4 in. plywood finish floor, or Floor-Topping Mixture\* as specified in the individual Floor-Ceiling Design. Max diam of opening is 6 in. B. Wood Joists — Nom 2 by 10 in. lumber joists spaced 16 in. OC with nom 1 by 3 in. lumber bridging and with ends firestopped.

C. Furring Channels — (Not Shown) — Resilient galv steel furring installed perpendicular to wood joists between wallboard (Item 1D) and wood joists and spaced max 24 in. OC. D. **Gypsum Board\*** — Nom 4 ft wide by 1/2 or 5/8 in. thick as specified in the individual Floor-Ceiling Design. Gypsum board attached to wood joists and furring channels as specified in the individual Floor-Ceiling Design. Max

2. Through Penetrants — One metallic pipe or tubing installed approximately midway between wood joist and centered within the firestop system. Diam of openings hole-sawed through flooring system and through gypsum board ceiling to be nom 1/4 in. larger than the outside diam of through penetrant. Pipe or tubing to be rigidly supported on both sizes of floor-ceiling assembly. The following types and sizes of metallic pipes or tubing may be

A. Steel Pipe — Nom 4 in. diam (or smaller) Schedule 5 (or heavier) steel pipe. B. Copper Pipe — Nom 4 in. diam (or smaller) Regular (or heavier) copper pipe. C. Copper Tubing — Nom 4 in. diam (or smaller) Type L (or heavier) copper tubing.

The T Rating of the firestop system is dependent upon the type of penetrant used as tabulated below:

Penetrant Type T Rating Hr Copper Pipe Copper Tubing

3. Pipe Covering\* — The following types of pipe coverings may be used: A. Pipe and Equipment Covering — Materials\* — Nom 1/2 in. thick hollow cylindrical heavy density (min 3.5 pcf) glass fiber units jacketed on the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing tape. Transverse joints secured with metal fasteners or with butt tape supplied with the product. Diam of openings hole-sawed through flooring system and through gypsum board ceiling to be nom 1/4 in.


larger than the outside diam of through-penetrant. See Pipe and Equipment Covering — Materials (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used. B. Pipe Covering Materials\* — Nom 1/2 in. thick unfaced mineral fiber pipe insulation sized to the outside diam of pipe or tube. Pipe insulation secured with min 8 AWG steel wire spaced max 12 in. OC. Diam of openings holesawed through flooring system and through gypsum board ceiling to be nom 1/4 in. larger than the outside diam of through-penetrant. IIG MINWOOL L L C — High Temperature Pipe Insulation 1200, High Temperature Pipe Insulation BWT or High

Temperature Pipe Insulation Thermaloc C. Sheathing Material\* — (Not Shown) — Used in conjunction with Item 3B. Foil-scrim-kraft or all service jacket material shall be wrapped around the outer circumference of the pipe insulation (Item 3B) with the kraft side exposed. Longitudinal joints and transverse joints sealed with metal fasteners or with butt tape. See **Sheathing Materials** (BVDV) category in the Building Materials Directory for names of manufacturers. Any sheathing material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread


Index of 25 or less and a Smoke Developed Index of 50 or less may be used. 4. Fill, Void or Cavity Material\* — Caulk — On top of assembly, a min 1-1/8 in. depth of fill material applied within annulus on top surface of floor. On bottom of assembly, a min 1/2 in. depth of fill material applied within annulus on bottom surface of ceiling. Additional fill material to be installed such that a min 1/2 in. thick crown is formed around

A/D FIRE PROTECTION SYSTEMS INC — A/D FireBarrier Silicone \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2001-12-10



the through penetrant on both sides of floor-ceiling assembly.



System No. F-C-3014

SECTION A-A

1. Floor-Ceiling Assembly — The fire-rated wood joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in Design Nos. L512, L513 or L514 in the UL Fire Resistance Directory, and shall include the following construction features: A. **Flooring System** — Lumber or min 1/2 in. plywood subfloor with lumber or min 3/4 in. plywood finish floor, or Floor-Topping Mixture\* as specified in the individual Floor-Ceiling Design. Max diam of

opening is 2 in. B. Wood Joists — Nom 2 by 10 in. lumber joists spaced 16 in. OC with nom 1 by 3 in. lumber bridging and with ends firestopped. As an alternate to lumber joists, nom 10 in. deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or **Structural Wood Members\*** with bridging as required with ends firestopped.

C. Furring Channels — (Not Shown) — Resilient galv steel furring installed perpendicular to wood joists between Gypsum board (Item 1D) and wood joists and spaced max 24 in. OC. D. Gypsum Board\* — Nom 4 ft wide by 1/2 or 5/8 in. thick as specified in the individual Floor-Ceiling Design. Gypsum board attached to wood joists and furring channels as specified in the individual Floor-Ceiling Design. Max diam of opening is 2 in. 2. Cables — One cable to be installed approximately midway between wood joist and centered within

the firestop system. Diam of openings hole-sawed through flooring system and through gypsum wallboard ceiling to be nom 1/4 in. larger than the outside diam of through penetrant. Cable to be rigidly supported on both sides of floor-ceiling assembly. The following types and sizes of copper conductor


A. 1/C-500 kcmil (or smaller) cable with cross-linked polyethylene insulation and jacket. B. Max 100 pair No. 24 AWG cable (or smaller) with polyvinyl chloride (PVC) insulation and jacket. C. Type RG/U coaxial cable with fluorinated ethylene propylene insulation and jacket.

D. Max 2/C — No. 12 AWG (or smaller) cable with (PVC) insulation and jacket. E. Max 3/C with ground — No. 10 AWG (or smaller) Type NM nonmetallic sheathed cable. F. Max 3/C — No. 4/0 AWG (or smaller) aluminum conductor service entrance cable with PVC

insulation and jacket. 2A. Cables (Not Shown) — As an alternate to Item 2, a max of seven cables bundled together and centered within the firestop system. Diam of openings hole-sawed through flooring system and through gypsum board ceiling to be nom 1/4 in. larger than the outside diam of cable bundle. Cables to be rigidly supported on both sides of floor-ceiling assembly. The following types and sizes of copper conductor cables may be used:

A. Max 4 pair No. 24 AWG cable (or smaller) with polyvinyl chloride (PVC) insulation and jacket. B. Type RG/U coaxial cable with fluorinated ethylene propylene insulation and jacket. 3. Fill, Void or Cavity Material\* — Caulk — On top of assembly, a min 1-1/8 in. depth of fill material applied within annulus on top surface of floor. On bottom of assembly, a min 1/2 in. depth of fill material applied within annulus on bottom surface of ceiling. Fill material to be forced into interstices of cable bundle to max extent possible on both sides Additional fill material to be installed such that a min 1/2 in. thick crown is formed around the through penetrant on both sides of floor-ceiling assembly. A/D FIRE PROTECTION SYSTEMS INC — A/D FireBarrier Silicone

\* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.



Last Updated on 2002-11-11

May 19, 2005 F Rating — 1 Hr T Rating — 1 Hr

System No. F-C-5002

L Rating At Ambient — 7 CFM/sq ft

1. Floor Assembly — The fire rated wood truss or combination wood and steel truss Floor-Ceiling assembly shall be constructed of the materials and in the manner described in the individual L500-Series Designs in the UL Fire Resistance Directory and shall include the following construction features: A. **Trusses** — Min 12 in. (305 mm) deep parallel chord trusses fabricated from nom 2 by 4 in. (51 by 102 mm) lumber in conjunction with galv steel truss plates or **Structural Wood Members\*** with bridging as required.

B. Flooring — Nom 3/4 in. (19 mm) thick plywood flooring with or without Floor Topping Mixture\*. Max diam of

hole-sawed opening in flooring is 7 in. (178 mm). C. Furring Channels — Rigid or resilient galv steel furring channels installed perpendicular to bottom chord of

D. Gypsum Board\* — Nom 4 ft (122 cm) wide by 5/8 in. (16 mm) thick, screw-attached to furring channels. Max diam of hole-sawed opening in gypsum board ceiling is 7 in. (178 mm). 2. Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 10 (or heavier) steel pipe or nom 3 in. (76 mm) diam (or smaller) Type L (or heavier) copper pipe. Pipe to be installed approximately midway between trusses and centered in circular cutouts in flooring (Item 1B) and gypsum board ceiling (Item 1D). Diam of circular cutouts in flooring and gypsum wallboard ceiling to be 1/2 to 3/4 in. (13 to 19 mm) larger than outside diam of pipe covering (Item 3) or tube insulation (Item 3A) on pipe. Pipe to be rigidly supported on both sides of Floor-Ceiling assembly. 3. Pipe Covering\* — Nom 1 in. (25 mm) thick hollow cylindrical heavy density (min 3.5 pcf or 56 kg/m3) glass fiber units jacketed on the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing lap tape. Transverse joints secured with metal fasteners or with butt strip tape supplied with the product.

See Pipe and Equipment Covering — Materials\* (BRGU) category in Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used. 3A. **Tube Insulation** — **Plastics+** — As an alternate to the glass fiber pipe covering (Item 3), nom 1/2 or 5/8 in. (13 or 16 mm) thick acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible foam furnished in the form of tubing with skin may be used.

See Plastics (QMFZ2) category in the Recognized Component Directory for names of manufacturers. Any Recognized Component tube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used.

4. Fill, Void or Cavity Materials\* — Wrap Strip — Nom 1/4 in. (6 mm) thick intumescent elastomeric material faced on one side with aluminum foil, supplied in 2 in. (51 mm) wide strips. Nom 2 in. (51 mm) wide strip tightly wrapped around pipe covering or tube insulation (foil side exposed), secured with two steel tie wires and slid into hole-sawed opening in flooring (Item 1B) and in gypsum wallboard ceiling (Item 1D). Bottom edge of wrap strip to project 9/16 to 11/16 in. (14 to 18 mm) below bottom surface of flooring and below bottom (ceiling) surface of gypsum wallboard.

3M COMPANY — Types FS-195, FS-195+ 5. Fill, Void or Cavity Materials\* — Caulk or Sealant — Nom 1/4 in. (6 mm) thickness of caulk to be applied to the exposed edge of the wrap strip layer (top of flooring and bottom of gypsum board ceiling). Generous application of caulk to be applied to fill all gaps at the wrap strip/flooring and wrap strip/gypsum board ceiling

3M COMPANY — CP 25WB+, IC 15WB+, FireDam 150+ caulk or FB-3000 WT sealant \* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Last Updated on 2005-05-19

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO COMPLIANCE WITH ALL APPLICABLE CODES DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851 ROPERTY ADDRESS: 3777 OLD BERRY POINT OB DESCRIPTION: New construction of a 3 stor units. The building provi 30,455 GSF

FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595

PERMIT REVIEW STAMP

**ISSUE HISTORY** 

11/22/19 SCHEMATIC DESIGN

02/28/20 PERMIT REVIEW SET

12/06/19 DESIGN DEVELOPMENT

**REVISION HISTORY** 

Description

Description

Date


Date


www.fuglebergkoch.com


MICHAEL E. GOVE


THE ROBERT 09/10/2019

FT. MYERS, FL UL REFERENCE DIRECTORY - PENETRATIONS









ATTIC VENT CALCULATIONS - AREA 1A					
	REQUIRED PROVIDED				
TOTAL ROOF AREA PER FBC 2017 (1/300) REQ. VENTILATED AREA	= 900 Sq.Ft. x 0.0033 2.97 Sq.Ft.				
TOTAL SOFFIT LIN. FT. OPENING NET VENTILATION	78 Lin.Ft. x 0.03 Sq.Ft.				
NET FREE AREA	1.49 Sq.Ft. 2.34 Sq.Ft.				
TOTAL RIDGE VENT LIN. FT. OPENING NET VENTILATION	12 Lin.Ft. x 0.125 Sq.Ft.				
NET FREE AREA	1.49 Sq.Ft. 1.50 Sq.Ft.				
TOTAL VENTILATED AREA	2.97 Sg.Ft. 3.84 Sg.Ft.				

ATTIC VENT CALCULATIONS - AREA 1B							
ATTIO VENT CALCOLATIONS - AILEA ID							
	REQUIRED	PROVIDED					
TOTAL ROOF AREA PER FBC 2017 (1/300) REQ. VENTILATED AREA	= 1417 Sq.Ft. x 0.0033 4.68 Sq.Ft.						
TOTAL SOFFIT LIN. FT.  OPENING NET VENTILATION + 10'-0" TAMYLN		75 Lin.Ft. x 0.03 Sq.Ft.					
NET FREE AREA  TOTAL RIDGE VENT LIN. FT.  OPENING NET VENTILATION [	2.34 Sq.Ft.	2.25 Sq.Ft. 20 Lin.Ft. x 0.125 Sq.Ft.					
NET FREE AREA	2.34 Sq.Ft.	2.50 Sq.Ft.					
TOTAL VENTILATED AREA	4.68 Sq.Ft.	4.75 Sq.Ft.					

	VENTILATION SCHEDULE	
ROOF VENT	MFGR. & MODEL No.	FREE AREA / L.F.
SOFFIT VENT AT EAVE	HARDIE SOFFIT PANEL	0.03 SQ. FT.
SOFFIT VENT AT EAVE	TAMLYN VENTED SOFFIT	0.062 SQ. FT.
RIDGE VENT	CERTAINTEED	0.125 SQ. FT.
OFF RIDGE VENT	4'-0" OFF RIDGE SHINGLE "FLAMCO"	0.96 SQ. FT.
	6'-0" OFF RIDGE SHINGLE "FLAMCO"	1.46 SQ. FT.

ATTIC VENT CALCULATIONS - AREA 1C					
	REQUIRED	PROVIDED			
TOTAL ROOF AREA PER FBC 2017 (1/300) REQ. VENTILATED AREA	= 1514 Sq.Ft. x 0.0033 5.00 Sq.Ft.				
TOTAL SOFFIT LIN. FT. OPENING NET VENTILATION [+ 10'-0" TAMYLN]		80 Lin.Ft. x 0.03 Sq.Ft.			
NET FREE AREA	2.50 Sq.Ft.	2.4 Sq.Ft.			
TOTAL RIDGE VENT LIN. FT. OPENING NET VENTILATION		20 Lin.Ft. x 0.125 Sq.Ft.			
NET FREE AREA	2.50 Sq.Ft.	2.50 Sq.Ft.			
TOTAL VENTILATED AREA	5.00 Sq.Ft.	4.90 Sq.Ft.			

TAMLYN ADDED ANOTHER .62 SQ. FT. IN FREE AIR SPACE.

ATTIC VENT CALCULATIONS - AREA 1D					
	REQUIRED	PROVIDED			
TOTAL ROOF AREA PER FBC 2017 (1/300) REQ. VENTILATED AREA	= 257 Sq.Ft. x 0.0033 0.85 Sq.Ft.				
TOTAL SOFFIT LIN. FT. OPENING NET VENTILATION	0.00 Oq.1 t.	68 Lin.F x 0.03 Sq.F			
NET FREE AREA	0.42 Sq.Ft.	2.04 Sq.I			
TOTAL RIDGE VENT LIN. FT.  OPENING NET VENTILATION 4'-0" OFF RIDGE VENT		1 Lin.l x 0.96 Sq.l			
NET FREE AREA	0.42 Sq.Ft.	0.96 Sq.I			
TOTAL VENTILATED AREA	0.85 Sq.Ft.	3.00 Sq.F			

## **GENERAL NOTES:**

- PAINT ALL ROOF VENTS & PENETRATIONS TO MATCH ROOF SHINGLE COLOR
- 2. COORDINATE DOWNSPOUT DISCHARGE WITH CIVIL DRAWINGS. WHERE NOT TAKEN TO STORM, PROVIDE SPLASH BLOCK.
- 3. DOWNSPOUTS AND GUTTERS SHOWN ARE MIN.

## **LEGEND**:

AREA 1D

- AREA 1D

AREA 1B


AREA 1C


C GUTTER

AREA 1A

AREA 1A

OSB DRAFTSTOPPING - TO UNDERSIDE OF ROOF DECK









**ROOF PLAN NOTES & LEGEND** 

1/8" = 1'-0" **ISSUE HISTORY** 11/22/19 SCHEMATIC DESIGN 2 12/06/19 DESIGN DEVELOPMENT 02/28/20 PERMIT REVIEW SET **REVISION HISTORY** No. Date Description



PERMIT REVIEW STAMP

2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www.fuglebergkoch.com BR569

CITY OF FORT MYERS


DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00851
PROPERTY ADDRESS: 3777 OLD BERRY POINT

JOB DESCRIPTION: New construction of a 3 story apartment building that includes 22 units of 3 types and 6 direct entry garage units. The building provides 30,455 GSF

THIS PLAN REVIEWED FOR SUBSTANTIAL CODE COMPLIANCE WITH ALL APPLICABLE CODES.

MICHAEL E. GOVE FLORIDA LICENSE #

FT. MYERS, FL BUILDING TYPE 1 - ROOF



AREA 1D -

AREA 1D

10' - 0"

TAMLYN VENTED SOFFIT


AREA 1A


1/32" = 1'-0"


AREA 1C


DRAFTSTOP LEGEND - BLDG 1


TAMLYN VENTED SOFFIT































































								FINISH	SCHEDULE -	UNITS					
					WALLS								CEILING		
		FLOOR	BASE	CROWN	NOR	TH	EAS	Т	SOU	TH	WES	ST .			
MARK	SPACE DESIGNATION	MATERIAL	MATERIAL	MOLDING	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	REMARKS
J01	ENTRY														
J02	KITCHEN 1	LVT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J03	LIVING/DINING	LVT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J04	UTILITY	CONC	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J05	BEDROOM 1	CARPET	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J06	WIC	CARPET	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J07	BATHROOM 1	СТ	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J08	BATHROOM 2	СТ	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J09	LAUNDRY	LVT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J10	KITCHEN 2	LVT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J11	BATHROOM 3	CT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J12	BEDROOM 2	CARPET	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J13	BEDROOM 3	CARPET	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J14	HALLWAY	LVT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J15	BATHROOM 4	СТ	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	
J16	SOLARIUM	LVT	WD		GWB	PT	GWB	PT	GWB	PT	GWB	PT	GWB	PT	




CITY OF FORT MYERS
THIS PLAN REVIEWER COMPTY


THIS PLAN REVIEWED FOR SUBSTANTIAL CODE COMPLIANCE WITH ALL APPLICABLE CODES.



THE DODEDT	Checked: DN
THE ROBERT	Approval: MC
	Date: 09/10/2019
FT. MYERS, FL	Project #: 5592
FINISH SCHEDU	JLES
A 2 4 2	

A3.13












































1 2 3 4 5	CITY OF FORT MYERS
DOOR SCHEDULE-COMMON AREA   DOOR   SCHEDULE-COMMON AREA   DOOR   SCHEDULE-COMMON AREA   DOOR   SCHEDULE-COMMON AREA   DOOR   SCHEDULE   DOOR   SCHEDULE	THIS PLAN REVIEWED FOR SUBSTANTIAL CODE COMPLIANCE WITH ALL APPLICABLE CODES.  DATE APPROVED: 06/17/20 PERMIT NUMBER: BLD2020-00851 PROPERTY ADDRESS: 3777 OLD BERRY POINT  JOB DESCRIPTION: New construction of a 3 story apartment building that includes 22 units of 3 types and 6 direct entry garage units. The building provides 30,455 GSF  A
U1   3'-0'   6'-8'   13/4"   FG	B  B
DOOR NOTES:  OFFSW WALL  FIRE CENT SCING  COARD PLEIDUR A  A ALL HEP DOORS AND HAMMES TO MARK APPROVED  COEFFS AND FORTH INCIDENT  COARD PLEIDUR  BURNING  OFFSW WALL  FIRE CENT SCING  COARD PLEIDUR  SIGNING  OFFSW WALL  FIRE CENT SCING  COARD PLEIDUR  SIGNING  OFFSW WALL  FIRE CENT SCING  COARD PLEIDUR  SIGNING  OFFSW WALL  SIGNING  OFFSW WALL	OARD /2" NELS  OR  C DARD  PERMIT REVIEW STAMP
D OF SMANUTES OF STANDARD FIRE TEST EXPOSURE  HARDWARE NOTES:  A REFER TO SPECIFICATIONS FOR HARDWARE GROUPS, ALL HARDWARE TO MEET TO GROUP RICH HARD HARD HAVE 107 THE REPORT HARDWARE TO MEET TO GROUP RICH HARD HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARD HAVE 107 THE RICH HARDWARE TO MEET TO GROUP RICH HARDWARE TO GROUP RICH HARDWARE TO MEET TO GROUP RICH H	DARD    1
F OOR AS SCHEDULED CONT. BEAD OF CAULKING SELFOND  2x WOOD FRAMING — CONT. BEAD OF CAULKING SIDING  INTERIOR  INTERIOR  CONT. BEAD OF CAULKING SIDING  CONT. SEAD OF CAULKING SIDING  FIBER CEMENT — CONT. SEALANT — SELFOND SELFOND SIDING  FIBER CEMENT — CONT. SEALANT — SELFOND SE	FUGLEBERG KOCH  2555 Tample Trail Winter Park FL 32789 (407) 629,0595
EXT. DOOR JAMB DETAIL (BALCONY)  F7 EXT. DOOR JAMB DETAIL- ENTRY  F9 GARAGE DOOR JAMB DETAIL  F1 INTERIOR  BALCONY  BREEZEWAY  BREEZEWAY	
SELF-AD-PED FLEXILE FLASHING ONE SHARING O	THE ROBERT  THE ROBERT  Approval: MG  Date: 09/10/2019  FT. MYERS, FL  Drawn: DM  Checked: DM  Approval: MG  Date: 09/10/2019  Project #: 5592  DOOR SCHEDULE AND  DETAILS
H3 EXTERIOR DOOR THRESHOLD DETAIL  H5 EXT. DOOR THRESHOLD DETAIL-BALCONY  THRESHOLD DETAIL-BALCO	A7.01  PLOTTED: 6/2/2020 1:13:16 PM

