

**NISER DETAIL** 

# 61G15-32.004 DESIGN OF WATER BASED FIRE PROTECTION SYSTEMS.

- (1) WATER BASED FIRE PROTECTION SYSTEMS INCLUDE, BUT ARE NOT LIMITED TO, AUTOMATIC SPRINKLER SYSTEMS OF WET, DRY, FINE WATER SPRAY (MIST), MANUAL AND DELUGE VALVE CONTROLLED TYPES, PUMPING SYSTEMS, STANDPIPES, FIRE WATER MAINS AND DEDICATED FIRE PROTECTION WATER SOURCES.
- (2) TO ENSURE MINIMUM DESIGN QUALITY IN FIRE PROTECTION SYSTEM ENGINEERING DOCUMENTS, SAID DOCUMENTS SHALL INCLUDE AS A MINIMUM THE FOLLOWING INFORMATION WHEN APPLICABLE:
- (A) THE POINT OF SERVICE FOR THE FIRE PROTECTION WATER SUPPLY AS DEFINED BY

THE POINT OF SERVICE AND FIRE DEPARTMENT CONNECTION IS LOCATED ON CIVIL DRAWINGS

(B) APPLICABLE NFPA STANDARD TO BE APPLIED, OR IN THE CASE WHERE NO SUCH STANDARD EXISTS, THE ENGINEERING STUDY, JUDGEMENTS, AND/OR PERFORMANCE BASED ANALYSIS AND CONCLUSIONS.

NFPA 13R, 2013 EDITION, INSTALLATION OF SPRINKLER SYSTEMS NFPA 24, 2010 EDITION, INSTALLATION OF FIRE SERVICE MAINS.

(C) CLASSIFICATION OF HAZARD OCCUPANCY FOR EACH ROOM OR AREA.

SYSTEM DESIGNED PER NFPA 13R USING A 0.05 GPM/SQ FT FOR ALL DWELLING UNITS (RESIDENTIAL OCCUPANCY) USING RESIDENTIAL SPRINKLERS.

(D) DESIGN APPROACH, WHICH INCLUDES SYSTEM TYPE, DENSITIES, DEVICE TEMPERATURE RATING, AND SPACING FOR EACH SEPARATE HAZARD OCCUPANCY.

SPRINKLER SYSTEM TO EXTEND INTO ALL AREAS IN ACCORDANCE WITH NFPA 13R LISTED AND APPROVED UPRIGHT SPRINKLER HEADS TO BE PROVIDED. SEE FIRE PROTECTION SCHEDULE ON THIS SHEET. HEADS SHALL BE RATED AT 155 DEGREES F.

(E) CHARACTERISTICS OF WATER SUPPLY TO BE USED, SUCH AS MAIN SIZE AND LOCATION, WHETHER IT IS DEAD-END OR CIRCULATING; AND IF DEAD-END, THE DISTANCE TO THE NEAREST CIRCULATING MAIN, AS WELL AS ITS MINIMUM DURATION AND RELIABILITY FOR THE MOST HYDRAULICALLY DEMANDING DESIGN AREA

THE WATER SUPPLY FOR THIS SPRINKLER SYSTEM IS PROVIDED BY A 10 INCH PRIVATELY OWNED WATER MAIN. THE DURATION FOR THE MOST REMOTE HYDRAULICALLY DEMANDING AREA IS 100 G.P.M. FOR 60 MINUTES.

(F) WHEN PRIVATE OR PUBLIC WATER SUPPLIES ARE USED, THE FLOW TEST DATA, INCLUDING TIME AND DATE OF TEST, WHO CONDUCTED THE TEST OR SUPPLIED INFORMATION, TEST ELEVATION, STATIC GAUGE PRESSURE AT NO FLOW, FLOW RATE WITH RESIDUAL GAUGE PRESSURE, HYDRANT BUTT COEFFICIENT, AND LOCATION 🌶 THE TEST IN RELATION TO THE HYDRAULIC POINT OF SERVICE.

PROVIDED BY SPRINKLER CONTRACTOR.

(G) VALVING AND ALARM REQUIREMENTS TO MINIMIZE POTENTIAL FOR IMPAIRMENTS AND UNRECOGNIZED FLOW OF WATER.

THE FIRE SPRINKLER RISER FOR THE BUILDING WILL BE EQUIPPED WITH A WATER FLOW SWITCH WITH A LOCAL ALARM AND OFF-SITE MONITORING.

(H) MICROBIAL INDUCED CORROSION (MIC). THE ENGINEER OF RECORD SHALL MAKE REASONABLE EFFORTS TO IDENTIFY WATER SUPPLIES THAT COULD LEAD TO MICROBIAL INDUCED CORROSION (MIC). SUCH EFFORTS MAY CONSIST OF DISCUSSIONS WITH LOCAL WATER PURVEYOR AND/OF FIRE OFFICIAL, FAMILIARITY WITH CONDITIONS IN THE LOCAL AREA, OR LABORATORY TESTING OF WATER SUPPLIES. WHEN CONDITION ARE FOUND THAT MAY RESULT IN MIC CONTAMINATION OF THE FIRE PROTECTION PIPING, THE ENGINEER SHALL DESIGN CORRECTIVE MEASURES.

BASED ON DISCUSSIONS WITH THE LOCAL WATER UTLITIES, THERE HAVE BEEN NO INDICATIONS OF M.I.C.

(I) BACKFLOW PREVENTION AND METERING SPECIFICATIONS AND DETAILS TO MEET LOCAL WATER PREVENTER REQUIREMENTS INCLUDING MAXIMUM ALLOWABLE PRESSURE DROP.

THE BACKFLOW PREVENTION DEVICE ASSEMBLY AND METERING EQUIPMENT WILL MEET THE REQUIREMENTS OF THE LOCAL WATER PURVEYOR. MAX. PRESSURE DROP 8 PSI.

(J) QUALITY AND PERFORMANCE SPECIFICATIONS OF ALL YARD AND INTERIOR FIRE PROTECTION COMPONENTS.

ALL NEW YARD AND INTERIOR FIRE PROTECTION EQUIPMENT SHALL BE U.L. LISTED AND F.M. APPROVED.

(3) CONTRACTOR SUBMITTALS WHICH DEVIATE FROM THE ABOVE MINIMUM DESIGN PARAMETERS SHALL BE CONSIDERED MATERIAL DEVIATIONS AND REQUIRE SUPPLEMENTAL ENGINEERING APPROVAL AND DOCUMENTATION.

THE SUCCESSFUL FLORIDA LICENSED FIRE PROTECTION CONTRACTOR SHALL SUBMIT FIRE PROTECTION SHOP DRAWINGS AS NEEDED TO FULFILL THE REQUIREMENTS FOR A FIRE SPRINKLER PERMIT.

(4) IN THE EVENT THE ENGINEER OF RECORD PROVIDES MORE INFORMATION AND DIRECTION THAN IS ESTABLISHED ABOVE, HE OR SHE SHALL BE HELD RESPONSIBLE FOR THE TECHNICAL ACCURACY OF THE WORK IN ACCORDANCE WITH APPLICABLE CODES, STANDARDS, AND SOUND ENGINEERING PRINCIPLES.

(5) THE UNDERGROUND AND INSIDE PIPING SHALL BE HYDROSTATICALLY TESTED AT 200 PSI FOR 2 HOURS PER 16.2.1

(6) THE FIRE PROTECTION CONTRACTOR SHALL COMPLY WITH CHAPTER 10 SECTION 10.2:

A. ALL UNDERGROUND PIPING FROM THE WATER MAIN TO THE RISER SHALL BE COMPLETELY FLUSHED. THE FLUSHING SHALL CONTINUE FOR SUFFICIENT TIME TO ENSURE CLEANING.

B. THE MINIMUM FLOW SHALL NOT BE LESS THAN: HYDRAULICALLY CALCULATED DEMAND INCLUDING HOSE STREAM ALLOWANCE, FLOW RATE AVAILABLE UNDER FIRE CONDITIONS.

(7) ALL PIPING AND APPURTENANCES SHALL BE PRESSURE TESTED AT 200 PSI OR 50 PSI IN EXCESS OF SYSTEM PRESSURE, WHICH EVER IS GREATER, FOR A MINIMUM OF 2 HOURS WITH OUT ANY LOSSES.

FIRE PROTECTION SCHEDULE								
SYMBOL	TEMP. RATING	TYPE	ORIFICE SIZE	K-FACTOR	FINISH	ACCESSORIES	SELECTION	
•	155°F	SEMI-RECESSED PENDENT	1/2"	4.9	WHITE	WHITE ESCUTCHEON	TYCO RAPID RESPONSE SERIES LFII	
	155°F	SEMI-RECESSED PENDENT	1/2"	5.6	WHITE	WHITE ESCUTCHEON	TYCO RAPID RESPONSE SERIES LFII	
•	155°F	HORIZONTAL SIDEWALL	1/2"	4.2	CHROME	-	TYCO RAPID RESPONSE SERIES	
				7			<b>†</b>	

HANGER SPACING FOR CPVC PIPING					
MAX. SPACING (FEET)					
5-1/2 6					
6-1/2					
8					
9					

# 

- 1. THESE DRAWINGS ARE INTENDED TO ILLUSTRATE THE DESIGN INTENT AND AID IN THE COORDINATION OF ELEMENTS OF A FIRE PROTECTION SPRINKLER DESIGN.
- 2. THE DESIGN OF THE FIRE PROTECTION SPRINKLER SYSTEM SHALL BE PROVIDED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION AND THE APPLICABLE STANDARDS FROM THE NATIONAL FIRE PROTECTION ASSOCIATION
- 3. THE FIRE PROTECTION SRRINKLER DESIGN SHALL BE COORDINATED WITH OTHER ASPECTS OF THE BUILDING DESIGN INCLUDING, BUT NOT LIMITED TO, FIRE ALARM, ELECTRICAL POWER AND LIGHTING, REFLECTED CEILING, DUCTWORK, PLUMBING AND THE BUILDING STRUCTURAL SYSTEM.
- 4. THE FIRE PROTECTION SPRINKLER DESIGN DRAWINGS SHALL BE SUBMITTED FOR COORDINATION PRIOR TO INSTALLATION OF THE SYSTEM. INSTALLATION WITHOUT COORDINATION WILL BE AT THE CONTRACTOR'S RISK AND REWORK OF THE SYSTEM SHALL BE PROVIDED WITHOUT ADDITIONAL COST.
- APPLICABLE FIRE CODES. FLORIDA FIRE PREVENTION CODE FIFTH EDITION, BASED ON NFPA 1, FIRE CODE, 2013 EDITION AND NFPA 101, LIFE SAFETY CODE, 2013 EDITION.
- 6. A STATE OF FLORIDA LICENSED FIRE SPRINKLER CONTRACTOR SHALL PROVIDE THE LAYOUT DOCUMENTS.

- 1. ALL WORK & MATERIAL SHALL BE DONE IN ACCORDANCE WITH NFPA 13R AND THE LOCAL AUTHORITY.
- 2. ALL PIPE AND FITTINGS TO BR CPVC, UNLESS NOTER OTHERWISE EXCEPT FOR THE BLDG. RISER WHICH SHALL BE SCHEDULE 40 GALVANIZED STEEL
- ALL RESIDENTIAL SPRINKLER HEAD SPACING TO BE IN ACCORDANCE WITH THE MANUFACTURER'S LISTING.
- 4. ALL FIREWALL PENETRATIONS TO BE SEALED IN ACCORDANCE WITH THEIR
- 5. PROVIDE SIGN ON DOOR INDICATING "FIRE RISER INSIDE".
- 6. ALL FIRE SPRINKLER WORK, INCLUDING CHANGES, ADDITIONS, RELOCATIONS, IMPROVEMENTS, AND/OR MODIFICATIONS TO THE FIRE SPRINKLER SYSTEM, MUST BE DONE PER NFPA-13 2013 EDITION, BY A LICENSED FIRE SPRINKLER CONTRACTOR WITH SEPARATE PERMIT AND PLANS.

## DESIGN CRITERIA

**GENERAL NOTES** 

1. THE NUMBER OF DESIGN SPRINKLERS SHALL INCLUDE ALL SPRINKLERS WITHIN A COMPARTMENT UP TO A MINIMUM OF FOUR SPRINKLERS UNDER A FLAT, SMOOTH, HORIZONTAL CEILING, ANY LINTEL WITH 8" MINIMUM WILL DIVIDE AN AREA INTO TWO COMPARTMENTS.

FIRE PROTECTION SYMBOL LEGEND					
<b>—</b> F—	FIRE PROTECTION SUPPLY PIPING				
<b>→</b> ×	SOLENOID VALVE WITH TAMPER SWITCH				
—∳ <sup>TS</sup>	BUTTERFLY VALVE WITH TAMPER SWITCH				
	FLOW SWITCH				
<b>—</b> FDC <b>—</b>	FIRE DEPARTMENT CONNECTION PIPING				
/	PIPE HANGER				
$\bigcirc$	POST INDICATING VALVE				
Q,	FIRE DEPT. CONNECTION				

## **ABBREVIATIONS**

ONT.	CONTINUATION	
ETR	EXISTING TO REMAIN	
N	NEW HEAD	
F	FIRE	
FH	FIRE HYDRANT	
FDC	FIRE DEPARTMENT CONNECTION	
FS	FLOW SWITCH	
GPM	GALLONS PER MINUTE	
PSI	POUNDS PER SQUARE INCH (WATER PRESSURE)	
PIV	POST INDICATING VALVE	
R	RELOCATE HEAD	

## FIRE HYDRANT FLOW TEST DATA TEST DATE: 6/17/16

TAMPER SWITCH

FORT MYERS FIRE DEPARTMENT TEST BY: THE FLOW HYDRANT #314425H045

LOCATION: SHOEMAKER LANE FORT MYERS FLORIDA

STATIC PRESSURE 56 PSI RESIDUAL PRESSURE: 48 PSI


2226 GPM

GENERAL NOTES

PITOT SIZE:

A CURRENT FIRE HYDRANT FLOW TEST HAS BEEN REQUESTED TO BE PERFORMED BY THE FORT MYERS FIRE DEPARTMENT AND THE RESULTS WHEN RECEIVED WILL BE PROVIDED.

2-1/2"



## **ISSUE HISTORY** No. Date 11/22/19 SCHEMATIC DESIGN DESIGN DEVELOPMENT 2 12/06/19 02/28/20 PERMIT REVIEW SET

PERMIT REVIEW STAMP

CITY OF FORT MYERS THIS PLAN REVIEWED FOR SUBSTANTIAL CO

DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00848 ROPERTY ADDRESS: 3810 OLD BERRY POINT

# **REVISION HISTORY** Date Description

06/03/20 PERMIT COMMENT RESPONSES

2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www.fuglebergkoch.com




KYLE J. CARTIER, P.E. 53269 JEFF A. KIRKMAN, P.E. 65629

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.


THE ROBER 09/10/2019 FT. MYERS, FL

LEGEND, SCHEDULES AND DETAILS - FIRE PROTECTION

FP0.01



PLOTTED: 6/4/2020



PERMIT REVIEW STAMP ISSUE HISTORY 1 11/22/19 SCHEMATIC DESIGN
2 12/06/19 DESIGN DEVELOPMENT REVISION HISTORY Date Description 05/06/20 PERMIT COMMENT RESPONSES FUGLEBERG KOCH 2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www.fuglebergkoch.com BR569

REFERENCE

The line up from BE | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 |




PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THE ROBERT

FT. MYERS, FL

BUILDING TYPE 1 - 2ND LEVEL - FIRE PROTECTION

**FP2.02** 



PERMIT REVIEW STAMP ISSUE HISTORY 1 11/22/19 SCHEMATIC DESIGN
2 12/06/19 DESIGN DEVELOPMENT REVISION HISTORY Date Description 05/06/20 PERMIT COMMENT RESPONSES FUGLEBERG KOCH

The line up from BE | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 |






THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THE ROBERT


09/10/2019 5592 FT. MYERS, FL

BUILDING TYPE 1 - 3RD LEVEL - FIRE PROTECTION

**FP2.03** 



PLOTTED: 6/4/2020 10:26:08 AM



THIS PLAN REVIEWED FOR SUBSTANTIAL CODE COMPLIANCE WITH ALL APPLICABLE CODES.

DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00848
PROPERTY ADDRESS: 3810 OLD BERRY POINT

JOB DESCRIPTION: New construction of a 3 story apartment building that includes 27 units of a 4 types
and 6 direct entry direct entry garage units. The building prov

1 THIS PLAN REVIEWED FOR SUBSTANTIAL CODE COMPLIANCE WITH ALL APPLICABLE CODES.

DATE APPROVED: 06/17/20
PERMIT NUMBER: BLD2020-00848
PROPERTY ADDRESS: 3810 OLD BERRY POINT

JOB DESCRIPTION: New construction of a 3 story apartment building that includes 27 units of a 4 types
and 6 direct entry direct entry garage units. The building prov

New York Property Address: 1 This PLAN REVIEW BLD 2020-00848

PROPERTY ADDRESS: 3810 OLD BERRY POINT

JOB DESCRIPTION: New construction of a 3 story apartment building that includes 27 units of a 4 types

and 6 direct entry direct entry garage units. The building prov

PERMIT REVIEW STAMP



CONSULTANT

SALAS O'BRIEN

| expect a difference |

3501 Quadrangle Boulevard, Suite 100
Orlando, Florida 32817
(407) 380-0400

CERT. OF AUTH. NO. 6106

GARY A. WILKERSON, P.E. 43167

| KYLE J. CARTIER, P.E. 53269
| JEFF A. KIRKMAN, P.E. 65629
| ADAM S. LEVINE, P.E. 77010

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.


THE ROBERT

Project

BUILDING TYPE 2 - 2ND LEVEL - FIRE PROTECTION

**FP2.06** 

OTTED: 6/4/2020



The line up from BE | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 |

ISSUE HISTORY 1 11/22/19 SCHEMATIC DESIGN
2 12/06/19 DESIGN DEVELOPMENT REVISION HISTORY Description 05/06/20 PERMIT COMMENT RESPONSES






THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.


THE ROBERT

09/10/2019 5592

BUILDING TYPE 2 - 3RD LEVEL - FIRE PROTECTION

**FP2.07** 










THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THE ROBERT

FT. MYERS, FL

BUILDING TYPE 3 - GROUND LEVEL - FIRE PROTECTION

FP2.09




BUILDING TYPE 3 - 2ND LEVEL - FIRE PROTECTION

3/32" = 1'-0"

REFERENCE

The line up from BE | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 | 06/17/20 |



JEFFREY A. KIRKMAN
STATE OF FLORIDA
PROFESSIONAL ENGINEER
Digitally signed by Jeffrey A Kirkman
Date: 2020.06.04 10:36:56-04'00' **LICENSE NO. 65629** 

PERMIT REVIEW STAMP

ISSUE HISTORY

		•
1	11/22/19	SCHEMATIC DESIGN
2	12/06/19	DESIGN DEVELOPMENT
3	02/28/20	PERMIT REVIEW SET
	REVI	SION HISTORY
No.	Date	Description
1	05/06/20	PERMIT COMMENT RESPONS



2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595 www. fuglebergkoch.com BR569



THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.


THE ROBERT

09/10/2019 5592 FT. MYERS, FL

**BUILDING TYPE 3 - 2ND** 


LEVEL - FIRE PROTECTION

FP2.10



BUILDING TYPE 3 - 3RD LEVEL - FIRE PROTECTION

3/32" = 1'-0"





THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, P.E. 05629

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY JEFFREY A. KIRKMAN, PE ON DATE INDICATED IN DIGITAL SIGNATURE USING A DIGITAL SIGNATURE.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

THE ROBERT

Check
Approx
Date:

FT. MYERS, FL

BUILDING TYPE 3 - 3RD LEVEL - FIRE PROTECTION

FP2.11

LOTTED: 6/4/2020