
VICINITY MAP



PROJECT SITE

N



THE ROBERT

MADISON, ALABAMA

PROJECT NARRATIVE:

This project narrative is provided as a brief outline of the proposed scope of building improvements for this Project.

The Project consists of the construction of a Clubhouse with in a new multi-unit residential rental apartment complex in Madison, AL accessed off of Dunlop Blvd and Lime Quarry Rd. The program includes a total of 270 dwelling units of 7 unit types (1, 2, & 3 bedroom).

The Clubhouse shall serve 6 multi-family residential buildings of 2 separate building types and 10 duplex townhomes consisting of 20 residences. The Clubhouse is classified as Type V(B) construction and is designed as a wood frame structure that includes engineered truss components for roofs. The buildings are placed on concrete slab on grade foundations with integral thickened edges and grade beams.

The Project program also includes amenity buildings which include a Pool Pavilion, a Fitness Center and a Trash enclosure, that are submitted under separate packages.

The Project scope includes site engineering and landscape improvements that are submitted under separate cover.

SYMBOL KEY:

DOOR SYMBOL	NUMBERED BY TYPE REFER TO SCHEDULE
WINDOW SYMBOL	NUMBERED BY TYPE REFER TO SCHEDULE
WALL TAG	WALL TYPE OR UL
GRID LINE TARGET	A,B,C, ETC. IN ONE DIRECTION 1,2,3, ETC. IN THE OTHER
ROOM TAG	ROOM NUMBER
TITLE	DRAWING NUMBER; SCALE
ELEVATION REFERENCES	DIRECTION OF VIEW; SHEET NUMBER
SECTION REFERENCES	DIRECTION OF VIEW; SHEET NUMBER
DETAIL REFERENCES	DETAIL AREA; SHEET NUMBER
INTERIOR ELEVATIONS	VIEW NUMBER; DIRECTION OF VIEW; SHEET NUMBER
LEVEL REFERENCE	Name; Elevation
ROOF SLOPE ARROW	SLOPE; SLOPE DIRECTION
ROOF SLOPE	SLOPE
ACCESSORY TAG	LOCATION OF NOTE APPLICATION; NOTE NUMBER
NOTE TAG	LOCATION OF NOTE APPLICATION; NOTE NUMBER
LEVEL CHANGE	CHANGE IN LEVEL
REVISION MARK	REV. LOCATION; REV. No.

DEFERRED SUBMITTALS:

1) Deferral of any submittal items shall have the prior approval of the Building Official having jurisdiction.

2) Submittal documents for deferred submittal items shall be submitted to the Entity designated below for the project who shall review them. These will then be forwarded by the Owner to the Building Official having jurisdiction with a notation indicating that the deferred submittal documents have been reviewed and that they have been found to be in general compliance with the design of the project.

3) The deferred submittal items shall not be installed until their design and submittal documents have been approved.

LIST (INCLUDING BUT NOT LIMITED TO):

A) BUILDING RAILINGS & GUARDRAILS
REVIEW BY ARCHITECT

B) FIRE ALARM SYSTEM
REVIEW BY ARCHITECT

C) AUTOMATIC FIRE SUPPRESSION (SPRINKLER) SYSTEM REVIEW BY ARCHITECT

D) PRE-ENGINEERED (WOOD) FLOOR & ROOF TRUSS SYSTEMS
REVIEW BY ARCHITECT

E) BUILDING IDENTIFICATION AND WAYFINDING SIGNAGE REVIEW BY OWNER

F) SITE FENCING
REVIEW BY LANDSCAPE ARCHITECT

OWNER/DEVELOPER	ARCHITECT	CIVIL ENGINEER	STRUCTURAL	MECHANICAL / ELECTRICAL / PLUMBING	LANDSCAPE ARCHITECT	INTERIOR DESIGN	CONTRACTOR
ROHDIE MADISON, LLC ATTN: RON LEICHTNER 52 VANDERBILT NEW YORK, NEW YORK 10017 PHONE (212) 682-5784	FUGLEBERG KOCH PLLC FUGLEBERG KOCH ATTN: MICHAEL GOVE, AIA 2555 TEMPLE TRAIL WINTER PARK, FLORIDA 32789 PHONE (407) 629-0595 FAX (407) 628-1057	MULLINS, LLC MULLINS, LLC 2101 WEST CLINTON AVE, SUITE 503, HUNTSVILLE, AL PHONE (256) 690-5312	ASE ENGINEERING SERVICES, INC. ASE ENGINEERINGSERVICES, INC 10244 EAST COLONIAL DRIVE, SUITE 202 ORLANDO, FLORIDA 32817 PHONE (407) 677-5565 FAX (407) 730-2999	JOSEPH, LAWRENCE & CO J&C Consulting Engineers 1180 HARWOOD AVE. SUITE 3000 ALTAMONTE SPRINGS, FLORIDA 32714 PHONE (321) 972-4466	TBD ATTN: NAME ADDRESS CITY, FL 3xxxx (407) 123-4567	ALYSSA ROHDIE ATTN: ALYSSA ROHDIE 52 VANDERBILT NEW YORK, NEW YORK 10017 PHONE (212) 682-5784	ESSIAN CONSTRUCTION & DEVELOPMENT ATTN: RICHARD SHASSIAN 999 DOUGLAS AVE. STE 1115 ALTAMONTE SPRINGS, FLORIDA 32714 PHONE (407) 245-8920

ARCHITECTURAL ABBREVIATIONS

A	
ABV	ABOVE
ACC.FL.	ACCESS FLOOR
ACOUST.	ACOUSTICAL
ACT	ACOUSTICAL CEILING TILE
A.D.	AREA DRAIN
ADJ.	ADJACENT
ADJUST.	ADJUSTABLE
AFF	ABOVE FINISHED FLOOR
ALT.	ALTERNATE
ALUM.	ALUMINUM
AL	ALUMINUM
ANG.	ANGLE
ANOD.	ANODIZED
APPROX.	APPROXIMATE
ARCH.	ARCHITECTURAL
AUTO.	AUTOMATIC
AVG.	AVERAGE
B	
BD.	BOARD
BLBD.	BLACK BOARD
BLDG.	BUILDING
BLK/BLK'G	BLOCK OR BLOCKING
BM.	BEAM
BOT.	BOTTOM
B.O.	BOTTOM OF
BRK.	BRICK
BSMT.	BASEMENT
BTWN	BETWEEN
B.U.	BUILT-UP
B.W.	BOTH WAYS
C	
CAB.	CABINET
CB. / TB.	CORKBOARD/TACKBOARD
C.B.	CATCH BASIN
CEM.	CEMENT
CER.	CERAMIC
C.H.	CEILING HEIGHT
CIR.	CIRCLE
C.J.	CONTROL JOINT
CLG.	CEILING
CLKG.	CAULKING
CL/℄	CENTER LINE
CLO.	CLOSET
CLR.	CLEAR
CMU.	CONCRETE MASONRY UNIT
C.O.	CLEAR OPENING
COL.	COLUMN
COMM.	COMMUNICATION
CONC.	CONCRETE
CONN.	CONNECTION
CONST.	CONSTRUCTION
CONTR.	CONTRACTOR
COOR.	COORDINATE
CONT.	CONTINUOUS
CPT.	CARPET
CSMT.	CASEMENT
C.T.	CERAMIC TILE
CTR.	CENTER
D	
D.	DEPTH
DBL.	DOUBLE
DEG.	DEGREE
DET.	DETAIL
D.F.	DRINKING FOUNTAIN
DIA.	DIAMETER
DIAG.	DIAGONAL
DIFF.	DIFFUSER
DIM.	DIMENSION
DISP.	DISPOSAL
DIV.	DIVIDER
DN.	DOWN
DR	DOOR
DRAP.	DRAPERY
DS.	DOWNSPOUT
DTL.	DETAIL
DWG.	DRAWING
DWR.	DRAWER
DW	DISHWASHER
E	
E	EAST
EA.	EACH
E.F.	EACH FACE
E.J.	EXPANSION JOINT
E.I.F.S.	EXTERIOR INSULATION AND FINISH SYSTEM
EL. / ELEV.	ELEVATION
ELEC.	ELECTRICAL
ELEV.	ELEVATOR
EMER.	EMERGENCY
ENCL.	ENCLOSURE
EQ.	EQUAL
EQUIP.	EQUIPMENT
E.W.	EACH WAY
E.W.C.	ELECTRIC WATER COOLER
EXIST.	EXISTING
EXP. JT	EXPANSION JOINT
EXT.	EXTERIOR
EXTRU.	EXTRUDED
F	
F.A.	FIRE ALARM
F.D.	FLOOR DRAIN
F.D.C.	FIRE DEPARTMENT CONNECTION
FDN.	FOUNDATION
F.E.	FIRE EXTINGUISHER
F.E.C.	FIRE EXTINGUISHER CABINET
FED.	FEDERAL
F.F.	FINISH FLOOR
F.H.C.	FIRE HOSE CABINET
FIN.	FINISH
FIXT	FIXTURE
F.L.	FLOW LINE
FLR.	FLOOR
FLUOR	FLUORESCENT
F.O.B.	FACE OF BRICK
F.O.C.	FACE OF CONCRETE
F.O.F.	FACE OF FINISH
F.O.S.	FACE OF STUD
F.R.	FIRE RETARDANT
F.S.	FULL SIZE
FT.	FOOT OR FEET
FTG.	FOOTING
FURR	FURRING
FUT.	FUTURE
F.V.	FIELD VERIFY
G	
GA.	GAUGE
GALV.	GALVANIZE
G.B.	GRAB BAR
G.C.	GENERAL CONTRACTOR
GEN.	GENERAL
GL.	GLASS
GR.	GRADE
GYP.	GYPSUM
H	
H.	HIGH
H.B.	HOSE BIBB
H.C.	HOLLOW CORE
H/C	HANDICAPPED
HD.	HEAD
HDW.	HARDWARE
HDWD.	HARDWOOD
H.M.	HOLLOW METAL
HORIZ.	HORIZONTAL
H.P.	HORSE POWER
HR	HOUR
HT.	HEIGHT
HVAC	HEATING, VENTILATION AND AIR CONDITIONING
HOL.	HOLLOW
I	
IN.	INCHES
INSUL.	INSULATION
INT.	INTERIOR
J	
JAN.	JANITOR
J.F.	JOINT FILLER
JNT.	JOINT
JST.	JOIST
K	
KIT.	KITCHEN
L	
L.	LONG OR LENGTH
LAB.	LABORATORY
LAM.	LAMINATE
LAV.	LAVATORY
LBL.	LABEL
L.H.	LEFT HAND
LIN	LINEN
L.L.V.	LONG LEG VERTICAL
LN	LINE
L.P.	LOW POINT
LT.	LIGHT
LVR.	LOUVER
M	
MAS.	MASONRY
MATL.	MATERIAL
MAX.	MAXIMUM
M.C.	MINERAL CORE
MECH.	MECHANICAL
MEMB.	MEMBRANE
MEZZ.	MEZZANINE
MFTR	MANUFACTURER
MGR.	MANAGER
M.H.	MANHOLE
MIN.	MINIMUM
MISC.	MISCELLANEOUS
MLDG.	MOLDING
MLWK.	MILLWORK
M.O.	MASONRY OPENING
M.R.	MOISTURE RESISTIVE
MRB.	MARBLE
M.T.	MARBLE THRESHOLD
MTD.	MOUNTED
MTL.	METAL
MULL.	MULLION
N	
N	NORTH
N/A	NOT APPLICABLE
N.I.C.	NOT IN CONTRACT
NO.	NUMBER
NOM.	NOMINAL
N.T.S.	NOT TO SCALE
O	
O.C.	ON CENTER
OD	OVERFLOW DRAIN
OH.	OVERHEAD
OPNG.	OPENING
OPP.	OPPOSITE
P	
PART.	PARTITION
PH	PRE HUNG
PL.	PLATE
P.L.	PROPERTY LINE
P.LAM.	PLASTIC LAMINATE
PLAS.	PLASTER
PLYWD.	PLYWOOD
PNL.	PANEL
POL.	POLISHED
PR.	PAIR
PREC.	PRECAST
PREFAB.	PREFABRICATED
PROJ.	PROJECT
PROP.	PROPERTY
P.T.	PRESSURE TREATED
PTD.	PAINTED
PVC	POLYVINYL CHLORIDE
PVRS	PAVERS
Q	
Q.T.	QUARRY TILE
QTY.	QUANTITY
R	
R	RISER
RAD.	RADIUS
R.B.	RUBBER BASE
RCP	REFLECTED CEILING PLAN
RD	ROOF DRAIN
RE:	REFER TO...
REF.	REFRIGERATOR
REINF.	REINFORCED
REQD.	REQUIRED
REV.	REVISED / REVISION
RH	RIGHT HAND
RM	ROOM
R.O.	ROUGH OPENING
S	
S	SOUTH
SAFB	SOUND ACOUSTICAL FIBER BOARD
S.C.	SOLID CORE
SCHED.	SCHEDULE
SECT.	SECTION
S.F.	SQUARE FOOT / FEET
SHLV./SH	SHELVING
SHT.	SHEET
SIM.	SIMILAR
SPEC.	SPECIFICATION
SQ.	SQUARE
SR	SEMI RECESSED
S.S.	STAINLESS STEEL
STAGG.	STAGGERED
STD.	STANDARD
STL.	STEEL
STN.	STAINED
STOR.	STORAGE
STRUCT.	STRUCTURAL
SUSP.	SUSPENDED
SYST.	SYSTEM
T	
T	TREAD
T & G	TONGUE & GROOVE
TEMP GL.	TEMPERED GLASS
TER	TERRAZZO
TH.	THICK
T.O.	TOP OF
TOIL.	TOILET
TYP.	TYPICAL
U	
U.O.N.	UNLESS OTHERWISE NOTED
V	
VAR.	VARIES
V.B.	VINYL BASE
VCT	VINYL COMPOSITION TILE
VER.	VERIFY
VERT.	VERTICAL
V.I.F.	VERIFY IN FIELD
W	
W	WEST / WIDE
W/	WITH
W.C.	WATER CLOSET
W/D	WASHER/DRYER COMBO
WD.	WOOD
WP.	WATER PROOF
W.R.	WATER RESISTANT
W/O	WITHOUT
WWF	WELDED WIRE FABRIC

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, extension, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 *(407) 629-0595*
www. fuglebergkoch.com *AA26002103*

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

THE MADISON
MADISON, AL

CLUBHOUSE COVER SHEET

CH0.00

PLOTTED: 5/3/2022
3:03:32 PM

INDEX OF DRAWINGS

SHT #	SHEET NAME	REV. No.	DATE
00 - GENERAL			
CH0.00	CLUBHOUSE COVER SHEET		04/15/2022
A0.01b	SHEET INDEX		04/15/2022
CH0.01	CLUBHOUSE CODE/LIFE SAFETY PLAN		04/15/2022
00 - GENERAL: 3			
01 - CIVIL			
C0	COVER		
C1	EXISTING CONDITIONS & DEMOLITION PLAN		
C2	SITE PLAN		
C2.1	SITE PLAN		
C2.2	SITE PLAN		
C2.3	KEYNOTE PLAN		
C2.4	OVERALL SITE PLAN		
C3	WATER INFRASTRUCTURE PLAN		
C4.1	STORM INFRASTRUCTURE PLAN		
C4.2	STORM INFRASTRUCTURE PLAN		
C4.3	STORM INFRASTRUCTURE PROFILES		
C5	SANITARY SEWER PLAN & PROFILE		
C5.1	SANITARY SEWER PLAN & PROFILE		
C6	OVERALL GRADING PLAN		
C6.1	GRADING PLAN		
C6.2	GRADING PLAN		
C7	EROSION CONTROL PLAN		
C8	FIRE TRUCK ACCESS PLAN		
C9.1	CIVIL DETAILS		
C9.2	CIVIL DETAILS		
L1	PVA LANDSCAPE PLAN		
PL-1	PARKING LOT LIGHTING PLAN, NOTES AND LEGEND		
D1	PRE DEVELOPMENT DRAINAGE MAP		
D2	POST DEVELOPMENT DRAINAGE MAP		
01 - CIVIL: 24			
02 - ARCHITECTURAL			
A1.01	ARCHITECTURAL SITE PLAN		04/15/2022
CH2.01	CLUBHOUSE FLOOR PLAN		04/15/2022
CH2.03	CLUBHOUSE REFLECTED CEILING PLAN		04/15/2022
CH2.04	CLUBHOUSE ROOF PLAN		04/15/2022
CH3.02	CLUBHOUSE - MAIL KIOSK INTERIOR ELEVATIONS		04/15/2022
CH3.04	CLUBHOUSE ENLARGED PLANS		04/15/2022
CH4.01	CLUBHOUSE EXTERIOR ELEVATIONS		04/15/2022
CH5.01	CLUBHOUSE BUILDING SECTIONS		04/15/2022
CH6.01	CLUBHOUSE PLAN DETAILS		04/15/2022
CH6.02	CLUBHOUSE SECTION DETAILS		04/15/2022
CH7.01	DOOR SCHEDULE AND DETAILS		04/15/2022
CH7.02	CLUBHOUSE WINDOW DETAILS AND SCHEDULES		04/15/2022
02 - ARCHITECTURAL: 12			04/15/2022
03 - STRUCTURAL			04/15/2022
CS1.01	GENERAL NOTES		04/15/2022
CS1.02	SHEAR SCHEDULE AND DETAILS		04/15/2022
CS2.01	FOUNDATION PLAN		04/15/2022
CS3.01	ROOF FRAMING PLAN		04/15/2022
CS5.01	SECTIONS AND DETAILS		04/15/2022
CS5.02	SECTIONS AND DETAILS		04/15/2022
CS5.03	SECTIONS AND DETAILS		04/15/2022
03 - STRUCTURAL: 7			
04 - MECHANICAL			
CHM0.01	SYMBOL LEGEND & GENERAL NOTES MECHANICAL		04/15/2022
CHM3.01	SCHEDULES MECHANICAL		04/15/2022
CHM4.01	DETAILS MECHANICAL		04/15/2022
CHM5.01	ENERGY CALCULATIONS MECHANICAL		04/15/2022
04 - MECHANICAL: 4			
05 - ELECTRICAL			
CHE2.00	CLUBHOUSE SYMBOL LEGEND & GENERAL NOTES ELE.		04/15/2022
CHE2.01	CLUBHOUSE POWER & SYSTEMS		04/15/2022
CHE2.02	CLUBHOUSE LIGHTING		04/15/2022
CHE3.01	CLUBHOUSE RISER DIAGRAM ELECTRICAL		04/15/2022
CHE3.02	CLUBHOUSE FIRE ALARM RISER DIAGRAM ELECTRICAL		04/15/2022
CHE4.01	CLUBHOUSE SCHEDULES ELECTRICAL		04/15/2022
05 - ELECTRICAL: 6			
06 - PLUMBING			
CHP0.01	SYMBOL LEGEND & GENERAL NOTES PLUMBING		04/15/2022
CHP2.01	CLUBHOUSE SANITARY PLUMBING		04/15/2022
CHP2.02	CLUBHOUSE DOMESTIC WATER PLUMBING		04/15/2022
CHP2.03	CLUBHOUSE ISOMETRIC PLUMBING		04/15/2022
CHP2.04	CLUBHOUSE SCHEDULE PLUMBING		04/15/2022
CHP2.05	CLUBHOUSE DETAIL PLUMBING		04/15/2022
05 - MECHANICAL: 6			
GRAND TOTAL: 62			

ISSUE HISTORY

No.	Date	Description
1	04/15/2022	PERMIT SUBMITTAL

REVISION HISTORY

No.	Date	Description

FUGLEBERG KOCH

2555 Temple Trail, Winter Park, FL 32789 *(407) 629-0595*
www. fuglebergkoch.com *AA26002103*

CONSULTANT

STATE OF ALABAMA
MICHAEL E GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234

THE ROBERT MADISON	Drawn: MB
MADISON, ALABAMA	Checked: JK
	Approval: MG
	Date: 04/15/2022
	Project #: 5722

SHEET INDEX

A0.01b

PLOTTED: 5/5/2022
9:58:21 AM

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103 - and are issued only for the specific project noted on these drawings. Any reproductions, retention, or modifications of these documents without the expressed written consent of Fuglebergs Koch is prohibited by law.

BUILDING CODE ANALYSIS - [2018 INTERNATIONAL BUILDING CODE]

CODE SUMMARY

APPLICABLE CODES

1. BUILDING CODE: 2018 INTERNATIONAL BUILDING CODE
2. LIFE SAFETY CODE: 2018 NFPA 101
3. PLUMBING CODE: 2018 INTERNATIONAL PLUMBING CODE
4. ENERGY CODE: 2018 INTERNATIONAL ENERGY CONSERVATION CODE AND AMMENDMENTS
5. FIRE CODE: 2018 INTERNATIONAL FIRE CODE
6. ICC/ANSI ACCESSIBILITY CODE: 2009 ACCESSIBLE AND USABLE BUILDING AND FACILITIES (AS REFERENCED IN 2018IBC).
7. ELECTRICAL CODE: 2017 NATIONAL ELECTRIC CODE
8. MECHANICAL CODE: 2018 INTERNATIONAL MECHANICAL CODE
9. NFPA 70, STANDARD FOR PORTABLE FIRE EXTINGUISHERS, 2017 ED.
10. NFPA 13R, STANDARD FOR INSTALLATION OF SPRINKLER SYSTEMS IN RESIDENTIAL OCCUPANCIES UP TO, AND INCLUDING FOUR STORIES IN HEIGHT, 2012 EDITION.

GENERAL CODE PARAMETERS

CLUBHOUSE

DESCRIPTION	REQUIRED OR ALLOWABLE	THIS PROJECT	REFERENCE	REMARKS
WIND SPEED	110 MPH	110 MPH	SEC. 1609	
SEISMIC ZONE	B	B	SEC. 1613	
SNOW LOAD	10	10	SEC. 1608	
FROST DEPTH	N/A	N/A	SEC 1805.2.1	

COMPONENTS AND CLADDING PRESSURES (NET, SEE PRESSURE ZONE DETAILS ON STRUCTURAL DRAWINGS

BUILDING CODE PARAMETERS - [2018 IBC]

DESCRIPTION	REQUIRED (Table 503)	AREA MODIFICATION REQUIREMENT	THIS PROJECT CLUBHOUSE	REFERENCE (FBC)	REMARKS
CONSTRUCTION TYPE	TYPE V(B)	TYPE V(B)	TYPE V(B)		
USE / OCCUPANCY			A-3	CH. 3 & 4	
FIRE RATING	0 HR	0 HR	0 HR	CH. 6	
OCCUPANCY SEPARATION	0 HR	0 HR	0 HR		TABLE 508.3.3
SPRINKLER	-	-	-	TABLE 903	
CLUBHOUSE	6,000 SF		2,850 SF	TABLE 506.2	
MEZZ/LOFT INCL	--		NO	TABLE 505	
HEIGHT LIMIT (S)	1 STORIES		1 STORIES	TABLE 504.4	
HEIGHT LIMIT PROVIDED (FT)	40'-0"		30'-10"	TABLE 504.3	
OCCUPANT LOAD	TABLE 1004.1.1		126 PEOPLE	TABLE 1004.1.1	
MIN No. OF EXITS	2		5	TABLE 1006.3.1	
MIN. STAIR WIDTH	N/A		N/A	S. 1005.1 / 1009.1	

BUILDING CODE PARAMETERS - [IBC 2018]

DESCRIPTION	REQUIRED OR ALLOWABLE	THIS PROJECT	REFERENCE	REMARKS
CLUBHOUSE (GROUP A-3, TYPE V (B):				
GROSS AREA	6,000 SF	2,850 SF	TABLE 503	
HEIGHT LIMIT	40'-0"	30'-10"	TABLE 503	
OCCUPANT LOAD	TABLE 1004.1.2	126 PERSONS	TABLE 1004.1.2	
MEZZ/LOFT INCL	NO			
HEIGHT LIMIT (S)	1 STORY	1 STORY	TABLE 503	

TABLE 402.4.2 AIR BARRIER AND INSULATION INSPECTION COMPONENT CRITERIA

COMPONENT	CRITERIA
Air barrier and thermal barrier	Exterior thermal envelope insulation for framed walls is installed in substantial contact and continuous alignment with building envelope air barrier. Breaks or joints in the air barrier are filled or repaired. Air-permeable insulation is not used as a sealing material. Air-permeable insulation is inside of an air barrier.
Ceiling/attic	Air barrier in any dropped ceiling/soffit is substantially aligned with insulation and any gaps are sealed. Attic access (except unvented attic), knee wall door, or drop down stair is sealed.
Walls	Corners and headers are insulated. Junction of foundation and sill plate is sealed.
Windows and doors	Space between window/door jambs and framing is sealed.
Rim joists	Rim joists are insulated and include an air barrier.
Floors (including above-garage and cantilevered floors)	Insulation is installed to maintain permanent contact with underside of subfloor decking. Air barrier is installed at any exposed edge of insulation.
Crawl space walls	Insulation is permanently attached to walls. Exposed earth in unvented crawl spaces is covered with Class I vapor retarder with overlapping joints taped.
Shafts, penetrations	Duct shafts, utility penetrations, knee walls and flue shafts opening to exterior or unconditioned space are sealed.
Narrow cavities	Batts in narrow cavities are cut to fit, or narrow cavities are filled by sprayed/blown insulation.
Garage separation	Air sealing is provided between the garage and conditioned spaces.
Recessed lighting	Recessed light fixtures are air tight, IC rated, and sealed to drywall. Exception-fixtures in conditioned space.
Plumbing and wiring	Insulation is placed between outside and pipes. Batt insulation is cut to fit around wiring and plumbing, or sprayed/blown insulation extends behind piping and wiring.
Shower/tub on exterior wall	Showers and tubs on exterior walls have insulation and an air barrier separating them from the exterior wall.
Electrical/phone box on exterior walls	Air barrier extends behind boxes or air sealed-type boxes are installed.
Common wall	Air barrier is installed in common wall between dwelling units.
HVAC register boots	HVAC register boots that penetrate building envelope are sealed to subfloor or drywall.
Fireplace	Fireplace walls include an air barrier.

FIRE-RESISTANCE RATING REQUIREMENTS (PER TABLE 601)

CLUBHOUSE - TYPE V(B)

	V(B) REQ'D	V(B) PROV
STRUCTURAL FRAME: INCLUDING COLUMNS, GIRDERS, TRUSSES	0	0
BEARING WALLS: EXTERIOR (PER TABLE 601/602/704.10)	0	0
INTERIOR	0*	0*
NONBEARING WALLS AND PARTITIONS: EXTERIOR (PER TABLE 601/602)	0	0
INTERIOR (PER SECTION 601)	0	0
FLOOR CONSTRUCTION: NOT INCLUDING SUPPORTING BEAMS AND JOISTS per EXCEPTION 2 of 7.12.4	0*	0*
ROOF CONSTRUCTION	0*	0*
SEPARATION DISTANCE (PER TABLE 602) 10' ≤ X < 30'	0	0

* SEE CODE PARAMETERS TABLE BELOW AND LIFE-SAFETY SHEETS FOR ADDITIONAL INFORMATION

ALABAMA ACCESSIBILITY CODE NOTES

1. CLUBHOUSE SHALL COMPLY WITH 2018 IBC: CHAPTER 11 ACCESSIBILITY.
2. ALL OPENINGS IN CLUBHOUSE SHALL BE MIN. 32" CLEAR WITH A 2'-10" DOOR MIN.
3. PROVIDE SOLID BLOCKING IN BATHROOM WALLS FOR GRAB BARS AS REQUIRED.
4. PROVIDE THERMOSTATS AND ELECTRICAL SWITCHES WHERE SHOWN ON M.E.P. DRAWINGS MOUNTED 42"-48" A.F.F. TO BOTTOM OF CONTROL.
5. RECEPTICALS IN CLUBHOUSE SHALL BE MOUNTED MIN. 15" A.F.F. TO BOTTOM OF CONTROL.

MEANS OF EGRESS - [IBC TABLE 1006.2.1 AND 1017.2]


OCCUPANCY CLASSIFICATION	LOCATION	MAX. TRAVEL DISTANCE TO EXIT (ALLOWABLE) UNSPRINK.	SPRINK.	MAX. TRAVEL DISTANCE (ACTUAL)	REMARKS
A-3 - CLUBHOUSE	CLUBHOUSE	200'	N/A	49'-9"	

1) See Life Safety Plans for specific information.


2) Section 1015.2.1 Two Exits:
Exception 1: Where interior exit stairways are interconnected by a 1-hour fire-resistance-rated *corridor* conforming to the requirements of Section 1018, the required exit separation shall be measured along the shortest direct line of travel within the *corridor*.

Exception 2: Where a building is equipped throughout with an automatic sprinkler system in accordance with Section 903.3.1.1 or 903.3.1.2, the separation distance of the exit doors or exit access doorways shall not be less than one-third of the length of the maximum overall diagonal dimension of the area served.

b) Table 1014.3 - Note b & 1016.2 - Note b
Buildings equipped throughout with an automatic sprinkler system in accordance with section 903.3.1.1 or 903.3.1.2.
See section 903 for occupancies where automatic sprinkler systems are permitted in accordance with section 903.3.1.2.



C4 FIRE EXTINGUISHER CABINET
1 1/2" = 1'-0"



F3 FIRE EXTINGUISHER CABINET
1" = 1'-0"

INSULATION AND FENESTRATION REQUIREMENTS BY COMPONENT (INTERNATIONAL ENERGY CONSERVATION CODE 2018 - CHAPTER 4 (CE)

CLIMATE ZONE	FENESTRATION U-FACTOR	SKYLIGHT U-FACTOR	GLAZED FENESTRATION SHGC	CEILING R-VALUE	WOOD FRAME WALL R-VALUE	ATTIC KNEEWALL	MASS FRAME WALL R-VALUE	FLOOR R-VALUE	BASEMENT WALL R-VALUE	SLAB R-VALUE & DEPTH	CRAWL SPACE WALL R-VALUE
3A	0.50	0.55	0.25	38	20	N/A	N/A	N/A	0	0	0
PROVIDED	0.40	N/A	0.25	38	21	N/A	N/A	N/A	N/A	N/A	N/A

MAXIMUM AREA OF EXTERIOR WALL OPENINGS:

FROM TABLE 705.8 - [2018 IBC]

ASSUMED PROPERTY LINE DISTANCE:

	ALLOWABLE	ACTUAL (WORST CASE)
UNPROTECTED, SPRINKLERED (UP, S)		
0 FT TO 3 FT	NP	NP
OVER 3 FT TO 5 FT	15%	--
OVER 5 FT TO 10 FT	25%	--
OVER 10 FT TO 15 FT	45%	25%
OVER 15 FT TO 20 FT	75%	--
OVER 20 FT TO 25 FT	NL	NL
OVER 25 FT TO 30 FT	NL	NL
OVER 30' FROM ASSUMED PROPERTY LINE	NR	NR


OCCUPANCY LOAD CHART PER 2018 IBC TABLE 1004.5

ROOM	AREA	S.F./PERSON	OCCUPANCY
GATHERING	828 S.F.	15 GSF	56
GAMEROOM	395 S.F.	15 GSF	27
RECEPTION	223 S.F.	100 GSF	3
OFFICE 1	158 S.F.	100 GSF	2
WORK ROOM	106 S.F.	100 GSF	2
OUTDOOR LOGIA	509 S.F.	15 GSF	34
TOTAL			124 PERSONS
MECH	20 S.F.	300 GSF	1
MECH/JANITORS	145 S.F.	300 GSF	1
TOTAL			2 PERSONS
TOTAL OCCUPANTS			126 PERSONS

PLUMBING FIXTURES REQ'D - IBC 2018 TABLE 2902.1

OCCUPANCY CLASSIFICATION	LOCATION	WATER CLOSETS (URINALS 419.2) MALE	WATER CLOSETS (URINALS 419.2) FEMALE	LAVATORIES MALE	LAVATORIES FEMALE	DRINKING FOUNTAIN	SERVICE SINK
A-3	CLUBHOUSE	1 PER 125	1 PER 65	1 PER 200	1 PER 200	1 PER 500	1
TOTAL OCCUPANTS = 126							
FIXTURES REQUIRED		2	2	2	2	1	1
FIXTURES PROVIDED		2	2	2	2	1 HI / 1 LOW	1

* URINAL = .67 IN ASSEMBLY OCCUPANCY PER 419.2
* CLUBHOUSE OCCUPANTS = 126



F6 CLUBHOUSE - LIFE SAFETY PLAN
3/16" = 1'-0"

LEGEND:

- EMERGENCY LIGHT (SEE ELECT DWGS FOR LOCATIONS)
- EXIT SIGN
- EXIT ACCESS TRAVEL DISTANCE
- COMMON PATH OF EGRESS TRAVEL
- F.E.C. — FIRE EXTINGUISHER VERIFY EXACT LOCATIONS AND TYPES WITH LOCAL FIRE OFFICIALS
- TD — EXIT ACCESS TRAVEL DISTANCE
- CP — COMMON PATH OF EGRESS TRAVEL
- 20 MIN DOOR
- 45 MIN DOOR
- 60 MIN DOOR
- 90 MIN DOOR
- REQUIRED 1 HOUR FIRE SEPARATION
- REQUIRED 2 HOUR FIRE SEPARATION

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103 - and are to be used only for the specific project noted on these drawings. Any reproductions, extensions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103
CONSULTANT
STATE OF ALABAMA MICHAEL E. GOVE 8234 4/15/22 REGISTERED ARCHITECT
MICHAEL GOVE
8234

THE MADISON
MADISON, AL

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

CLUBHOUSE CODE/ LIFE SAFETY PLAN

CH0.01

PLOTTED: 5/3/2022 3:03:37 PM

The Roberts Apartments at Town Madison

Address:
Dunlop Blvd
Madison, AL 35758

Prepared for:
Rohdie Group

Plan Set Date:
November 16, 2021

General Notes:

1.The locations of existing utilities are shown in as approximate only. The contractor shall verify the exact location of all existing utilities before commencing work. Contractor shall be fully responsible for any and all damages which might occur by his failure to exactly locate and preserve any and all utilities.

2.Contractor is responsible for making application and paying for necessary permits.

3.The Contractor shall prevent the destruction of all survey monuments, bench marks, property corners and all other survey points. Where the removal of such points are necessary for the accomplishment of the work, the Contractor shall inform the Engineer in writing, prior to the disturbance of any point, and shall not disturb the point until written permission to do so has been issued by the Engineer.

4.All existing trees outside of the limits of work shall be protected during the accomplishment of the work, and are not to be damaged in any manner.

5.All boulders, debris, excess construction materials, material generated from demolition of existing structures and facilities or trash shall be removed from site at contractor's expense.

6.Pavement cuts shall be repaired with material in-kind to that removed.

7.In accordance with generally accepted construction practices, the contractor is solely and completely responsible for conditions of the job site, including safety of all persons and property during performance of the work. This requirement applies continuously and shall not be limited to normal working hours.

8.Contractor shall provide adequate traffic control devices and safety measures for construction work within public right-of-ways in accordance with the Manual on Uniform Traffic Control Devices for Streets and Highways.

9.The duty of the Engineer to conduct construction observation of the contractor's performance is not intended to include review of the adequacy of the Contractor's safety measures, in, on or near the construction site.

10.The Contractor shall be responsible for cleaning dirt and debris from the adjoining streets parking lots, and drives during construction. Any damage to adjoining and existing facilities shall be repaired by the Contractor, at no additional cost to the owner, during the construction of this site.

11.No fill dirt shall be placed on the property that might interfere with drainage flow from adjacent property. Storm drainage system shall be installed prior to fill material being placed.

12.The Contractor shall be totally responsible for TVI, vacuum testing manholes, and air testing sewer lines if required.

13.No changes shall be made to these approved plans without the Engineer of Record being notified before changes are made and the Engineer of Record acquiring approval from the City Engineer.

14.All sanitary sewer pipe shall either be SDR 26 PVC or Class 350 Ductile Iron.

15. The City of Madison Construction Specifications Manual for Public Improvements, latest edition and any revision thereof, are hereby made part of these plans.

16. If approval from any State or Federal Regulatory Agency is required to perform work on this project, a copy of each permit required shall be delivered to the City of Madison Engineering Department prior to the approval of said plans.

17. The Alabama Handbook for Erosion Control, Sediment Control and Stormwater Management on Construction Sites and Urban Areas, Vol. 1 and 2, latest edition and any revision thereof, are hereby made a part of these plans.


18. Contractor is required to schedule a Pre-Construction meeting with Engineering Inspector before commencement of work. Call 256-797-8025 for scheduling or go to www.madisonal.gov/index.aspx?NID=126 (pre-construction requirements) for more information.

19. Call 811 prior to any digging for Utility work.

Sheet Index

Cover	C0
Existing Conditions & Demolition Plan	C1
Site Plan	C2.X
Keynote Plan	C2.3
Water Infrastructure Plan	C3
Storm Infrastructure Plan	C4.X
Sanitary Sewer Infrastructure Plan	C5.X
Grading & Drainage Plan	C6.X
Erosion Control Plan	C7
Fire Truck Access Plan	C8
Civil Details	C9.X

Site



Vicinity Map
Not to Scale

Certificate of Approval by Fire Department
The undersigned, as a duly authorized representative of the Madison Fire Department, City of Madison, AL, certifies the within site plan has been reviewed and approved.

By: _____

Date: 12-7-21

Certificate of Approval by City Council
The undersigned, as representative of the City Council of Madison, Alabama, hereby certified that the property and site plan has been approved by the City Council

By: _____

Date: 12-7-21

Certificate of Approval by City Engineer
The undersigned, as City Engineer of the City of Madison, AL, hereby approves the within site plan.

By: E. Michelle Dumas

Date: December 3, 2021

Certificate of Approval by Planning Director
The undersigned, as Director of Planning for the City of Madison, AL, hereby certifies that the property and site plan has been inspected, reviewed, and found to be compliant with the City's Zoning Ordinance and Subdivision Regulations.

By: _____

Date: 12/9/2021

Madison Utilities

Submitted for approval:

ENGINEER


APPROVED:

BUSINESS DEVELOPMENT COORDINATOR

DEVELOPER

GENERAL MANAGER

NOTE: CONSTRUCTION SPECIFICATIONS FOR WATER AND SANITARY SEWER LATEST EDITION AS ADOPTED BY MADISON UTILITES (MU), IS HEREBY MADE PART OF THESE PLANS. CONTRACTOR SHALL CONTACT MU TO SCHEDULE A PRE-CONSTUCTION MEETING PRIOR TO THE START OF ANY WATER OR SEWER CONSTRUCTION.




Overall View
Scale: 1" = 200'

FINAL FOR DEVELOPMENT
DEC 09 2021


TOWN MADISON

Prepared by:

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 503, Huntsville, AL 35805
(256) 690-5312



SILT FENCE
NOT to Scale



Gravel Construction Entrance
NOT to Scale

I, CHARLES MIKE FRANKLIN, THE SURVEYOR OF RECORD, CERTIFY THAT THE SUBDIVISION SHOWN HEREON LIES WITHIN FLOOD HAZARD AREAS "X" & "AE" AS SHOWN ON THE FEDERAL INSURANCE ADMINISTRATION'S FLOOD INSURANCE RATE MAPS FOR THE CITY OF HUNTSVILLE, ALABAMA.

FIRM PANEL # 01089C0311F (EFFECTIVE DATE 8/16/2018)
(AMENDED BY LOMR-F 19-04-3126 P EFFECTIVE DATE 10/13/2020)

CHARLES MIKE FRANKLIN, PLS
AL REG. NO. 18980

ALABAMA LICENSED NO. 18980 PROFESSIONAL LAND SURVEYOR CHARLES M. FRANKLIN

Demolition Notes: (this sheet only)

1. CONTRACTOR SHALL LOCATE, MAINTAIN & PROTECT EX. UTILITIES ON SITE. ANY DAMAGE TO SUCH SHALL BE REPAIRED AND/OR REPLACE AT NO EXPENSE TO THE OWNER.
2. ALL EXISTING TREES WITHIN THE GRADING LIMITS ARE TO BE REMOVED.

Demolition Keynote Legend: (this sheet only)

- A. Req'd sawcut, full depth, ex. curb & gutter, sidewalk, and/or asphalt, at this point.
- B. Req'd demo & remove ex. curb & gutter, sidewalk, and/or asphalt, this area.
- C. Req'd silt fence, length as shown, coord. w/ Erosion Control Plan, see detail.
- D. Req'd Gravel Construction Entrance, coord. w/ Erosion Control Plan, see detail.
- E. Req'd rework, coord w/ Utility Plan.

LIME QUARRY ROAD

S 88°08'48" E 92.08'

S 51°19'08" E 169.03'

S 00°00'00" E 674.80'

N 49°01'17" E 186.22'

N 35°35'52" E 209.51'

N 43°35'16" E 334.61'

N 22°15'19" E 321.00'

N 17°16'19" E 268.77'

S 12°42'27" W 220.61'

S 10°24'36" W 162.85'

S 18°05'36" W 204.42'

S 89°58'59" W 961.65'

1% Annual Chance Floodplain Boundary

Excavation Area

FLOODWAY

FLOODWAY BOUNDARY

EX. 10' GAS EASEMENT D.B.852/PG.999-1000

EXISTING UTILITY & DRAINAGE EASEMENT

60' U & D. EASEMENT

30.0'

60.0'

50.0'

615.9

C 2,185 LF

15' UTILITY EASEMENT

Special Flood Hazard Area (SFHA) Zone AE

LOT 2

LOT 4

DUNLOP BOULEVARD

GRESS EASEMENT D.B.1027/PG.1027

Ex. SPHW
Ex. INV OUT 617.98±

Ex. SWSI
Ex. INV IN (E) 623.29±
Ex. INV (S) 619.39±
Ex. INV OUT 619.39±

Ex. SPHW
Ex. INV OUT 624.50±

Ex. JB
Ex. RIM 634.21±
Ex. INV IN 625.4
Ex. INV OUT 62(

Ex. SWSI
Ex. INV IN 624.00±
Ex. INV OUT 623.90±

Ex. JB
Ex. RIM 634.24±
Ex. INV IN 625.96±
Ex. INV OUT 625.86±

Ex. JB
Ex. INV IN (S)629.13±
Ex. INV IN (N) 628.63±
Ex. INV IN (E) 627.24±
Ex. INV OUT 627.14±

Ex. DWSI
Ex. INV IN 629.35±
Ex. INV OUT 629.25±

Ex. SWSI
Ex. INV OUT 630.80±

Ex. SWSI
Ex. INV OUT 630.45±

Ex. SWSI
Ex. INV IN 630.14±
Ex. INV OUT 630.04±

Ex. SWSI
Ex. INV IN 628.57±
Ex. INV OUT 628.07±

Ex. SWSI
Ex. INV IN 628.98±
Ex. INV OUT 628.88±

Ex. SPHW
Ex. INV OUT 629.59±

FINAL FOR DEVELOPMENT
DEC 09 2021

Existing Conditions & Demo Plan
Scale: 1" = 50'

TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project. Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA LICENSED NO. 18980 PROFESSIONAL LAND SURVEYOR CHARLES M. FRANKLIN
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: Rohdie Group

Existing Conditions & Demolition Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C1

AASHTO NOTE:

THE INTERSECTION SITE DISTANCE AND GEOMETRIC DESIGN OF THIS SUBDIVISION MEET RECOMMENDATIONS SET FORTH IN THE PREVAILING AASHTO STANDARDS.

INTERSECTION SIGHT DISTANCE

LOCATION	DESIGN SPEED	AASHTO GUIDELINES RIGHT	AASHTO GUIDELINES LEFT	ACTUAL SIGHT DISTANCE RIGHT	ACTUAL SIGHT DISTANCE LEFT	SIGHT DISTANCE SATISFIED
DRIVE @ LIMESTONE QUARRY ROAD	25 MPH	280	240	386	500+	YES
DRIVE @ DUNLOP BLVD	45 MPH	500	430	500+	500+	YES

Fire Flow & Notes:

Date & Time Tested: 6-3-21 at 9:20 AM

Static	112
Residual	88
Flow	76

1,465 GPM

Note: Knox Boxes shall be required for riser room access

City Notes:

1. All traffic controls devices shall be erected and maintained in conformance with the Manual of Uniform-Control Devices and any revisions thereof.
2. Required fire flows cannot be determined precisely until the specific building use, construction type, and other faactors have been disclosed and reviewed. The applicant will comply with the fire flow and fire safety and suppression requirements and all adopted city codes and regulations.
3. All drainage ditches are to be centered on property lines unless shown.
4. All utilities will be underground.
5. If adverse conditions are uncovered during construction, the city engineer may require modification of these plans to the extent necessary to assure compliance with the city's construction specifications manual.
6. Setbacks are governed by the latest addition of the Madison Zoning Ordinance.
7. Any signage requires separate review, approval, and permitting.

Layout Notes:

1. All dimensions are from back of curb, U.N.O.
2. Sidewalks to have max cross slope of 2%.

Site Notes:

1. Property line bearings are based on state plan coordinates, NAD 1983, as determined by CORS, GTAC. Distances are based on actual field survey. All bearing and distances are plat and measured.
2. All traffic control devices shall be erected and maintained in conformance with the Manual on Uniform Traffic Control Devices and any revisions thereof.
3. All drainage ditches shall be centered on property lines unless otherwise shown.
4. All utilities are underground.
5. If adverse conditions on the site are uncovered during construction, the City Engineer may require modification to these plans to the extent necessary to assure compliance with the City's Construction Specifications.
6. All lots shall be graded so that runoff will be directed to the Street or to drainage ways in a dedicated easement.
7. Setbacks are governed by the latest edition of the Madison Zoning Ordinance.
9. Required fire flows cannot be determined precisely until the specific building use, construction type, and other factors have been disclosed and reviewed. The applicant will comply with the fire flow and fire safety and suppression requirements of all adopted City codes and regulations.
10. Plaza areas shall be hardscape areas of concrete, paver, or some other durable, consistent material, compliant with ADA accessible surfaces; pattern & materials to be further refined through the design and construction process.
11. Contractor shall coordinate with site Engineer for handicap ramp layout prior to construction to ensure compliance with design and ADA requirements.
12. Special maintenance agreement for utilities under streetscape conditions/elements/materials (pavers, walls, trees, etc.) required prior to issuance of C.O.
13. Coordinate with Geotechnical Engineer to ensure roads in excavated areas achieve proper compaction to Geotechnical Engineers requirements and recommendations.

Site Information:

Total Lot Area:
- Pre Subdivided: 30.48 acre (1,327,894 sf)
- Remaining Property: 12.81 acre (558,067 sf)
- Post Subdivision: 17.67 acre (769,807 sf)

Zoning District: UC (Urban Center District)

Adjoining Zoning
- North: B3 (General Business District)
- South: UC (Urban Center District)
- West: UC (Urban Center District)
- East: UC (Urban Center District)

Building Info:
- Sprinkler System: Residential Buildings NFPA 13r
- Stories (max.): 4
- Height
  - 4-Story Buildings: 55'-3"
  - Townhouse Apartment: 27'-8"

Type of Construction
- 4-Story Building: V(a)
- Others: V(b)

Occupancy type
- Residential Buildings: R-2
- Clubhouse & Fitness Buildings: A-3
- Dumpster Enclosure: U

Units:

1 Bed	102
2 Bed	138
3 Bed	44
Total	284

Density Schedule:

Net: 284/17.67 = 16.07 = 16 units/acre

Building Number	SF * Stories	Total SF by Type
Building 1	12,989 * 4	= 51,956 sf
Building 2 & 5	14,612 * 4	= 116,896 sf
Building 3 & 6	13,043 * 4	= 104,344 sf
Building 4	4,415 * 1	= 4,415 sf
Building 7	14,610 * 4	= 58,440 sf
Building 8 - 17	1,787 * 2	= 32,166 sf
Grill Building	480 * 1	= 480 sf
Maintenance and Pool Building	200 * 1	= 200 sf
Total		= 317,948 sf
Ratio	317,948 sf / 769,807 sf = 0.41	

Total Disturbed Area:
- Total: 17.67 acre

Parking Information:

Req'd Parking
- Units: 1.0 * units (1 bed) + 2.0 * units (2 bed) + 2.5 * units (3 bed) ==> 1.0 * 102 + 2 * 138 + 2.5 * 44 = 102 + 276 + 110 =
- Total Required: 488
- Total Provided: 520

Clubhouse/Rental Office
- Total Required: 1
- Total Provided: 17

Tandem Spaces: 78


ADA Accessible Parking
Req'd Parking
- Total Required: 13
- Total Provided: 14

Bicycle Information:
Req'd Spaces
- Units: unit / 5 ==> 284/5 = 56.8
- Total Required: 57
- Total Provided: 62

Parking Table:

Parking Info

Attached Garage	78
Open	442
- Compact	21 (4.8%)
- Standard Parking	421 (95.2%)
Total	520
Tandem Spaces	78
Clubhouse/Vistor	17
Bicycle	62


LIME QUARRY ROAD
Villas Project
Req'd Sidewalk of this project
S 88°08'48" E
92.08'
S 51°19'08" E
69.05'
Ex. SPHW
Ex. INV OUT 617.98±
Ex. SWSI
Ex. INV IN (E) 623.29±
Ex. INV (S) 619.39±
Ex. INV OUT 619.39±
Ex. SPHW
Ex. INV OUT 624.50±
Ex. JB
Ex. RIM 634.21±
Ex. INV IN 625.41±
Ex. INV OUT 620.93±
Ex. SWSI
Ex. INV IN 624.00±
Ex. INV OUT 623.90±
Ex. JB
Ex. RIM 634.24±
Ex. INV IN 625.96±
Ex. INV OUT 625.86±
Ex. JB
Ex. INV IN (S)629.13±
Ex. INV IN (N) 628.63±
Ex. INV IN (E) 627.24±
Ex. INV OUT 627.14±
Ex. DWSI
Ex. INV IN 629.35±
Ex. INV OUT 629.25±
Ex. SWSI
Ex. INV OUT 630.80±
Ex. SWSI
Ex. INV OUT 630.45±
Ex. SWSI
Ex. INV IN 630.14±
Ex. INV OUT 630.04±
Ex. SWSI
Ex. INV IN 628.57±
Ex. INV OUT 628.07±
Ex. SWSI
Ex. INV IN 628.98±
Ex. INV OUT 628.88±
Ex. SPHW
Ex. INV OUT 629.59±
Dumpster
Bicycle Rack (x3)
BLDG 1
FFE 630.00
Bicycle Rack (x5)
EX. 10' GAS EASEMENT
D.B.852/PG.999-1000
Excavation Area
1% Annual Chance Floodplain Boundary
N 49°01'17" E
186.22'
FLOODWAY
L46
L47
L40
L41
L42
L43
L44
L45
L48
L49
L50
L51
L52
L53
L54
L55
L56
L57
L58
L59
L60
L61
L62
L63
L64
L65
L66
L67
L68
L69
L70
L71
L72
L73
L74
L75
L76
L77
L78
L79
L80
L81
L82
L83
L84
L85
L86
L87
L88
L89
L90
L91
L92
L93
L94
L95
L96
L97
L98
L99
L100
L101
L102
L103
L104
L105
L106
L107
L108
L109
L110
L111
L112
L113
L114
L115
L116
L117
L118
L119
L120
L121
L122
L123
L124
L125
L126
L127
L128
L129
L130
L131
L132
L133
L134
L135
L136
L137
L138
L139
L140
L141
L142
L143
L144
L145
L146
L147
L148
L149
L150
L151
L152
L153
L154
L155
L156
L157
L158
L159
L160
L161
L162
L163
L164
L165
L166
L167
L168
L169
L170
L171
L172
L173
L174
L175
L176
L177
L178
L179
L180
L181
L182
L183
L184
L185
L186
L187
L188
L189
L190
L191
L192
L193
L194
L195
L196
L197
L198
L199
L200
L201
L202
L203
L204
L205
L206
L207
L208
L209
L210
L211
L212
L213
L214
L215
L216
L217
L218
L219
L220
L221
L222
L223
L224
L225
L226
L227
L228
L229
L230
L231
L232
L233
L234
L235
L236
L237
L238
L239
L240
L241
L242
L243
L244
L245
L246
L247
L248
L249
L250
L251
L252
L253
L254
L255
L256
L257
L258
L259
L260
L261
L262
L263
L264
L265
L266
L267
L268
L269
L270
L271
L272
L273
L274
L275
L276
L277
L278
L279
L280
L281
L282
L283
L284
L285
L286
L287
L288
L289
L290
L291
L292
L293
L294
L295
L296
L297
L298
L299
L300
L301
L302
L303
L304
L305
L306
L307
L308
L309
L310
L311
L312
L313
L314
L315
L316
L317
L318
L319
L320
L321
L322
L323
L324
L325
L326
L327
L328
L329
L330
L331
L332
L333
L334
L335
L336
L337
L338
L339
L340
L341
L342
L343
L344
L345
L346
L347
L348
L349
L350
L351
L352
L353
L354
L355
L356
L357
L358
L359
L360
L361
L362
L363
L364
L365
L366
L367
L368
L369
L370
L371
L372
L373
L374
L375
L376
L377
L378
L379
L380
L381
L382
L383
L384
L385
L386
L387
L388
L389
L390
L391
L392
L393
L394
L395
L396
L397
L398
L399
L400
L401
L402
L403
L404
L405
L406
L407
L408
L409
L410
L411
L412
L413
L414
L415
L416
L417
L418
L419
L420
L421
L422
L423
L424
L425
L426
L427
L428
L429
L430
L431
L432
L433
L434
L435
L436
L437
L438
L439
L440
L441
L442
L443
L444
L445
L446
L447
L448
L449
L450
L451
L452
L453
L454
L455
L456
L457
L458
L459
L460
L461
L462
L463
L464
L465
L466
L467
L468
L469
L470
L471
L472
L473
L474
L475
L476
L477
L478
L479
L480
L481
L482
L483
L484
L485
L486
L487
L488
L489
L490
L491
L492
L493
L494
L495
L496
L497
L498
L499
L500
L501
L502
L503
L504
L505
L506
L507
L508
L509
L510
L511
L512
L513
L514
L515
L516
L517
L518
L519
L520
L521
L522
L523
L524
L525
L526
L527
L528
L529
L530
L531
L532
L533
L534
L535
L536
L537
L538
L539
L540
L541
L542
L543
L544
L545
L546
L547
L548
L549
L550
L551
L552
L553
L554
L555
L556
L557
L558
L559
L560
L561
L562
L563
L564
L565
L566
L567
L568
L569
L570
L571
L572
L573
L574
L575
L576
L577
L578
L579
L580
L581
L582
L583
L584
L585
L586
L587
L588
L589
L590
L591
L592
L593
L594
L595
L596
L597
L598
L599
L600
L601
L602
L603
L604
L605
L606
L607
L608
L609
L610
L611
L612
L613
L614
L615
L616
L617
L618
L619
L620
L621
L622
L623
L624
L625
L626
L627
L628
L629
L630
L631
L632
L633
L634
L635
L636
L637
L638
L639
L640
L641
L642
L643
L644
L645
L646
L647
L648
L649
L650
L651
L652
L653
L654
L655
L656
L657
L658
L659
L660
L661
L662
L663
L664
L665
L666
L667
L668
L669
L670
L671
L672
L673
L674
L675
L676
L677
L678
L679
L680
L681
L682
L683
L684
L685
L686
L687
L688
L689
L690
L691
L692
L693
L694
L695
L696
L697
L698
L699
L700
L701
L702
L703
L704
L705
L706
L707
L708
L709
L710
L711
L712
L713
L714
L715
L716
L717
L718
L719
L720
L721
L722
L723
L724
L725
L726
L727
L728
L729
L730
L731
L732
L733
L734
L735
L736
L737
L738
L739
L740
L741
L742
L743
L744
L745
L746
L747
L748
L749
L750
L751
L752
L753
L754
L755
L756
L757
L758
L759
L760
L761
L762
L763
L764
L765
L766
L767
L768
L769
L770
L771
L772
L773
L774
L775
L776
L777
L778
L779
L780
L781
L782
L783
L784
L785
L786
L787
L788
L789
L790
L791
L792
L793
L794
L795
L796
L797
L798
L799
L800
L801
L802
L803
L804
L805
L806
L807
L808
L809
L810
L811
L812
L813
L814
L815
L816
L817
L818
L819
L820
L821
L822
L823
L824
L825
L826
L827
L828
L829
L830
L831
L832
L833
L834
L835
L836
L837
L838
L839
L840
L841
L842
L843
L844
L845
L846
L847
L848
L849
L850
L851
L852
L853
L854
L855
L856
L857
L858
L859
L860
L861
L862
L863
L864
L865
L866
L867
L868
L869
L870
L871
L872
L873
L874
L875
L876
L877
L878
L879
L880
L881
L882
L883
L884
L885
L886
L887
L888
L889
L890
L891
L892
L893
L894
L895
L896
L897
L898
L899
L900
L901
L902
L903
L904
L905
L906
L907
L908
L909
L910
L911
L912
L913
L914
L915
L916
L917
L918
L919
L920
L921
L922
L923
L924
L925
L926
L927
L928
L929
L930
L931
L932
L933
L934
L935
L936
L937
L938
L939
L940
L941
L942
L943
L944
L945
L946
L947
L948
L949
L950
L951
L952
L953
L954
L955
L956
L957
L958
L959
L960
L961
L962
L963
L964
L965
L966
L967
L968
L969
L970
L971
L972
L973
L974
L975
L976
L977
L978
L979
L980
L981
L982
L983
L984
L985
L986
L987
L988
L989
L990
L991
L992
L993
L994
L995
L996
L997
L998
L999
L1000
L1001
L1002
L1003
L1004
L1005
L1006
L1007
L1008
L1009
L1010
L1011
L1012
L1013
L1014
L1015
L1016
L1017
L1018
L1019
L1020
L1021
L1022
L1023
L1024
L1025
L1026
L1027
L1028
L1029
L1030
L1031
L1032
L1033
L1034
L1035
L1036
L1037
L1038
L1039
L1040
L1041
L1042
L1043
L1044
L1045
L1046
L1047
L1048
L1049
L1050
L1051
L1052
L1053
L1054
L1055
L1056
L1057
L1058
L1059
L1060
L1061
L1062
L1063
L1064
L1065
L1066
L1067
L1068
L1069
L1070
L1071
L1072
L1073
L1074
L1075
L1076
L1077
L1078
L1079
L1080
L1081
L1082
L1083
L1084
L1085
L1086
L1087
L1088
L1089
L1090
L1091
L1092
L1093
L1094
L1095
L1096
L1097
L1098
L1099
L1100
L1101
L1102
L1103
L1104
L1105
L1106
L1107
L1108
L1109
L1110
L1111
L1112
L1113
L1114
L1115
L1116
L1117
L1118
L1119
L1120
L1121
L1122
L1123
L1124
L1125
L1126
L1127
L1128
L1129
L1130
L1131
L1132
L1133
L1134
L1135
L1136
L1137
L1138
L1139
L1140
L1141
L1142
L1143
L1144
L1145
L1146
L1147
L1148
L1149
L1150
L1151
L1152
L1153
L1154
L1155
L1156
L1157
L1158
L1159
L1160
L1161
L1162
L1163
L1164
L1165
L1166
L1167
L1168
L1169
L1170
L1171
L1172
L1173
L1174
L1175
L1176
L1177
L1178
L1179
L1180
L1181
L1182
L1183
L1184
L1185
L1186
L1187
L1188
L1189
L1190
L1191
L1192
L1193
L1194
L1195
L1196
L1197
L1198
L1199
L1200
L1201
L1202
L1203
L1204
L1205
L1206
L1207
L1208
L1209
L1210
L1211
L1212
L1213
L1214
L1215
L1216
L1217
L1218
L1219
L1220
L1221
L1222
L1223
L1224
L1225
L1226
L1227
L1228
L1229
L1230
L1231
L1232
L1233
L1234
L1235
L1236
L1237
L1238
L1239
L1240
L1241
L1242
L1243
L1244
L1245
L1246
L1247
L1248
L1249
L1250
L1251
L1252
L1253
L1254
L1255
L1256
L1257
L1258
L1259
L1260
L1261
L1262
L1263
L1264
L1265
L1266
L1267
L1268
L1269
L1270
L1271
L1272
L1273
L1274
L1275
L1276
L1277
L1278
L1279
L1280
L1281
L1282
L1283
L1284
L1285
L1286
L1287
L1288
L1289
L1290
L1291
L1292
L1293
L1294
L1295
L1296
L1297
L1298
L1299
L1300
L1301
L1302
L1303
L1304
L1305
L1306
L1307
L1308
L1309
L1310
L1311
L1312
L1313
L1314
L1315
L1316
L1317
L1318
L1319
L1320
L1321
L1322
L1323
L1324
L1325
L1326
L1327
L1328
L1329
L1330
L1331
L1332
L1333
L1334
L1335
L1336
L1337
L1338
L1339
L1340
L1341
L1342
L1343
L1344
L1345
L1346
L1347
L1348
L1349
L1350
L1351
L1352
L1353
L1354
L1355
L1356
L1357
L1358
L1359
L1360
L1361
L1362
L1363
L1364
L1365
L1366
L1367
L1368
L1369
L1370
L1371
L1372
L1373
L1374
L1375
L1376
L1377
L1378
L1379
L1380
L1381
L1382
L1383
L1384
L1385
L1386
L1387
L1388
L1389
L1390
L1391
L1392
L1393
L1394
L1395
L1396
L1397
L1398
L1399
L1400
L1401
L1402
L1403
L1404
L1405
L1406
L1407
L1408
L1409
L1410
L1411
L1412
L1413
L1414
L1415
L1416
L1417
L1418
L1419
L1420
L1421
L1422
L1423
L1424
L1425
L1426
L1427
L1428
L1429
L1430
L1431
L1432
L1433
L1434
L1435
L1436
L1437
L1438
L1439
L1440
L1441
L1442
L1443
L1444
L1445
L1446
L1447
L1448
L1449
L1450
L1451
L1452
L1453
L1454
L1455
L1456
L1457
L1458
L1459
L1460
L1461
L1462
L1463
L1464
L1465
L1466
L1467
L1468
L1469
L1470
L1471
L1472
L1473
L1474
L1475
L1476
L1477
L1478
L1479
L1480
L1481
L1482
L1483
L1484
L1485
L1486
L1487
L1488
L1489
L1490
L1491
L1492
L1493
L1494
L1495
L1496
L1497
L1498
L1499
L1500
L1501
L1502
L1503
L1504
L1505
L1506
L1507
L1508
L1509
L1510
L1511
L1512
L1513
L1514
L1515
L1516
L1517
L1518
L1519
L1520
L1521
L1522
L1523
L1524
L1525
L1526
L1527
L1528
L1529
L1530
L1531
L1532
L1533
L1534
L1535
L1536
L1537
L1538
L1539
L1540
L1541
L1542
L1543
L1544
L1545
L1546
L1547
L1548
L1549
L1550
L1551
L1552
L1553
L1554
L1555
L1556
L1557
L1558
L1559
L1560
L1561
L1562
L1563
L1564
L1565
L1566
L1567
L1568
L1569
L1570
L1571
L1572
L1573
L1574
L1575
L1576
L1577
L1578
L1579
L1580
L1581
L1582
L1583
L1584
L1585
L1586
L1587
L1588
L1589
L1590
L1591
L1592
L1593
L1594
L1595
L1596
L1597
L1598
L1599
L1600
L1601
L1602
L1603
L1604
L1605
L1606
L1607
L1608
L1609
L1610
L1611
L1612
L1613
L1614
L1615
L1616
L1617
L1618
L1619
L1620
L1621
L1622
L1623
L1624
L1625
L1626
L1627
L1628
L1629
L1630
L1631
L1632
L1633
L1634
L1635
L1636
L1637
L1638
L1639
L1640
L1641
L1642
L1643
L1644
L1645
L1646
L1647
L1648
L1649
L1650
L1651
L1652
L1653
L1654
L1655
L1656
L1657
L1658
L1659
L1660
L1661
L1662
L1663
L1664
L1665
L1666
L1667
L1668
L1669
L1670
L1671
L1672
L1673
L1674
L1675
L1676
L1677
L1678
L1679
L1680
L1681
L1682
L1683
L1684
L1685
L1686
L1687
L1688
L1689
L1690
L1691
L1692
L1693
L1694
L1695
L1696
L1697
L1698
L1699
L1700
L1701
L1702
L1703
L1704
L1705
L1706
L1707
L1708
L1709
L1710
L1711
L1712
L1713
L1714
L1715
L1716
L1717
L1718
L1719
L1720
L1721
L1722
L1723
L1724
L1725
L1726
L1727
L1728
L1729
L1730
L1731
L1732
L1733
L1734
L1735
L1736
L1737
L1738
L1739
L1740
L1741
L1742
L1743
L1744
L1745
L1746
L1747
L1748
L1749
L1750
L1751
L1752
L1753
L1754
L1755
L1756
L1757
L1758
L1759
L1760
L1761
L1762
L1763
L1764
L1765
L1766
L1767
L1768
L1769
L1770
L1771
L1772
L1773
L1774
L1775
L1776
L1777
L1778
L1779
L1780
L1781
L1782
L1783
L1784
L1785
L1786
L1787
L1788
L1789
L1790
L1791
L1792
L1793
L1794
L1795
L1796
L1797
L1798
L1799
L1800
L1801
L1802
L1803
L1804
L1805
L1806
L1807
L1808
L1809
L1810
L1811
L1812
L1813
L1814
L1815
L1816
L1817
L1818
L1819
L1820
L1821
L1822
L1823
L1824
L1825
L1826
L1827
L1828
L1829
L1830
L1831
L1832
L1833
L1834
L1835
L1836
L1837
L1838
L1839
L1840
L1841
L1842
L1843
L1844
L1845
L1846
L1847
L1848
L1849
L1850
L1851
L1852
L1853
L1854
L1855
L1856
L1857
L1858
L1859
L1860
L1861
L1862
L1863
L1864
L1865
L1866
L1867
L1868
L1869
L1870
L1871
L1872
L1873
L1874
L1875
L1876
L1877
L1878
L1879
L1880
L1881
L1882
L1883
L1884
L1885
L1886
L1887
L1888
L1889
L1890
L1891
L1892
L1893
L1894
L1895
L1896
L1897
L1898
L1899
L1900
L1901
L1902
L1903
L1904
L1905
L1906
L1907
L1908
L1909
L1910
L1911
L1912
L1913
L1914
L1915
L1916
L1917
L1918
L1919
L1920
L1921
L1922
L1923
L1924
L1925
L1926
L1927
L1928
L1929
L1930
L1931
L1932
L1933
L1934
L1935
L1936
L1937
L1938
L1939
L1940
L1941
L1942
L1943
L1944
L1945
L1946
L1947
L1948
L1949
L1950
L1951
L1952
L1953
L1954
L1955
L1956
L1957
L1958
L1959
L1960
L1961
L1962
L1963
L1964
L1965
L1966
L1967
L1968
L1969
L1970
L1971
L1972
L1973
L1974
L1975
L1976
L1977
L1978
L1979
L1980
L1981
L1982
L1983
L1984
L1985
L1986
L1987
L1988
L1989
L1990
L1991
L1992
L1993
L1994
L1995
L1996
L1997
L1998
L1999
L2000
L2001
L2002
L2003
L2004
L2005
L2006
L2007
L2008
L2009
L2010
L2011
L2012
L2013
L2014
L2015
L2016
L2017
L2018
L2019
L2020
L2021
L2022
L2023
L2024
L2025
L2026
L2027
L2028
L2029
L2030
L2031
L2032
L2033
L2034
L2035
L2036
L2037
L2038
L2039
L2040
L2041
L2042
L2043
L2044
L2045
L2046
L2047
L2048
L2049
L2050
L2051
L2052
L2053
L2054
L2055
L2056
L2057
L2058
L2059
L2060
L2061
L2062
L2063
L2064
L2065
L2066
L2067
L2068
L2069
L2070
L2071
L2072
L2073
L2074
L2075
L2076
L2077
L2078
L2079
L2080
L2081
L2082
L2083
L2084
L2085
L2086
L2087
L2088
L2089
L2090
L2091
L2092
L2093
L2094
L2095
L2096
L2097
L2098
L2099
L2100
L2101
L2102
L2103
L2104
L2105
L2106
L2107
L2108
L2109
L2110
L2111
L2112
L2113
L2114
L2115
L2116
L2117
L2118
L2119
L2120
L2121
L2122
L2123
L2124
L2125
L2126
L2127
L2128
L2129
L2130
L2131
L2132
L2133
L2134
L2135
L2136
L2137
L2138
L2139
L2140
L2141
L2142
L2143
L2144
L2145
L2146
L2147
L2148
L2149
L2150
L2151
L2152
L2153
L2154
L2155
L2156
L2157
L2158
L2159
L2160
L2161
L2162
L2163
L2164
L2165
L2166
L2167
L2168
L2169
L2170
L2171
L2172
L2173
L2174
L2175
L2176
L2177
L2178
L2179
L2180
L2181
L2182
L2183
L2184
L2185
L2186
L2187
L2188
L2189
L2190
L2191
L2192
L2193
L2194
L2195
L2196
L2197
L2198
L2199
L2200
L2201
L2202
L2203
L2204
L2205
L2206
L2207
L2208
L2209
L2210
L2211
L2212
L2213
L2214
L2215
L2216
L2217
L2218
L2219
L2220
L2221
L2222
L2223
L2224
L2225
L2226
L2227
L2228
L2229
L2230
L2231
L2232
L2233
L2234
L2235
L2236
L2237
L2238
L2239
L2240
L2241
L2242
L2243
L2244
L2245
L2246
L2247
L2248
L2249
L2250
L2251
L2252
L2253
L2254
L2255
L2256
L2257
L2258
L2259
L2260
L2261
L2262
L2263
L2264
L2265
L2266
L2267
L2268
L2269
L2270
L2271
L2272
L2273
L2274
L2275
L2276
L2277
L2278
L2279
L2280
L2281
L2282
L2283
L2284
L2285
L2286
L2287
L2288
L2289
L2290
L2291
L2292
L2293
L2294
L2295
L2296
L2297
L2298
L2299
L2300
L2301
L2302
L2303
L2304
L2305
L2306
L2307
L2308
L2309
L2310
L2311
L2312
L2313
L2314
L2315
L2316
L2317
L2318
L2319
L2320
L2321
L2322
L2323
L2324
L2325
L2326
L2327
L2328
L2329
L2330
L2331
L2332
L2333
L2334
L2335
L2336
L2337
L2338
L2339
L2340
L2341
L2342
L2343
L2344
L2345
L2346
L2347
L2348
L2349
L2350
L2351
L2352
L2353
L2354
L2355
L2356
L2357
L2358
L2359
L2360
L2361
L2362
L2363
L2364
L2365
L2366
L2367
L2368
L2369
L2370
L2371
L2372
L2373
L2374
L2375
L2376
L2377
L2378
L2379
L2380
L2381
L2382
L2383
L2384
L2385
L2386
L2387
L2388
L2389
L2390
L2391
L2392
L2393
L2394
L2395
L2396
L2397
L2398
L2399
L2400
L2401
L2402
L2403
L2404
L2405
L2406
L2407
L2408
L2409
L2410
L2411
L2412
L2413
L2414
L2415
L2416
L2417
L2418
L2419
L2420
L2421
L2422
L2423
L2424
L2425
L2426
L2427
L2428
L2429
L2430
L2431
L2432
L2433
L2434
L2435
L2436
L2437
L2438
L2439
L2440
L2441
L2442
L2443
L2444
L2445
L2446
L2447
L2448
L2449
L2450
L2451
L2452
L2453
L2454
L2455
L2456
L2457
L2458
L2459
L2460
L2461
L2462
L2463
L2464
L2465
L2466
L2467
L2468
L2469
L2470
L2471
L2472
L2473
L2474
L2475
L2476
L2477
L2478
L2479
L2480
L2481
L2482
L2483
L2484
L2485
L2486
L2487
L2488
L2489
L2490
L2491
L2492
L2493
L2494
L2495
L2496
L2497
L2498
L2499
L2500
L2501
L2502
L2503
L2504
L2505
L2506
L2507
L2508
L2509
L2510
L2511
L2512
L2513
L2514
L2515
L2516
L2517
L2518
L2519
L2520
L2521
L2522
L2523
L2524
L2525
L2526
L2527
L2528
L2529
L2530
L2531
L2532
L2533
L2534
L2535
L2536
L2537
L2538
L2539
L2540
L2541
L2542
L2543
L2544
L2545
L2546
L2547
L2548
L2549
L2550
L2551
L2552
L2553
L2554
L2555
L2556
L2557
L2558
L2559
L2560
L2561
L2562
L2563
L2564
L2565
L2566
L2567
L2568
L2569
L2570
L2571
L2572
L2573
L2574
L2575
L2576
L2577
L2578
L2579
L2580
L2581
L2582
L2583
L2584
L2585
L2586
L2587
L2588
L2589
L2590
L2591
L2592
L2593
L2594
L2595
L2596
L2597
L2598
L2599
L2600
L2601
L2602
L2603
L2604
L2605
L2606
L2607
L2608
L2609
L2610
L2611
L2612
L2613
L2614
L2615
L2616
L2617
L2618
L2619
L2620
L2621
L2622
L2623
L2624
L2625
L2626
L2627
L2628
L2629
L2630
L2631
L2632
L2633
L2634
L2635
L2636
L2637
L2638
L2639
L2640
L2641
L2642
L2643
L2644
L2645
L2646
L2647
L2648
L2649
L2650
L2651
L2652
L2653
L2654
L2655
L2656
L2657
L2658
L2659
L2660
L2661
L2662
L2663
L2664
L2665
L2666
L2667
L2668
L2669
L2670
L2671
L2672
L2673
L2674
L2675
L2676
L2677
L2678
L2679
L2680
L2681
L2682
L2683
L2684
L2685
L2686
L2687
L2688
L2689
L2690
L2691
L2692
L2693
L2694
L2695
L2696
L2697
L2698
L2699
L2700
L2701
L2702
L2703
L2704
L2705
L2706
L2707
L2708
L2709
L2710
L2711
L2712
L2713
L2714
L2715
L2716
L2717
L2718
L2719
L2720
L2721
L2722
L2723
L2724
L2725
L2726
L2727
L2728
L2729
L2730
L2731
L2732
L2733
L2734
L2735
L2736
L2737
L2738
L2739
L2740
L2741
L2742
L2743
L2744
L2745
L2746
L2747
L2748
L2749
L2750
L2751
L2752
L2753
L2754
L2755
L2756
L2757
L2758
L2759
L2760
L2761
L2762
L2763
L2764
L2765
L2766
L2767
L2768
L2769
L2770
L2771
L2772
L2773
L2774
L2775
L2776
L2777
L2778
L2779
L2780
L2781
L2782
L2783
L2784
L2785
L2786
L2787
L2788
L2789
L2790
L2791
L2792
L2793
L2794
L2795
L2796
L2797
L2798
L2799
L2800
L2801
L2802
L2803
L2804
L2805
L2806
L2807
L2808
L2809
L2810
L2811
L2812
L2813
L2814
L2815
L2816
L2817
L2818
L2819
L2820
L2821
L2822
L2823
L2824
L2825
L2826
L2827
L2828
L2829
L2830
L2831
L2832
L2833
L2834
L2835
L2836
L2837
L2838
L2839
L2840
L2841
L2842
L2843
L2844
L2845
L2846
L2847
L2848
L2849
L2850
L2851
L2852
L2853
L2854
L2855
L2856
L2857
L2858
L2859
L2860
L2861
L2862
L2863
L2864
L2865
L2866
L2867
L2868
L2869
L2870
L2871
L2872
L2873
L2874
L2875
L2876
L2877
L2878
L2879
L2880
L2881
L2882
L2883
L2884
L2885
L2886
L2887
L2888
L2889
L2890
L2891
L2892
L2893
L2894
L2895
L2896
L2897
L2898
L2899
L2900
L2901
L2902
L2903
L2904
L2905
L2906
L2907
L2908
L2909
L2910
L2911
L2912
L2913
L2914
L2915
L2916
L2917
L2918
L2919
L2920
L2921
L2922
L2923
L2924
L2925
L2926
L2927
L2928
L2929
L2930
L2931
L2932
L2933
L2934
L2935
L2936
L2937
L2938
L2939
L2940
L2941
L2942
L2943
L2944
L2945
L2946
L2947
L2948
L2949
L2950
L2951
L2952
L2953
L2954
L2955
L2956
L2957
L2958
L2959
L2960
L2961
L2962
L2963
L2964
L2965
L2966
L2967
L2968
L2969
L2970
L2971
L2972
L2973
L2974
L2975
L2976
L2977
L2978
L2979
L2980
L2981
L2982
L2983
L2984
L2985
L2986
L2987
L2988
L2989
L2990
L2991
L2992
L2993
L2994
L2995
L2996
L2997
L2998
L2999
L3000
L3001
L3002
L3003
L3004
L3005
L3006
L3007
L3008
L3009
L3010
L3011
L3012
L3013
L3014
L3015
L3016
L3017
L3018
L3019
L3020
L3021
L3022
L3023
L3024
L3025
L3026
L3027
L3028
L3029
L3030
L3031
L3032
L3033
L3034
L3035
L3036
L3037
L3038
L3039
L3040
L3041
L3042
L3043
L3044
L3045
L3046
L3047
L3048
L3049
L3050
L3051
L3052
L3053
L3054
L3055
L3056
L3057
L3058
L3059
L3060
L3061
L3062
L3063
L3064
L3065
L3066
L3067
L3068
L3069
L3070
L3071
L3072
L3073
L3074
L3075
L3076
L3077
L3078
L3079
L3080
L3081
L3082
L3083
L3084
L3085
L3086
L3087
L3088
L3089
L3090
L3091
L3092
L3093
L3094
L3095
L3096
L3097
L3098
L3099
L3100
L3101
L3102
L3103
L3104
L3105
L3106
L3107
L3108
L3109
L3110
L3111
L3112
L3113
L3114
L3115
L3116
L3117
L3118
L3119
L3120
L3121
L3122
L3123
L3124
L3125
L3126
L3127
L3128
L3129
L3130
L3131
L3132
L3133
L3134
L3135
L3136
L3137
L3138
L3139
L3140
L3141
L3142
L3143
L3144
L3145
L3146
L3147
L3148
L3149
L3150
L3151
L3152
L3153
L3154
L3155
L3156
L3157
L3158
L3159
L3160
L3161
L3162
L3163
L3164
L3165
L3166
L3167
L3168
L3169
L3170
L3171
L3172
L3173
L3174
L3175
L3176
L3177
L3178
L3179
L3180
L3181
L3182
L3183
L3184
L3185
L3186
L3187
L3188
L3189
L3190
L3191
L3192
L3193
L3194
L3195
L3196
L3197
L3198
L3199
L3200
L3201
L3202
L3203
L3204
L3205
L3206
L3207
L3208
L3209
L3210
L3211
L3212
L3213
L3214
L3215
L3216
L3217
L3218
L3219
L3220
L3221
L3222
L3223
L3224
L3225
L3226
L3227
L3228
L3229
L3230
L3231
L3232
L3233
L3234
L3235
L3236
L3237
L3238
L3239
L3240
L3241
L3242
L3243
L3244
L3245
L3246
L3247
L3248
L3249
L3250
L3251
L3252
L3253
L3254
L3255
L3256
L3257
L3258
L3259
L3260
L3261
L3262
L3263
L3264
L3265
L3266
L3267
L3268
L3269
L3270
L3271
L3272
L3273
L3274
L3275
L3276
L3277
L3278
L3279
L3280
L3281
L3282
L3283
L3284
L3285
L3286
L3287
L3288
L3289
L3290
L3291
L3292
L3293
L3294
L3295
L3296
L3297
L3298
L3299
L3300
L3301
L3302
L3303
L3304
L3305
L3306
L3307
L3308
L3309
L3310
L3311
L3312
L3313
L3314
L3315
L3316
L3317
L3318
L3319
L3320
L3321
L3322
L3323
L3324
L3325
L3326
L3327
L3328
L3329
L3330
L3331
L3332
L3333
L3334
L3335
L3336
L3337
L3338
L3339
L3340
L3341
L3342
L3343
L3344
L3345
L3346
L3347
L3348
L3349
L3350
L3351
L3352
L3353
L3354
L3355
L3356
L3357
L3358
L3359
L3360
L3361
L3362
L3363
L3364
L3365
L3366
L3367
L3368
L3369
L3370
L3371
L3372
L3373
L3374
L3375
L3376
L3377
L3378
L3379
L3380
L3381
L3382
L3383
L3384
L3385
L3386
L3387
L3388
L3389
L3390
L3391
L3392
L3393
L3394
L3395
L3396
L3397
L3398
L3399
L3400
L3401
L3402
L3403
L3404
L3405
L3406
L3407
L3408
L3409
L3410
L3411
L3412
L3413
L3414
L3415
L3416
L3417
L3418
L3419
L3420
L3421
L3422
L3423
L3424
L3425
L3426
L3427
L3428
L3429
L3430
L3431
L3432
L3433
L3434
L3435
L3436
L3437

TOWN MADISON

Layout Notes:

1. All dimensions are from back of curb, U.N.O.
2. Sidewalks to have max cross slope of 2%.

Excavation Area

FLOODWAY BOUNDARY

60' U. & D. EASEMENT

15' UTILITY EASEMENT

BLDG 2
FFE 633.00

BLDG 3
FFE 630.90

BLDG 4
FFE 632.75

Clubhouse

BLDG 5
FFE 633.00

BLDG 6
FFE 629.60

BLDG 7
FFE 626.50

BLDG 13
FFE 629.75

BLDG 14
FFE 622.60

BLDG 15
FFE 621.90

BLDG 16
FFE 620.80

BLDG 17
FFE 621.50

LOT 2

FFE 630.00

FFE 630.00

S 89°58'59" W 961.65'

Site Plan
Scale: 1" = 30'

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect of the project. All Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 503, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT
RICHARD SCOTT MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: Rohdie Group

FINAL FOR DEVELOPMENT
Site Plan
DEC 09 2021

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C2.1

TOWN MADISON

Layout Notes:

1. All dimensions are from back of curb, U.N.O.
2. Sidewalks to have max cross slope of 2%.

Sidewalk part of Villas Project

Req'd Sidewalk of this project

LIME QUARRY ROAD

Ex. SPHW
Ex. INV OUT 617.98±

Ex. SWSI
Ex. INV IN (E) 623.29±
Ex. INV (S) 619.39±
Ex. INV OUT 619.39±

Ex. SPHW
Ex. INV OUT 624.50±

Ex. JB
Ex. RIM
Ex. INV
Ex. INV

Ex. SWSI
Ex. INV IN 624.00±
Ex. INV OUT 623.90±

S 88°08'48" E
92.08'

S 57°19'08" E
169.05'

L46
L47
L39
L40
L36
L41
L50
L49
L48
L44
L43
L52

N 49°01'17" E
186.22'
FLOODWAY

N 32°56'32" E
259.57'

1% Annual Chance Floodplain Boundary

Excavation Area

BLDG 1
FFE 630.00

BLDG 8
FFE 627.80

BLDG 9
FFE 627.90

BLDG 10
FFE 628.40

BLDG 11
FFE 628.30

BLDG 12
FFE 629.00

BLDG 13
FFE 629.75

FINAL FOR DEVELOPMENT
DEC 09 2021

Site Plan
Scale: 1" = 30'

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 503, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT RICHARD SCOTT MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL


PREPARED FOR: Rohdie Group

Site Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C2.2



Notes:

1. All traffic control devices shall be erected and maintained in conformance with the Manual on Uniform Traffic-Control Devices and any revision thereof.
2. Required Fire Flows cannot be determined precisely until the specific building use, construction type and other factors have been disclosed and reviewed. The applicant will comply with the fire flow and fire safety and suppression requirements of all adopted city codes and regulations.
3. All drainage ditches are to be centered on property lines unless otherwise shown.
4. All utilities shall be underground.
5. If adverse conditions are uncovered during construction, the city engineer may require modification of these plans to the extent necessary to assure compliance with the City's construction specification manual.
6. All lots shall be graded so that run-off will be directed to the street or to drainage ways in a dedicated easement.
7. Setbacks are governed by the latest edition of the Zoning Ordinance of the City of Madison.
8. Dumpster enclosure, per City of Madison requirements, required prior to Certificate of Occupancy for building.

Keynote Legend:

A1	Req'd Standard 24" Conc. Curb & Gutter, see detail.
A2	Req'd Concrete Integral Curb, see detail.
A3	Req'd Fully Mountable Curb w/ Channel, see detail.
A4	Req'd 18" Conc. Ribbon Curb, see detail.
B1	Req'd 4" thick Conc. Sidewalk, width as shown.
B2	Req'd Curb Ramp, curb-return style
B3	Req'd 6" thick Conc. Paving with 6x6 10/10 WWM
B4	Req'd Turn-down Sidewalk, see detail.
B5	Req'd flush condition between pavement and sidewalk, coord. w/ Grading Plan.
B6	Req'd truncated domes and detectible warning pavers.
B7	Req'd sidewalk guardrail, per Town Madison Specs.
C1	Req'd Asphalt Paving, see detail.
D1	Req'd parking stall striping, white, 4" wide, painted.
D2	Req'd ADA parking stall striping & markings, blue, 4" wide, painted.
E1	Req'd Utility Infrastructure, see Utility Plan.
E2	Req'd Grate Inlet, see Utility Plan
F1	Req'd "STOP" sign, per Town Madison Specs.
F2	Req'd ADA Parking sign, per Town Madison Specs.
F3	Req'd Dumpster enclosure; coord. w/ Architectural Plans.
F4	Req'd "Compact Parking" sign, per Town Madison Specs.
G1	Req'd Concrete 8" Concrete Wheel Stop.

Fire Department Notes:

1. SECURITY GATES SHALL MEET MADISON FIRE & RESCUE REQUIREMENTS FOR ACCESSIBILITY (CLICK 2 ENTER)

Keynote Plan
Scale: 1" = 50'

FINAL FOR DEVELOPMENT
DEC 09 2021

TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT JAMES L. MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: Rohdie Group

Keynote Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C2.3

TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face are instruments of service in respect of the Project. Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT ROBERT SCOTT MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: Rohdie Group

Overall Site Plan


Job No.: 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C2.4

FINAL FOR DEVELOPMENT
DEC 09 2021

Overall View
Scale: 1" = 100'




FDC w/ Sign Detail
NOT to Scale

Notes:


1. All service lines shall be stubbed & capped within 5' of buildings for plumbing tie-in.
2. Private hydrants shall be silver in color.
3. Connection to existing water main to be provided and installed by Developer.
4. Class 1 commination automatic standpipe shall be required in stairways for 4 story buildings.
5. Elevator/Emergency Knox Boxes required.
6. IFC 2015 510.1 Emergency responder radio coverage in new buildings. All new buildings shall have approved radio coverage for emergency responders within the building based upon the exisiting coverage levels of the public safety communication systems of the jurisdicton at the exterior of the building. This section shall not require improvement of the existing public safety communication systems.
7. Fire vault valves are required to be electronically tampered.

Water Legend:


- W — W — 8" Domestic Line
- — • — • — 2" Domestic Service Line
- 6" Sprinkler Line



Utility Meter Detail
NOT to Scale



Utility Branch Detail
NOT to Scale



Water Plan
Scale: 1" = 50'

FINAL FOR DEVELOPMENT
DEC 09 2021

TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in which the aforesaid Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT RICHARD SCOTT MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Water Infrastructure Plan

Job No.	21-128
Date:	2021 11-16
Drawn By:	JLH
Checked By:	RS

SHEET NUMBER

C3

TOWN MADISON

LIME QUARRY ROAD

Villas Project

Req'd Sidewalk of this project

S 88°08'48" E 92.08'

S 5°51'19" E 69.05'

BLDG 1
FFE 630.00

BLDG 2
FFE 633.00

BLDG 3
FFE 630.90

BLDG 4
FFE 632.75

Clubhouse
FFE 631.18

BLDG 5
FFE 633.00

BLDG 6
FFE 627.80

BLDG 7
FFE 626.50

BLDG 9
FFE 627.50

BLDG 10
FFE 628.00

BLDG 11
FFE 629.60

BLDG 12
FFE 629.00

BLDG 13
FFE 629.75

BLDG 14
FFE 621.60

BLDG 15
FFE 621.90

BLDG 16
FFE 620.60

BLDG 17
FFE 621.50

LOT 2

LOT 4

DUNLOP BOULEVARD

1% Annual Chance Floodplain Boundary

Excavation Area

FLOODWAY

FLOODWAY BOUNDARY

60' U. & D. EASEMENT

N 49°01'17" E 186.22'

N 35°55'52" E 259.57'

N 22°35'21" E 321.00'

S 10°24'36" W 162.85'

N 13°35'16" E 334.61'

N 4°19'26" W 230.61'

S 12°42'28" W 265.56'

S 89°56'59" W 961.65'

Ex. SSMH 3
STA 7+06.03
Ex. TOP 625.52±
Ex. INV IN 608.98±
Ex. INV OUT 608.92±

Special Flood Hazard Area (SFHA) Zone AE

33 LF of 15" HDPE (x2) @ 1.00%

29 LF of 24" HDPE (x3) @ 1.00%

Ex. SWSI
Ex. INV IN (E) 623.29±
Ex. INV (S) 619.39±
Ex. INV OUT 619.39±

Ex. SPHW
Ex. INV OUT 624.50±

Ex. JB
Ex. RIM 634.21±
Ex. INV IN 625.4
Ex. INV OUT 62(

Ex. SWSI
Ex. INV IN 624.00±
Ex. INV OUT 623.90±

Ex. JB
Ex. RIM 634.24±
Ex. INV IN 625.96±
Ex. INV OUT 625.86±

Ex. JB
Ex. INV IN (S)629.13±
Ex. INV IN (N) 628.63±
Ex. INV IN (E) 627.24±
Ex. INV OUT 627.14±

Ex. DWSI
Ex. INV IN 629.35±
Ex. INV OUT 629.25±

Ex. SWSI
Ex. INV OUT 630.80±

Ex. SWSI
Ex. INV OUT 630.45±

Ex. SWSI
Ex. INV IN 630.14±
Ex. INV OUT 630.04±

Ex. SWSI
Ex. INV IN 628.57±
Ex. INV OUT 628.07±

Ex. SWSI
Ex. INV IN 628.98±
Ex. INV OUT 628.88±

Ex. SPHW
Ex. INV OUT 629.59±

EX SW
Rim = 632.00

SPHW H
Rim = 622.00

Pipe H1 10.99'
of 18.00" HDPE

Pipe H2 18.02'
of 18.00" HDPE

GI H1
Rim = 624.76

GI H2
Rim = 625.00

SPHW G
Rim = 623.00

Pipe G1 52.50'
of 24.00" HDPE

Pipe G8 43.90'
of 18.00" HDPE

GI G8
Rim = 626.69

GI G6
Rim = 628.00

GI G9
Rim = 628.38

Pipe G2 29.69'
of 24.00" HDPE

Pipe G3 52.08'
of 24.00" HDPE

Pipe G7 92.27'
of 18.00" HDPE

Pipe G6 155.96'
of 18.00" HDPE

JB G1
Rim = 627.25

SPHW E
Rim = 622.00

Pipe E1 55.26'
of 24.00" HDPE

Pipe E2 37.37'
of 24.00" HDPE

GI G2
Rim = 626.52

Pipe G4 69.91'
of 18.00" HDPE

SPHW F
Rim = 623.00

GI G3
Rim = 627.54

GI G4
Rim = 628.56

GI G5
Rim = 630.86

Pipe F12 52.06'
of 18.00" HDPE

Pipe F11 96.79'
of 18.00" HDPE

Pipe F10 52.06'
of 18.00" HDPE

JB F1
Rim = 628.58
Pipe F1 = 622.90
Pipe F2 = 623.08

GI F12
Rim = 629.59
Pipe F12 = 625.84

GI F11
Rim = 627.75
Pipe F11 = 624.40
Pipe F12 = 624.50

GI F10
Rim = 630.39
Pipe F10 = 626.64

GI F4
Rim = 627.06
Pipe F2 = 623.42
Pipe F3 = 623.42
Pipe F11 = 623.42

Pipe F3 64.12'
of 24.00" HDPE

SPHW I
Rim = 625.00

GI I3
Rim = 627.94
Pipe F3 = 623.75
Pipe F4 = 623.85

Pipe F4 78.22'
of 18.00" HDPE

Pipe F5 52.04'
of 18.00" HDPE

GI F8
Rim = 629.99
Pipe F5 = 624.91
Pipe F6 = 624.71

Pipe F6 86.99'
of 18.00" HDPE

GI F1
Rim = 628.39
Pipe E1 = 623.14

GI F2
Rim = 628.67
Pipe F4 = 624.25
Pipe F5 = 624.35

Pipe F9 72.72'
of 18.00" HDPE

GI F9
Rim = 628.97
Pipe F9 = 625.62
Pipe F10 = 625.72

Pipe F7 127.04'
of 18.00" HDPE

GI F7
Rim = 631.18
Pipe F7 = 627.37
Pipe F8 = 627.47

Pipe F8 55.31'
of 18.00" PVC

GI F8
Rim = 631.00
Pipe F8 = 627.75

SPHW D
Rim = 624.00

Pipe D1 37.41'
of 18.00" HDPE

JB B1
Rim = 622.90
Pipe B1 = 618.30
Pipe B2 = 618.40

GI D1
Rim = 626.50
Pipe D1 = 623.25

GI D2
Rim = 622.93
Pipe B2 = 618.49
Pipe B3 = 618.59

Excavation Area

SPHW B
Rim = 612.00

Pipe B1 20.99'
of 30.00" HDPE

Pipe B3 90.09'
of 30.00" HDPE

Pipe B2 18.00'
of 30.00" HDPE

GI B3
Rim = 623.80
Pipe B3 = 619.05
Pipe B4 = 619.15

GI A1
Rim = 620.63
Pipe A1 = 617.13
Pipe A2 = 617.23

SPHW A
Rim = 618.00

GI A2
Rim = 620.67
Pipe A2 = 617.32
Pipe A3 = 617.42

Pipe A1 18.49'
of 18.00" HDPE

Pipe A3 64.08'
of 18.00" HDPE

Pipe A4 36.22'
of 18.00" RCP

Pipe A2 78.05'
of 18.00" HDPE

GI A3
Rim = 622.60
Pipe A3 = 619.25
Pipe A4 = 619.35

GI A4
Rim = 622.80
Pipe A4 = 619.55

GI B4
Rim = 624.64
Pipe B4 = 619.76
Pipe B5 = 619.86
Pipe B13 = 619.86

Pipe B4 121.79'
of 30.00" HDPE

Pipe B16 98.54'
of 18.00" RCP

Pipe B15 98.73'
of 18.00" HDPE

GI B15
Rim = 628.00
Pipe B15 = 624.75

GI B16
Rim = 628.00
Pipe B16 = 624.75

GI B11
Rim = 631.18
Pipe B11 = 626.38
Pipe B12 = 626.48

Pipe B14 116.78'
of 18.00" HDPE

Pipe B13 103.78'
of 18.00" RCP

GI B14
Rim = 628.00
Pipe B14 = 624.15
Pipe B15 = 624.25

GI B13
Rim = 628.00
Pipe B13 = 623.46
Pipe B14 = 623.56
Pipe B16 = 623.56

Pipe B11 84.78'
of 18.00" HDPE

GI B12
Rim = 630.20
Pipe B12 = 626.99

Pipe B12 85.97'
of 18.00" HDPE

GI J2
Rim = 631.49
Pipe J2 = 629.36

Pipe J2 110.42'
of 15.00" HDPE

GI J1
Rim = 631.49
Pipe J1 = 628.70
Pipe J2 = 628.80
Pipe J3 = 628.80

Pipe J1 25.51'
of 15.00" HDPE

GI J3
Rim = 631.49
Pipe J3 = 629.25

Pipe J3 37.27'
of 15.00" HDPE

SPHW C
Rim = 615.00

Pipe C1 45.69'
of 24.00" HDPE

Pipe C7 63.17'
of 18.00" HDPE

Pipe C2 31.00'
of 18.00" HDPE

Pipe C3 51.78'
of 18.00" HDPE

GI C7
Rim = 621.00
Pipe C7 = 617.80

GI C6
Rim = 623.88
Pipe C6 = 620.63

GI C3
Rim = 620.04
Pipe C3 = 615.89
Pipe C4 = 615.98

JB C1
Rim = 619.65
Pipe C1 = 615.26
Pipe C2 = 615.36
Pipe C7 = 615.36

GI C2
Rim = 615.65
Pipe C2 = 615.52
Pipe C3 = 615.62

GI C4
Rim = 619.34

Pipe C4 69.95'
of 18.00" HDPE

Pipe C6 70.10'
of 18.00" HDPE

Pipe C5 209.98'
of 18.00" HDPE

GI B5
Rim = 626.00
Pipe B5 = 620.63
Pipe B6 = 620.73

Pipe B6 127.61'
of 24.00" HDPE

Pipe B17 12.96'
of 24.00" HDPE

Pipe B9 50.06'
of 18.00" HDPE

GI B17
Rim = 626.46
Pipe B17 = 623.21
Pipe B9 = 623.31

GI B8
Rim = 626.56
Pipe B8 = 623.01
Pipe B17 = 623.11

Pipe B8 57.07'
of 24.00" HDPE

Pipe B7 138.63'
of 24.00" HDPE

GI B6
Rim = 624.72
Pipe B6 = 621.37
Pipe B7 = 621.47

GI B7
Rim = 626.12
Pipe B7 = 622.14

GI B10
Rim = 630.31
Pipe B10 = 625.01
Pipe B11 = 625.11

Pipe B10 52.06'
of 18.00" HDPE

GI B9
Rim = 627.72
Pipe B9 = 624.38
Pipe B10 = 624.48

Storm Plan
Scale: 1" = 50'

FINAL FOR DEVELOPMENT
DEC 09 2021

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER JAMES L. MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---


Storm Infrastructure Plan


Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS


SHEET NUMBER


C4.1


TOWN MADISON


























REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service for use solely with respect to Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER RICHARD SCOTT MULLINS 29511
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Storm Infrastructure Profiles

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS


SHEET NUMBER


C4.2


FINAL FOR DEVELOPMENT
DEC 09 2021


Storm Profiles
Horizontal Scale: 1" = 60'
Vertical Scale: 1" = 6'


TOWN MADISON




















FINAL FOR DEVELOPMENT
DEC 09 2021

Storm Profiles
Horizontal Scale: 1" = 60'
Vertical Scale: 1" = 6'

REVISIONS
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service for use solely by Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 503, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER JOSEPH L. MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Storm Infrastructure Profiles

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER
C4.3

TOWN MADISON

LIME QUARRY ROAD

part of Villas Project

Req'd Sidewalk of this project

N 83°24'19" E 219.34'

S 88°08'48" E 62.08'

S 89°58'59" W 690.05'

S 89°58'59" W 961.65'

S 89°58'59" W 354.36'

LOT 1

LOT 2

LOT 4

DUNLOP BOULEVARD

1% Annual Chance Floodplain Boundary

FLOODWAY

FLOODWAY BOUNDARY

Special Flood Hazard Area (SFHA) Zone A

Excavation Area

60' G.P.C. & U.E. EASEMENT

BLDG 1 FFE 630.00

BLDG 2 FFE 633.00

BLDG 3 FFE 630.90

BLDG 4 FFE 632.75 Clubhouse

BLDG 5 FFE 633.00

BLDG 6 FFE 629.60

BLDG 7 FFE 626.50

BLDG 9 FFE 627.30

BLDG 10 FFE 628.40

BLDG 11 FFE 628.50

BLDG 12 FFE 628.60

BLDG 13 FFE 628.75

BLDG 14 FFE 622.60

BLDG 15 FFE 621.90

BLDG 16 FFE 620.80

BLDG 17 FFE 621.50

SSMH 1 STA 2+66.18 TOP 619.30 INV IN 611.00 INV OUT 610.80

SSMH 2 STA 4+30.50 TOP 620.87 INV IN 612.75 INV OUT 612.65

SSMH 3 STA 7+06.03 Ex. TOP 625.52± Ex. INV IN 608.98± Ex. INV OUT 608.92±

SSMH 4 STA 10+39.01 TOP 629.66 INV IN 618.82 INV OUT 618.72

SSMH 5 STA 14+39.01 TOP 626.82 INV OUT 620.82

SSMH 6 STA 6+28.84 TOP 625.00 INV IN 616.82 INV OUT 616.72

SSMH 7 STA 10+28.84 TOP 628.34 INV OUT 622.00

SSMH 8 STA 12+58.12 TOP 630.62 INV OUT 622.00

8" DIP 164 LF @ 1.00%

8" DIP 266 LF @ 2.04%

8" DIP 364 LF @ 0.94%

8" PVC 245 LF @ 1.00%

8" PVC 198 LF @ 2.00%

8" PVC 400 LF @ 0.50%

8" PVC 400 LF @1.30%

8" PVC 219 LF @1.45%

Ex. MSMH STA 12+19.46 Ex. TOP 618.90± Ex. INV IN 602.87± Ex. INV OUT 602.69± INV IN 605.37

Ex. HSMH Ex. TOP 618.98± Ex. INV 600.81±

Ex. SPHW Ex. INV OUT 617.98±

Ex. SWSI Ex. INV IN (E) 623.29± Ex. INV (S) 619.39± Ex. INV OUT 619.39±

Ex. SWSI Ex. INV IN 62 Ex. INV OUT

Ex. RIM 634.24± Ex. INV IN 625.96± Ex. INV OUT 625.86±

Ex. JB Ex. INV IN (S)629.13± Ex. INV IN (N) 628.63± Ex. INV IN (E) 627.24± Ex. INV OUT 627.14±

Ex. DWSI Ex. INV IN 629.35± Ex. INV OUT 629.25±

Ex. SWSI Ex. INV OUT 630.80±

Ex. SWSI Ex. INV OUT 630.45±

Ex. SWSI Ex. INV IN 630.14± Ex. INV OUT 630.04±

Ex. SWSI Ex. INV IN 628.57± Ex. INV OUT 628.07±

Ex. SWSI Ex. INV IN 628.98± Ex. INV OUT 628.88±

Ex. SPHW Ex. INV OUT 629.59±

Ex. DWSI Ex. INV IN (N) 626.15± Ex. INV IN (E) 626.55± Ex. INV OUT 626.05±

Ex. DWSI Ex. INV OUT 626.96±

Sanitary Notes:
1. Proposed Sanitary Sewer Mains are to match at crown of existing 30" Sewer Main.
2. All Sanitary Laterals shall be 6" PVC at minimum of 1.00% slope.
3. All private manholes are to have a generic cover that does not reference Madison Utilities.

FINAL FOR DEVELOPMENT

DEC 09 2021

Sanitary Sewer Plan
Scale: 1" = 60'

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect of the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 503, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT MICHAEL E. MULLINS

November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---


Sanitary Sewer Infrastructure Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER


C5


TOWN MADISON




Sanitary Sewer Plan & Profile
Horizontal Scale: 1" = 60'
Vertical Scale: 1" = 12'

ALIGNMENT - Ex. MSMH TO SSMH 7






Sanitary Sewer Plan & Profile
Horizontal Scale: 1" = 60'
Vertical Scale: 1" = 12'




ALIGNMENT - SSMH 4 TO SSMH 8



Sanitary Sewer Plan & Profile
Horizontal Scale: 1" = 60'
Vertical Scale: 1" = 12'

ALIGNMENT - SSMH 2 TO SSMH 5



FINAL FOR DEVELOPMENT
DEC 8 2021

REVISIONS
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project. All Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER JOHN L. HOLLOWAY
November 16, 2021

The Roberts Apartments at TM
Madison, AL

PREPARED FOR: ---

Sanitary Sewer Plan & Profile

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER
C5.1



TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT JAMES L. MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Overall Grading Plan

Job No.	21-128
Date:	2021 11-16
Drawn By:	JLH
Checked By:	RS

SHEET NUMBER

C6

1% Annual Chance Floodplain Boundary

FLOODWAY BOUNDARY

Excavation Area

60' W. & D. EASEMENT

BLDG 12
FFE 629.00

BLDG 13
FFE 629.75

BLDG 14
FFE 622.60

BLDG 15
FFE 621.90

BLDG 16
FFE 620.80

BLDG 17
FFE 621.50

BLDG 3
FFE 630.90

BLDG 4
FFE 632.75

Clubhouse

BLDG 7
FFE 626.50

BLDG 6
FFE 629.60

BLDG 2
FFE 633.00

BLDG 5
FFE 633.00

FINAL FOR DEVELOPMENT
DEC 09 2021

Grading Plan
Scale: 1" = 30'

TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service and shall remain property of Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT MJL
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Grading Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C6.1

TOWN MADISON

LIME QUARRY ROAD

Sidewalk part of Villas Project

Req'd Sidewalk of this project

1% Annual Chance Floodplain Boundary

Excavation Area

BLDG 1
FFE 630.00

BLDG 8
FFE 627.80

BLDG 9
FFE 627.90

BLDG 10
FFE 628.40

BLDG 11
FFE 628.30

BLDG 12
FFE 629.00

BLDG 13
FFE 629.75

Ex. SPHW
Ex. INV OUT 617.98±

Ex. SWSI
Ex. INV IN (E) 623.29±
Ex. INV (S) 619.39±
Ex. INV OUT 619.39±

Ex. SPHW
Ex. INV OUT 624.50±

Ex. SWSI
Ex. INV IN 624.00±
Ex. INV OUT 623.90±

Ex. JB
Ex. RIM
Ex. INV I
Ex. INV

S 88°08'48" E
469.03'

FINAL FOR DEVELOPMENT
12 8 9 2021

Grading Plan
Scale: 1" = 30'

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER JOHN L. MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Grading Plan

Job No: 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER

C6.2

Erosion Control Phasing:

THIS CONSTRUCTION SEQUENCE IS BASED ON THE ENGINEER'S OPINION AND NOT INTENDED TO BE A COMPREHENSIVE LIST OF EVENTS. THE CONTRACTOR SHOULD USE HIS/HER DISCRETION TO DETERMINE THE BEST SEQUENCE OF CONSTRUCTION. IN ADDITION, ALL EROSION AND SEDIMENTATION CONTROL MEASURES MUST BE INSTALLED PRIOR TO SELECT WORK ITEMS OR AT THE POINT OF COMPLETION OF EACH WORK ITEM, DEPENDING ON THE NATURE OF THE ITEM. EXAMPLE: SEDIMENT CONTROL PRIOR TO GRADING AND INLET PROTECTION UPON COMPLETION OF INLET CONSTRUCTION.

PHASE 1 - PRE CONSTRUCTION

1. INSTALL SILT FENCE AND CONSTRUCTION ENTRANCE AS SHOWN AND OTHER AREAS TO PREVENT SEDIMENT FROM BEING WASHED ON TO ADJOINING PROPERLY.

PHASE 2 - DEMOLITION, SITE PREPARATION AND GRADING

1. PROTECT EXISTING VEGETATION BUFFER ALONG EXISTING PROPERTY BOUNDARY.
2. INSTALL SILT FENCE AS SHOWN AND OTHER AREAS TO PREVENT SEDIMENT FROM BEING WASHED FROM THE SITE.
3. INSTALL WATTLE CHECK DAMS IN DITCHES & CONCENTRATED DRAINAGE WAYS TO PREVENT SEDIMENT FROM BEING WASHED DOWNSTREAM.
4. PERFORM SITE PREPARATION, DEMOLITION, AND CLEAR AND GRUB THE SITE.
5. INSTALL UTILITIES AND UNDERGROUND-RELATED IMPROVEMENTS.
6. GRADING ACCORDING TO THE GRADING PLAN; INSTALL FILTER AT DRAINAGE FLUMES AND LEAVE EXISTING DRAINAGE WAYS IN PLACE.

PHASE 3

1. BEGIN FOUNDATION CONSTRUCTION AND OTHER BUILDING PREPARATIONS.
2. MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES, SUCH THAT THEY ARE PERFORMING THEIR FUNCTION PROPERLY, CLEAN OUT, SEDIMENT BUILD-UP WHEN FACILITIES REACH 50% CAPACITY, MAKE SURE THAT ADEQUATE DRAINAGE IS PROVIDED TO REDUCE RUNOFF ONTO EXISTING ROADS.
3. COMPLETE THE PLACEMENT OF AGGREGATE BASE TO MEET GRADE AND COMPACTION REQUIREMENTS, & COMPACTION TEST AFTER PASSING INSPECTION, THEN START ASPHALT PAVING.
4. INSTALL SIDEWALKS AND RELATED SITE IMPROVEMENTS.
5. CONTRACTOR SHOULD BLOW SEED AND STRAW ON ALL DISTURBED AREAS IN ORDER TO REDUCE EROSION. BARE GROUND AREAS SHOULD BE MINIMIZED DURING CONSTRUCTION.
6. CONTRACTOR SHOULD BE AWARE THAT EROSION MAY OCCUR IN AREAS THAT ARE UNPROTECTED ON THE CONSTRUCTION SITE. IF THE CONTRACTOR OBSERVES SEDIMENT ACCUMULATION OR EROSION PROBLEMS ON SITE, THEN THE CONTRACTOR MUST CONSULT WITH THE QCP TO DETERMINE THE NECESSARY MEASURES TO STOP SEDIMENTATION, SUCH AS SILT FENCES, WATTLE CHECK DAMS, ETC., AND THEN TAKE THE NECESSARY MEASURES TO STOP THE EROSION, SUCH AS SEED/MULCH, SOD, EROSION BLANKETS, ETC. AS DIRECTED BY THE QCP.


PHASE 4


1. SOLID SOD WILL BE UTILIZED IN ALL DISTURBED AREAS TO EXPEDITE VEGETATIVE COVER ON THE AREAS DISTURBED BY CONSTRUCTION. THE VEGETATIVE COVER WILL PREVENT LONG TERM EROSION OF THE SITE.
2. PERMANENT SEEDING WILL BE UTILIZED IN ANY OTHER DISTRUBED AREAS THAT DO NOT RECEIVE SOLID SOD. THE PERMANENT SEEDING WILL BE MAINTAINED AND WILL PREVENT SOIL EROSION.
3. FINAL STABILIZATION OF DISTURBED AREAS MUST, AT A MINIMUM, BE INITIATED IMMEDIATELY WHENEVER ANY CLEARING, GRADING, EXCAVATING OR OTHER EARTH DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED ON ANY PORTION OF THE SITE. TEMPORARY, STABILIZATION OF DISTRUBED AREAS MUST BE INITIATED IMMEDIATELY WHENEVER WORK TOWARD PROJECT COMPLETION AND FINAL STABILIZATION OF ANY PRTION OF THE SITE HAS TEMPORARILY CEASED ON ANY PORTION OF THE SITE AND WILL NOT RESUME FOR A PERIOD EXCEEDING THIRTEEN (13) DAYS.
4. RIP RAP - NO STEEP DISTURBED SLOPES ARE ANTICIPATED BUT IF UNEXPECTED CONSTRUCITON ISSUES CREATE STEEPER DISTURB SLOPES, THEY WILL BE STABILIZED WITH RIP RAP TO PROTECT SOIL ON THE SLOPES FROM EROSION. THE RIP RAP WILL PROTECT THE SOIL FROM EROSION DUE TO CONCENTRATED RUNOFF. IT WILL BE USED TO STABILIZE SLOPES THAT ARE UNSTABLE DUE TO SEEPAGE. IT IS ALSO USED TO SLOW THE VELOCITY OF CONCENTRATED RUNOFF WHICH IN TURN INCREASES THE POTENTIAL FOR INFILTRATION.
5. STORM WATER DETENTION BASIN MUST BE MAINTAINED AFTER CONSTRUCTION AND REGULAR USAGE, REPLANT REES, GRASS, SHRUBS OR VINES WHERE NEEDED TO MAINTAIN ADEQUATE COVER FOR EROSION CONTROL MAINTAIN GRASS PLANTINGS WITH PERIODIC APPLICATIONS OF FERTILIZER AND MOWING. THE CITY OF MADISON ALSO REQUIRES THAT THESE DETENTION PONDS RETAIN THE 1.14 INCH, 24 HOUR STORM TO MIMIC THE PRE-DEVELOPMENT CONDITIONS OF PEAK DISCHARGE RATE AND DISCHARGE VOLUME. THIS WILL RETAIN AND SLOW DISCHARGE TO ALLOW SETTLEMENT, OR FILTERING, OF SEDIMENT AND DEBRIS PRIOR TO DISCHARGE INTO THE ADJACENT EXISTING GRASS DRAINAGE DITCH.

GRASS SWALES MUST BE MAINTAINED: INSPECT THE CHANNEL FOLLOWING STORM EVENTS BOTH DURING AND AFTER GRASS COVER IS ESTABLISHED; MAKE NEEDED REPAIRS IMMEDIATELY. ALSO, CHECK THE CHANNEL OUTLET AND ROAD CROSSING FOR BLOCKAGE, PONDING, SEDIMENT, AND BANK INSTABILITY, BREAKS AND ERODED AREAS; REMOVE ANY BLOCKAGE, AND MAKE REPAIRS IMMEDIATELY TO.


Erosion Control Notes:

1. EROSION CONTROL SHALL BE MAINTAINED AT ALL TIMES AND SHALL BE IN ACCORDANCE WITH ALABAMA'S BEST MANAGEMENT PRACTICES.
2. SILT FENCE SHALL BE PLACED IN ACCORDANCE WITH THE CITY OF MADISON STORMWATER MANAGEMENT MANUAL.
3. SILT FENCE IS REQUIRED WHERE NECESSARY TO PREVENT EROSION AND WASHING OF TOPSOIL INTO EXISTING WATERWAYS AND DRAINAGE DITCHES UNTIL TIME AS GRASS HAS BEEN FINALLY ESTABLISHED.
4. EROSION CONTROL IS REQUIRED AROUND INSTALLED STORM DRAINAGE INLETS AND BOXES AS SHOWN HEREON, UNTIL SUCH TIME AS GRASS HAS BEEN FIRMLY ESTABLISHED TO PREVENT TOPSOIL EROSION FROM WASHING INTO SAID INLETS.
5. 20" WATTLES SHALL BE USED AS TEMPORARY CHECK DAMS IN NEW AND EXISTING DRAINAGE DITCHES UNTIL SUCH TIME AS GRASS HAS BEEN FIRMLY ESTABLISHED TO PREVENT DITCHES FROM WASHING OUT.
6. AN ENTRANCE CONSTRUCTION PAD SHALL BE BUILT AT ALL EXITS FROM THIS CONSTRUCTION AREA TO EXISTING TRAVELED ROADWAYS IN ACCORDANCE WITH THE DETAILS SHOWN ON THESE PLANS.
7. THE CONTRACTOR IS REQUIRED TO SEED GRASS OR OTHERWISE STABILIZE ALL DISTURBED AREAS AS SHOWN AS SOON AS CONSTRUCTION HAS BEEN COMPLETED IN THE IMMEDIATE AREA.
8. THE CONTRACTOR IS REQUIRED TO INSURE THAT ALL RUNOFF FROM THE CONSTRUCTION SITE ONTO EXISTING AREAS HAVE BEEN ADEQUATELY TREATED BY THE USE OF EROSION CONTROL METHODS AS SHOWN HEREON.
9. ALL REAR YARD DITCHES MUST BE FULLY SODDED.
10. ALL R.O.W. MUST HAVE FULL STAND OF GRASS PRIOR TO FINAL INSPECTION.
11. ALL GRADED SLOPES SHALL BE GRADED TO A MAXIMUM SLOPE OF 4%.






SILT FENCE
NOT to Scale



Gravel Construction Entrance
NOT to Scale



Erosion Control Plan
Scale: 1" = 50'

FINAL FOR DEVELOPMENT
DEC 09 2021

TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service for use solely with respect to Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT RICHARD SCOTT MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Erosion Control Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER
C7

TOWN MADISON

LIME QUARRY ROAD

Villas Project

Req'd Sidewalk of this project

Ex. SPHW
Ex. INV OUT 617.98±

Ex. SWSI
Ex. INV IN (E) 623.29±
Ex. INV (S) 619.39±
Ex. INV OUT 619.39±

Ex. SPHW
Ex. INV OUT 624.50±

Ex. JB
Ex. RIM 634.21±
Ex. INV IN 625.4
Ex. INV OUT 62(

Ex. SWSI
Ex. INV IN 624.00±
Ex. INV OUT 623.90±

Ex. JB
Ex. RIM 634.24±
Ex. INV IN 625.96±
Ex. INV OUT 625.86±

S 88°08'48" E
92.08'

S 51°19'05" E
69.05'

1% Annual Chance Floodplain Boundary

N 49°01'17" E
186.22'
FLOODWAY

Excavation Area

BLDG 1
FFE 630.00

BLDG 8
FFE 627.80

BLDG 9
FFE 627.90

BLDG 10
FFE 628.40

BLDG 11
FFE 628.30

BLDG 12
FFE 629.00

BLDG 13
FFE 629.75

Ex. JB
Ex. INV IN (S)629.13±
Ex. INV IN (N) 628.63±
Ex. INV IN (E) 627.24±
Ex. INV OUT 627.14±

Ex. DWSI
Ex. INV IN 629.35±
Ex. INV OUT 629.25±

Ex. SWSI
Ex. INV OUT 630.80±

N 30°58'52" E
209.57'

1% Annual Chance Floodplain Boundary

Excavation Area

FLOODWAY BOUNDARY

60' U & D EASEMENT

N 22°35'21" E 321.00'

S 10°24'36" W 162.85'

S 16°40'35" W 324.42'

Excavation Area

BLDG 2
FFE 633.00

LOT 4

BLDG 3
FFE 630.90

LOT 2

BLDG 4
FFE 632.75

Clubhouse

DUNLOP BOULEVARD

S 00°01'47" E 674.80'

Ex. SWSI
Ex. INV OUT 630.45±

Ex. SWSI
Ex. INV IN 630.14±
Ex. INV OUT 630.04±

Ex. SWSI
Ex. INV IN 628.57±
Ex. INV OUT 628.07±

Ex. SWSI
Ex. INV IN 628.98±
Ex. INV OUT 628.88±

Ex. SPHW
Ex. INV OUT 629.59±

BLDG 14
FFE 622.60

BLDG 15
FFE 621.90

BLDG 16
FFE 620.80

BLDG 17
FFE 621.50

BLDG 7
FFE 626.50

BLDG 6
FFE 629.60

BLDG 5
FFE 633.00

FLOODWAY

N 12°42'28" W 230.61'
N 19°26'59" E 295.58'

S 89°58'59" W 961.65'

FINAL FOR DEVELOPMENT
DEC 09 2021

Fire Truck Plan
Scale: 1" = 50'

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED LANDSCAPE ARCHITECT
RICHARD SCOTT MULLINS
November 16, 2021

The Roberts Apartments at TM

Madison, AL


PREPARED FOR: ---

Fire Truck Access Plan

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS


SHEET NUMBER

C8




1 - 8" - 30" SOLID COVERS SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
2 - 12" - 30" FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05. 8" & 10" SOLID COVERS FIT DIRECTLY ONTO DRAIN BASINS WITH THE USE OF A PVC BODY TOP. SEE DRAWING NO. 7001-110-045.
3 - DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS. RISERS ARE NEEDED FOR BASINS OVER 84" DUE TO SHIPPING RESTRICTIONS. SEE DRAWING NO. 7001-110-065.
4 - DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 FOR CORRUGATED HDPE (ADS N-12/HANCOR DUAL WALL), N-12 HP, & PVC SEWER (4" - 24").
5 - ADAPTERS CAN BE MOUNTED ON ANY ANGLE 0° TO 360°. TO DETERMINE MINIMUM ANGLE BETWEEN ADAPTERS SEE DRAWING NO. 7001-110-012.
6 - 12" - 30" SOLID COVERS SHALL MEET H-20 LOAD RATING.
7 - 8" & 10" SOLID COVERS ARE RATED FOR LIGHT DUTY APPLICATIONS ONLY; NO CONCRETE COLLAR NEEDED FOR LIGHT DUTY RATING.

Nyloplast Junction-Box
NOT to Scale




Fully Mountable Curb & Channel
NOT to Scale




Concrete Integral Curb
NOT to Scale

TOP 6" OF SUBGRADE SHALL BE COMPACTED TO 100% PROCTOR DENSITY, BELOW 6" IS TO BE COMPACTED TO 95% PROCTOR DENSITY AS DETERMINED BY AASHTO T-99 COMPACTION TEST. SEE SPECIFICATIONS. FOR ADDITIONAL INFORMATION.




1. 112 LBS./S.Y. (1") HOT BITUMINOUS CONCRETE WEARING COURSE, ALDOT REF. 424-A, MIX 2 (SLUICEOUS AGGREGATE)
2. 224 LBS./S.Y. (2") HOT BITUMINOUS CONCRETE BINDER COURSE, ALDOT REF. 414, MIX 1 OF SPECS.
3. 0.10 GAL./S.Y. EMULSIFIED ASPHALT OR 0.07 GAL./S.Y. TACK COAT. ALL MATERIALS ARE TO BE IN ACCORDANCE WITH SEC. 405 OF THE AL. DOT SPECIFICATIONS.
4. 1" LAYER OF DENSE GRADED LIMESTONE BASE COURSE. AL. DOT REF. 301 OF SPECS. ALL MATERIALS SHALL BE IN ACCORDANCE WITH SEC. 825, TYPE "B", COMPACTION TO 100% LVD.


Asphalt Paving Section
NOT to Scale




Clean-out
NOT to Scale



Arcat U-Rack "Braced' 2-Bike Rack Module
NOT to Scale





TRAFFIC AREAS




NON-TRAFFIC AREAS

Storm Pipe Bedding
NOT to Scale







Concrete Sloped Paved Headwall
NOT to Scale



Concrete Paving
NOT to Scale






SECTIONAL VIEW

NOTES


1. All concrete shall be class "A" and shall develop a minimum compressive strength of 3000 PSI in 28 days.
2. Reinforcing shall be grade 60 deformed bars and shall conform to ASTM requirements.
3. Steps are required on all Junction Boxes when dimensions from bottom of top slab to top of bottom slab is greater than 4'-0".

Junction Box for 15" to 24" Pipes
NOT to Scale




SECTIONAL VIEW

Inlet Box for 15" to 24" Pipes
NOT to Scale



Concrete Ribbon
NOT to Scale



NOTES: – EXPANSION JOINTS REQUIRED AT 75' INTERVALS
– CONSTRUCTION JOINTS REQUIRED AT 25' INTERVALS
– 3000 p.s.i. CONCRETE

Concrete Curb & Gutter
NOT to Scale

FINAL FOR DEVELOPMENT
DEC 09 2021

TOWN MADISON

REVISIONS
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service and shall remain the property of Firms listed on face, and shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER JOHN L. MULLINS 24918
November 16, 2021


The Roberts Apartments at TM
Madison, AL
PREPARED FOR: ---

Civil Details


Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER
C9.1


TOWN MADISON



UTILITY CROSSING DETAILS
NOT TO SCALE




FLEXIBLE PIPE-TO-MANHOLE CONNECTOR DETAIL
NOT TO SCALE




TYPICAL SECTION
STANDARD SANITARY SEWER MANHOLE DETAIL
NOT TO SCALE

(BASE SECTION FOR 8" – 24" PIPE SHOWN. LARGER PIPES MOVEMBER REQUIRE LARGER MANHOLE. CONSULT MANHOLE MANUFACTURER FOR DETAILS)




(OPTION NO. 1)
BEDDING AND BACKFILL REQUIREMENTS AROUND MANHOLES AND OTHER DRAINAGE & SANITARY SEWER STRUCTURES WITHIN TRAFFIC AREAS
NOT TO SCALE

NOTE:
1. TRAFFIC AREAS SHALL EXTEND TO 5 FT BEYOND BACK OF CURB OR EDGE OF PAVEMENT, UNLESS OTHERWISE NOTED ON PLAN VIEW.
2. ASPHALT PAVING FOR STREETS SHALL MEET CURRENT CITY REQUIREMENTS.




MANHOLE PLAN

MANHOLE INVERT DETAIL
NOT TO SCALE



NOTES:
1. ALL PVC SERVICE LATERALS SHALL HAVE A CONTINUOUS STRIP OF METAL TRACER TAPE INSTALLED 2' - 3' BELOW FINISH GRADE FROM CENTERLINE OF SANITARY SEWER TO ROW/EASEMENT.
2. CURB MARKERS SHALL BE PROVIDED FOR SERVICE LATERALS. REFER TO SECTION 5 - DESIGN CRITERIA FOR SERVICE LATERALS.

SERVICE CONNECTION FOR DEEP SEWER (MORE THAN 6')
NOT TO SCALE



NOTES:
1. ALL PVC SERVICE LATERALS SHALL HAVE A CONTINUOUS STRIP OF METAL TRACER TAPE INSTALLED 2' - 3' BELOW FINISH GRADE FROM CENTERLINE OF SANITARY SEWER TO ROW/EASEMENT.
2. CURB MARKERS SHALL BE PROVIDED FOR SERVICE LATERALS. REFER TO SECTION 5 - DESIGN CRITERIA FOR SERVICE LATERALS.

SERVICE CONNECTION FOR SHALLOW SEWER (6' OR LESS)
NOT TO SCALE

FINAL FOR DEVELOPMENT
DEC 09 2021

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project and Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

ALABAMA REGISTERED PROFESSIONAL ENGINEER JAMES L. MULLINS
November 16, 2021

The Roberts Apartments at TM
Madison, AL

PREPARED FOR: ---

Civil Details

Job No. 21-128
Date: 2021 11-16
Drawn By: JLH
Checked By: RS

SHEET NUMBER
C9.2

Irrigation Requirements:

1. Piping
   - 1.1. All irrigation main lines shall be SCH 40 PVC, sized as shown, and shall be buried a min. of 30" below finish grade and installed in trenches with proper identifying tape for in-field location.
   - 1.2. All irrigation laterals shall be Class 200 PVC and shall be buried a min. of 18" below finish grade.
   - 1.3. Funny pipe may be used for connection of spray head bodies or dripline to irrigation mains, however, individual funny pipe runs shall not exceed 6'.
   - 1.4. In all instances where irrigation piping crosses hardscape, irrigation piping shall be installed in a SCH 40 PVC sleeve sized a min. of 2 sizes larger than the largest pipe crossing hardscape.
   - 1.5. Common trenches may be used for main and lateral piping and wiring.
2. Valves
   - 2.1. System shall have a master valve as part of the controlled irrigation system in location as indicated on Landscape Plan.
   - 2.2. Master Valve shall be pressure-regulated such that output pressure is ~100 psi.
   - 2.3. All valves for this system shall be RainBird PESB model with PRS-D pressure regulation module, sized as appropriate for the individual zone for lateral lines or to match the main line for the master valve.
   - 2.4. System shall be zoned to such that beds and turf areas are not irrigated together, with proximate, similar areas zoned together to minimize zone/valve count, within reason. Zoning/valving shall be included in submitted design for approval by Landscape Architect, prior to beginning installation.
   - 2.5. All valves shall be fitted with RainBird decoders for communication with two-wire based controller system.
   - 2.6. All valves shall be installed in RainBird PVB standard or jumbo valve boxes, installed per manufacturer's details, specs, & requirements.
3. Landscape Bed Irrigation
   - 3.1. Landscape Bed zone valves shall be pressure-regulated such that dripline operates at ~40 psi.
   - 3.2. Landscape beds shall be irrigated by dripline tubing, RainBird model XFS. Dripline tubing may be installed at finish grade, below mulch, or just below finish grade.
   - 3.3. Shrubs and trees shall, at minimum, have 1 row of dripline along 2 sides of the plants, located generally above the rootball of the plant, as well as 1 row of dripline along 2 sides of the plants, located 1' outside the rootball for shrubs and 3' outside the rootball for trees.
4. Sod Area Irrigation
   - 4.1. Sod zone valves shall be pressure-regulated such that heads operate at ~40 psi.
   - 4.2. Sod areas shall be irrigated by spray nozzle, with pressure-regulating spray body. Spray bodies shall be Hunter Pro-Spray model PRS40 with MP Rotator spray nozzles.
   - 4.3. Nozzle selection shall be appropriate for throw radius and area shape.
   - 4.4. All spray heads shall be trained to minimize overspray onto all hardscape areas, buildings, fences, furnishings, etc.
5. Quick Couplers
   - 5.1. Contractor shall install a 1" RainBird quick coupler at each location indicated on Landscape Plan.
   - 5.2. Quick Couplers shall be piped off of Irrigation Mains.
   - 5.3. Quick Coupler shall be installed in RainBird PVB standard valve box, per manufacturer's details, specs, & requirements.
6. Controller
   - 6.1. Irrigation controller for this system shall be RainBird ESP-LXD two-wire decoder controller. Location as shown on Landscape Plan.
   - 6.2. Controller shall be mounted in appropriate RainBird stainless steel pedestal, per manufacturer's requirements and specifications.
   - 6.3. Contractor shall coordinate with Owner for any communication tie-in to Owner's overall property infrastructure management system.
7. Wiring & Grounding
   - 7.1. All valves shall be connected to the controller by two-wire product which meets or exceeds minimum requirements of controller manufacturer, using DBY connectors installed in gel-filled housing.
   - 7.2. Grounding, lightning arrestors, and other related fixtures shall be installed per controller manufacturer's details, specs, & requirements. Should the controller manufacturer require certification of grounding measures installation, contractor shall arrange for such inspection and make adjustments as required for certification. Landscape Architect shall be included in all correspondence and inspections.

Landscape/Irrigation Inspections:

1. Contractor shall coordinate with Landscape Architect at tree delivery for inspection by Landscape Architect and approval prior to unloading.
2. Contractor shall stake, identify, and/or prepare the following for approval by Landscape Architect prior to installation:
   - 2.1. Finish Grade
   - 2.2. Tree Locations
   - 2.3. Bed Lines
   - 2.4. Landscape Irrigation Main Line
   - 2.5. All Valve Boxes
   - 2.6. Quick Couplers
   - 2.7. Landscape Irrigation Controller

NOTE: Any plant materials that are damaged (by transport, handling, installation, or other construction activities) are rejected and shall be replaced at no cost or delay to the Owner.

Landscape Installation Notes:

1. All existing trees outside of the limits of work for this project shall be protected during the construction and installation of these improvements and are not to be damaged in any manner. Any damage to such shall be brought to the attention of the Landscape Architect immediately for determination of appropriate corrective measures, if any. Contractor shall execute said corrective measures at no additional cost to the Owner.
2. All areas to receive landscape plantings (trees, shrubs, sod, etc.) shall be backfilled with min. 12" of topsoil (from nearby stripped topsoil stockpiles) prior to plant material installation or mulching. Placed topsoil shall be worked to remove and/or break-up any large clumps of soil and shall be fine-graded in all areas for a smooth, consistent finish product. Any debris or deleterious materials within the 12" profile of landscape areas shall be removed prior to placing any topsoil Any debris, large roots, rocks, etc. shall be removed from the topsoil prior to finish-grading efforts.
3. Contractor shall stake tree locations and layout bed lines for approval by Landscape Architect prior to installation. Adjust staked locations and bed lines as directed.
4. All landscape materials are subject to approval of the Owner or Landscape Architect at any time during the job, up until point of acceptance.
5. All plants shall meet standards set forth by the American Standards for Nursery Stock.
6. Provide No. 1 grade or better nursery grown stock grown in an approved, recognized nursery in accordance with requirements of applicable standards as noted herein. Provide only healthy, vigorous, stock free of disease, insects, injuries, abrasions crown die-back or disfigurements.
7. All trees shall have a single, straight leader (co-dominate leaders are unacceptable) unless otherwise noted. Trees with narrow crotches of included bark, split bark with inrolled callus, dead, broken, or flush-cut branches will not be accepted. Rootballs shall be firm, neat, slightly tapered and well burlapped. Trees with loose or broken rootballs at time of planting shall be rejected. All trees indicated as B&B/WB in plant schedule shall be balled and burlapped and set in wire basket at time of digging at nursery.
8. Plant material transported in open vehicles / trailers is damaged and subject to rejection.
9. Any rejected plants shall be removed from the site and replaced by acceptable plants meeting drawings notes & specifications at no additional cost to the owner.
10. All plant material, upon delivery to site shall be immediately planted in prepared and prior-approved beds and pits. If contractor is unable to plant within 2 hours of plant delivery to site, plants shall be heeled in, the roots kept moist, and plants otherwise protected and maintained until installation at no cost to the owner.
11. All plant material shall be handled by the container or rootball and not by the top growth.
12. Plants injured on job site are not acceptable and shall be replaced by contractor at no additional cost to the owner.
13. All plant material shall be warranted by Landscape Contractor for a period of one year after final acceptance. Dead or declining plant material shall be rejected and shall be replaced by Landscape Contractor at no cost to the owner. It is the Contractor's responsibility to contact the Owner at the end of the warranty period. If the Contractor fails to notify and meet with the Owner, the warranty period shall continue until the meeting is held, dead or declining plant material is replaced, and the project is accepted by the Owner.
14. Trees shall be staked with ArborTie product, min. three (3) per tree, per manufacturer's requirements and recommendations. Tree staking shall be removed from established plants at the end of the warranty period.
15. Mulch for trees and shrub beds shall be pine straw, installed to 3" settled thickness. Mulch shall extend min. 4' around trees.
16. All trees shall be purchased from the following supplier list, all subject to approval & pre-selection by Owner and/or Landscape Architect:

Hunter Trees	Alpine, AL	(866) 348-6837
Select Trees	Bishop, GA	(706) 743-5124
Bold Spring Nursery	Hawkinsville, GA	(478) 783-4975

17. Finish grade shall be approved by Landscape Architect and Owner's representative. All weeds shall be sprayed and removed prior to planting, seeding, and/or sodding.
18. All disturbed areas within the project's property and associated ROW shall be fully treated by either:
    - 18.1. Solid sod shall be planted with Tifton Bermuda over raked and fine-graded finish grade. Full, consistent stand of turf shall be established in all areas designated, prior to landscape acceptance.
    - 18.2. Landscape Bed area, mulched per notes.
19. Ex. turf areas shall be protected as much as is practicable. Any turf areas damaged as part of this work shall be repaired/replaced to match surrounding at no cost to the owner.
20. Contractor shall arrange for landscape inspection with Landscape Architect upon completion of installation for final acceptance.

Landscape Design Notes:

Plantings shown on this plan are required as part of the City of Madison's Zoning Ordinance. The plantings shall be installed prior to project Certificate of Occupancy.

This project is expected to have a full landscape design and implementation which will be handled by contractor direction and/or Supplemental Landscape Plan. Such plantings are not required by the Municipality and are, therefore, not subject to review/approval by such and are not included herein.

Contractor is to coordinate with Owner/Engineer/Landscape Architect to include such plantings in any pricing/bids put forth on this project.

Grand Avenue Site Furnishings:

The following are required at each location indicated:

1. 4' x 12' x 4" thk Conc. Pad
2. Bench -- "Harpo" as manufactured by LandscapeForms 69" length with aluminum slats
3. Litter Receptacle -- "Poe" as manufactured by LandscapeForms

Both bench and receptacle shall be installed per manufacturer's requirements and recommendations, mounted to concrete pad.

Plant List

Key	Scientific name	Common Name	Min. Size	Condition	Notes
Trees					
ARB	*Acer rubrum 'Brandywine'*	Brandywine Red Maple	3.5" Caliper	B&B / WB	Full & Matched
LSF	*Lagerstroemia x 'Sarah's Favorite'*	Sarah's Favorite Crape Myrtle	12' Height	B&B / WB	3- or 5-cane Only, Full & Matched
MVG	*Magnolia virginiana 'Australis'*	Australs Bay Magnolia	3.5" Caliper	B&B / WB	3- or 5-cane Only, Full & Matched
QLR	*Quercus lyrata 'QLR5D' P.P.A.F.*	Resilience Overcup Oak	3.5" Caliper	B&B / WB	Full & Matched
QTN	*Quercus nuttallii 'QNSTD' P.P. #16,254*	Sangria Nuttall Oak	3.5" Caliper	B&B / WB	Full & Matched
UAP	*Ulmus americana 'Princeton'*	Princeton American Elm	3.5" Caliper	B&B / WB	Full & Matched
Shrubs					
JGC	*Juniperus x pfitzeriana 'Aurea Improved'*	Gold Coast Juniper	5 Gal. and 18" hgt.	Container	Full & Matched
LES	*Loropetalum chinense 'Shang-white'*	Emerald Snow Loropetalum	5 Gal. and 18" hgt.	Container	Full & Matched
LRD	*Loropetalum chinense 'Shang-Red'*	Red Diamond Loropetalum	7 Gal. and 36" hgt.	Container	Full & Matched
TGZ	*Cleyera japonica 'Conthery'*	Bronze Beauty Cleyera	7 Gal. and 36" hgt.	Container	Full & Matched
Decorative Grasses					
CSL	*Cortaderia selloana*	Selloa Pampasgrass	5 Gal. and 30" hgt.	Container	Full & Matched
MSA	*Miscanthus sinensis 'Adagio'*	Adagio Fountain Grass	5 Gal. and 24" hgt.	Container	Full & Matched
MCL	*Muhlenbergia capillaris 'Lenca'*	Royal Mist Pink Muhly Grass	3 Gal. and 18" hgt.	Container	Full & Matched
MLL	*Muhlenbergia lindheimeri 'Lein'*	Autumn Glow Muhly Grass	3 Gal. and 18" hgt.	Container	Full & Matched



STATE OF ALABAMA
HARRY MATHIS SNEED
NUMBER 690
PROFESSIONAL LANDSCAPE ARCHITECT
Nov 17, 2021

Req'd PVA Landscape Calculations:

Grand Avenue			
	Total Length	733 LF	
	Req'd Trees	9	(1 tree / 50 LF)
	Provided Trees	9	
Perimeter			
	Total Length	979 LF	
	Req'd Trees	20	(1 tree / 50 LF)
	Req'd Shrubs	120	(6 shrubs / 50 LF)
	Provided Trees	20	
	Provided Shrubs	120	
Interior			
	Req'd LS Area	8,352 sf	(464 spaces x 18 sf)
	Req'd Trees	42	(1 tree / 200 sf)
	Req'd Shrubs	168	(4 shrubs / 200 sf)
	Provided LS Area	8,500+ sf	
	Provided Trees	42	
	Provided Shrubs	172	

FINAL FOR DEVELOPMENT
DEC 09 2021

REVISIONS
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---
Date: ---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect to the Project. Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 303, Huntsville, AL 35805
(256) 690-5312

The Roberts Apartments at Town Madison

Madison, AL

PREPARED FOR: Rohdie Group

PVA Landscape Plan


Job No. 21-128
Date: 2021 11/17
Drawn By: HMS
Checked By: HMS

SHEET NUMBER
L1

LIGHTING NOTES

1. VERIFY EXACT LOCATIONS WITH OWNER'S REPRESENATIVE BEFORE ROUGHING IN.
2. CONTRACTOR SHALL CHECK ALL LIGHTING FIXTURES FOR EXACT MOUNTING TYPE AND SPACE REQUIRED BEFORE ROUGHING IN.
3. ELECTRICAL CONTRACTOR SHALL WORK CLOSELY WITH THE OWNER'S REPRESENTATIVE, TO VERIFY EXACT TYPE OF EQUIPMENT TO BE INSTALLED, AND THE DIMENSIONS WHICH MAY EFFECT THE EXACT PLACEMENT OF ELECTRICAL WORK.
4. FURNISH AND INSTALL LAMPS AS WITH FIXTURES.
5. ALL WORK SHALL BE IN COMPLIANCE WITH NFPA 70, AND THE CITY OF MADISON LIGHTING ORDINANCE REQUIREMENTS.





NOTE:
FACTORY SUPPLIED TEMPLATE MUST BE USED WHEN SETTING ANCHOR BOLTS.

2 PL PL TYPICAL POLE BASE DETAIL
NOT TO SCALE

LUMINAIRE SCHEDULE

Symbol	Label	Qty	Lum. Watts	Lum. Lumens	LLF	Arrangement	Description
▭ ▫	A	8	147	22020	0.95	SINGLE	RSX2-LED-P3-40K-R4-MVOLT-SPA-DDBXD Mounted on 25' Sq Steel Pole
▨ ▫	B	3	244	31073	0.95	SINGLE	RSX2-LED-P6-40K-R5-MVOLT-SPA-DDBXD Mounted on 25' Sq Steel Pole
▭▪▭	C	10	374	25667	0.95	SINGLE	RSX2-LED-P4-40K-R5-MVOLT-SPA-DDBXD Mounted on 25' Sq Steel Pole
▭▫	D	2	312	41525	0.95	SINGLE	RSX3-LED-P4-40K-R5-MVOLT-SPA-DDBXD Mounted on 25' Sq Steel Pole

CALCULATION SUMMARY

Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Parking and Driveways	Illuminance	Fc	2.5	6.1	0.8	3.1:1	7.6:1
Spillover	Illuminance	Fc	0.1	0.9	0.0	N.A.	N.A.

FINAL FOR DEVELOPMENT
DEC 09 2021

GRAPHIC SCALE: 1"=50'-0" (50' 0 50')

Sept 20, 2021 - 05:39:57

REVISIONS	BY

PROJECT TITLE:
ROBERTS APARTMENTS
INTER DUNLOP BLVD/LIME QUARRY
MADISON, ALABAMA


SHEET TITLE:
PARKING LOT LIGHTING PLAN, NOTES AND LEGEND

STAMP:
ALABAMA REGISTERED
NO. 11457
PROFESSIONAL ENGINEER
JAMES A. STOCKTON
9-20-2021

ASSOCIATED ENGINEERING SERVICES
HUNTSVILLE, ALABAMA

DATE SEP 2021
SCALE 1"=50'-0"
DRAWN N.A. Snow
JOB P-21135
SHEET PL-1
OF --- SHEETS

P135-PL1



TOWN MADISON

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face, are instruments of service in respect of which said Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

The Roberts Apartments at TM

Madison, AL

PREPARED FOR: ---

Pre Development Drainage Map

Job No.	19-177
Date:	2021 9-21
Drawn By:	JLH
Checked By:	RS

SHEET NUMBER

D1

TOWN MADISON

LIME QUARRY ROAD

Villas Project

Req'd Sidewalk of this project

1% Annual Chance Floodplain Boundary

FLOODWAY

Excavation Area

EXISTING UTILITY & DRAINAGE EASEMENT

60' U & D EASEMENT

15' UTILITY EASEMENT

GRESS EASEMENT PG. 1027

EXISTING GAS EASEMENT D.B. 552 PG. 999-1000

DUNLOP BOULEVARD

LOT 2

LOT 4

BLDG 1 FFE 630.00

BLDG 2 FFE 633.00

BLDG 3 FFE 630.90

BLDG 4 FFE 632.75

BLDG 5 FFE 633.00

BLDG 6 FFE 627.80

BLDG 7 FFE 626.50

BLDG 8 FFE 627.90

BLDG 9 FFE 627.80

BLDG 10 FFE 629.00

BLDG 11 FFE 629.00

BLDG 12 FFE 629.00

BLDG 13 FFE 629.75

BLDG 14 FFE 629.60

BLDG 15 FFE 621.90

BLDG 16 FFE 620.80

Clubhouse FFE 631.00

Special Flood Hazard Area (SFHA) Zone AE

Ex. SPHW Ex. INV OUT 617.98±

Ex. SWSI Ex. INV IN (E) 623.29± Ex. INV (S) 619.39± Ex. INV OUT 619.39±

Ex. SPHW Ex. INV OUT 624.50±

Ex. SWSI Ex. INV IN 624.00± Ex. INV OUT 623.90±

Ex. JB Ex. RIM 634.21± Ex. INV IN 625.4 Ex. INV OUT 62(

Ex. JB Ex. RIM 634.24± Ex. INV IN 625.96± Ex. INV OUT 625.86±

Ex. JB Ex. INV IN (S)629.13± Ex. INV IN (N) 628.63± Ex. INV IN (E) 627.24± Ex. INV OUT 627.14±

Ex. DWSI Ex. INV IN 629.35± Ex. INV OUT 629.25±

Ex. SWSI Ex. INV OUT 630.80±

Ex. SWSI Ex. INV OUT 630.45±

Ex. SWSI Ex. INV IN 630.14± Ex. INV OUT 630.04±

Ex. SWSI Ex. INV IN 628.57± Ex. INV OUT 628.07±

Ex. SWSI Ex. INV IN 628.98± Ex. INV OUT 628.88±

Ex. SPHW Ex. INV OUT 629.59±

FINAL FOR DEVELOPMENT Dec 09 2021

REVISIONS

Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---
Date:	---

All documents, including Drawings and Bid Specifications, prepared or furnished by Firms listed on face are instruments of service in respect to the Project. Firms listed on face, shall retain an ownership and property interest therein whether or not the Project is completed. Such documents are not intended to represented to be suitable for reuse by the Client or others on extensions of the Project or on any other project. Any reuse without written verification by Firms listed on face will entitle Firms listed on face to further compensation at rates to be agreed upon by Firms listed on face and the Client.

MULLINS, LLC
CIVIL ENGINEERING, DEVELOPMENT DESIGN
SURVEYING, LANDSCAPE ARCHITECTURE
2101 West Clinton Avenue, Suite 103, Huntsville, AL 35805
(256) 690-5312

The Roberts Apartments at TM

Madison, AL


PREPARED FOR: ---

Post Development Drainage Map

Job No.	19-177
Date:	2021 9-21
Drawn By:	JLH
Checked By:	RS

SHEET NUMBER

D2



H2 ARCHITECTURAL SITE PLAN
1" = 60'-0"

N

GENERAL NOTES:

1. SEE CIVIL PLAN FOR PARKING SUMMARY.
2. THIS SITE PLAN IS FOR ARCHITECTURAL INFORMATION ONLY. SEE CIVIL & LANDSCAPE DOCUMENTS FOR SPECIFIC BUILDING LOCATION & OTHER SITE REQUIREMENTS. SEE LANDSCAPE DRAWINGS UNDER SEPARATE COVER FOR SITE CONFIGURATION, LAYOUT, GRADING AND RELATED INFORMATION
3. THE SWIMMING POOL(S) SHOWN ON THE DRAWINGS ARE PROVIDED FOR GENERAL LOCATION AND SHAPE SUGGESTION PURPOSES ONLY. FUGLEBERG KOCH LLC IS NOT QUALIFIED TO PROVIDE SERVICES FOR POOLS AND MAKES NO ATTEMPT TO DO SO. POOL DESIGN DOCUMENTS FOR CONSTRUCTION, CODE COMPLIANCE, AGENCY APPROVALS, CONSTRUCTION CERTIFICATION AND OTHER SERVICES REQUIRED FOR THE POOL(S) SHALL BE PERFORMED BY OTHERS UNDER THE SEPARATE CONTRACT WITH THE OWNER

LEGEND:

M.C METER CENTER. APROX 2000 AMP LOAD PER NEC

B DESIGNATED ANSI TYPE 'A' UNIT

DESIGNATED ACCESIBLE GARAGE

ISSUE HISTORY

No.	Date	Description
1	04/15/2022	PERMIT SUBMITTAL

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA LICENSED ARCHITECT 8234 4/15/22 REGISTERED ARCHITECT


MICHAEL GOVE
8234

THE ROBERT MADISON *MADISON, ALABAMA*	Drawn: MB Checked: JK Approval: MG Date: 04/15/2022 Project #: 5722

ARCHITECTURAL SITE PLAN

A1.01

PLOTTED: 5/5/2022
4:14:52 PM



H1 CLUBHOUSE - GROUND LEVEL
1/4" = 1'-0"

GENERAL NOTES:

01. EXTERIOR DIMENSIONS ARE FROM EXTERIOR FACE OF STUD TO EXTERIOR FACE OF STUD. WHEN A TENANT WALL OCCURRS, DIMENSIONS ARE TAKEN TO THE CENTERLINE. ALL OTHER DIMENSIONS ARE FROM OUTSIDE FACE OF STUD UNLESS NOTED OTHERWISE. SEE UNIT PLANS FOR FURTHER DIMENSIONS.

02. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES.

03. CONTRACTOR TO COORDINATE FLOOR & CEILING CONTROL JOINT PLACEMENT COMMON AREA AT 8'-0" MAX ON CENTER WHERE POSSIBLE.

04. SEE CIVIL PLANS FOR ACTUAL FINISH FLOOR ELEVATIONS.

05. REFER TO CIVIL DWGS. FOR SIDEWALK CONDITIONS.

LEGEND:

A. REFER TO ARCHITECTURAL PLANS FOR LOCATION OF FIRE RISER ROOM AND THE WATER RISER ROOM REQUIRED FOR EACH BUILDING LOCATION.

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, extension, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-9595
www.fuglebergkoch.com AA26002103
CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT
MICHAEL GOVE
8234


Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

THE MADISON
MADISON, AL

CLUBHOUSE FLOOR PLAN

CH2.01

PLOTTED: 5/3/2022 3:03:39 PM



K2 CLUBHOUSE REFLECTED CEILING PLAN
1/4" = 1'-0"

GENERAL NOTES:

A. ALL DIMENSIONS ARE FROM OUTSIDE FACE OF STUD UNLESS NOTED OTHERWISE. SEE UNIT PLANS FOR FURTHER DIMENSIONS.
B. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES.
C. SEE A300 SERIES SHEETS FOR UNIT PLAN INFORMATION.

RCP LEGEND

NOTE: SEE ELECTRICAL AND INTERIOR DESIGN FOR FIXTURE SCHEDULES

- SURFACED MOUNTED LED LIGHT FIXTURE
- PENDANT LIGHT FIXTURE
- CHANDALIER
- ATTIC ACCESS PANEL
- CEILING FAN
- EXHAUST FAN - CEILING MOUNTED
- SQUARE SUPPLY DIFFUSER - CEILING MOUNTED
- SQUARE RETURN DIFFUSER - CEILING MOUNTED
- (F) FAN JUNCTION BOX
- LIGHTED EXIT SIGN
- WALL MOUNTED LIGHT FIXTURE - COORDINATE LOCATION AND MOUNTING HEIGHT WITH OWNER & INTERIOR DESIGNER

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, extensions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234

THE MADISON
MADISON, AL

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

CLUBHOUSE REFLECTED CEILING PLAN

CH2.03


PLOTTED: 5/3/2022 3:03:42 PM

VENTILATION SCHEDULE		
ROOF VENT	MF'GR & MODEL #	FREE AREA
HARDIE VENTED SOFFIT	HARDIE SOFFIT	0.0347 SQ.FT
RIDGE VENT	CERTAINTEED	0.125 SQ.FT
OFF RIDGE VENT	4'-0" OFF RIDGE SHINGLE "FLAMCO"	0.96 SQ.FT
	6'-0" OFF RIDGE SHINGLE "FLAMCO"	1.46 SQ.FT

ATTIC VENT CALCULATIONS - AREA "A"		
	REQUIRED	PROVIDED
TOTAL ROOF AREA	= 2302 Sq.Ft.	
PER IBC 2018	x 0.0033	
REQ. VENTILATED AREA	7.60 Sq.Ft.	
TOTAL SOFFIT LIN. FT.		60 Lin.Ft.
OPENING NET VENTILATION		x 0.07 Sq.Ft.
NET FREE AREA	3.80 Sq.Ft.	4.2 Sq.Ft.
TOTAL RIDGE VENT LIN. FT.		28 Lin.Ft.
OPENING NET VENTILATION		x 0.125 Sq.Ft.
NET FREE AREA	3.80 Sq.Ft.	3.50 Sq.Ft.
TOTAL VENTILATED AREA	7.60 Sq.Ft.	7.70 Sq.Ft.

ATTIC VENT CALCULATIONS - AREA "B"		
	REQUIRED	PROVIDED
TOTAL ROOF AREA	= 599 Sq.Ft.	
PER IBC 2018	x 0.0033	
REQ. VENTILATED AREA	1.98 Sq.Ft.	
TOTAL SOFFIT LIN. FT.		15 Lin.Ft.
OPENING NET VENTILATION		x 0.07 Sq.Ft.
NET FREE AREA	0.99 Sq.Ft.	1.05 Sq.Ft.
TOTAL RIDGE VENT LIN. FT.		10 Lin.Ft.
OPENING NET VENTILATION		x 0.125 Sq.Ft.
NET FREE AREA	0.99 Sq.Ft.	1.25 Sq.Ft.
TOTAL VENTILATED AREA	1.98 Sq.Ft.	2.30 Sq.Ft.

ATTIC VENT CALCULATIONS - AREA "C"		
	REQUIRED	PROVIDED
TOTAL ROOF AREA	= 296 Sq.Ft.	
PER IBC 2018	x 0.0033	
REQ. VENTILATED AREA	0.98 Sq.Ft.	
TOTAL SOFFIT LIN. FT.		10 Lin.Ft.
OPENING NET VENTILATION		x 0.07 Sq.Ft.
NET FREE AREA	0.49 Sq.Ft.	0.7 Sq.Ft.
TOTAL RIDGE VENT LIN. FT.		4 Lin.Ft.
OPENING NET VENTILATION		x 0.125 Sq.Ft.
NET FREE AREA	0.49 Sq.Ft.	0.50 Sq.Ft.
TOTAL VENTILATED AREA	0.98 Sq.Ft.	1.20 Sq.Ft.



H2 CLUBHOUSE - ROOF PLAN
1/4" = 1'-0"

GENERAL NOTES:

1. PAINT ALL ROOF VENTS & PENETRATIONS TO MATCH ROOF SHINGLE COLOR
2. COORDINATE DOWNSPOUT DISCHARGE WITH CIVIL DRAWINGS. WHERE NOT TAKEN TO STORM, PROVIDE SPLASH BLOCK.
3. LEAVE OPENING IN MAIN ROOF SHEATHING FOR VENTILATION UNDERNEATH OVER BUILT AREAS.
4. DOWNSPOUTS AND GUTTERS SHOWN ARE MIN. REQUIREMENTS SUBJECT TO OWNER'S CONSIDERATIONS
5. CONTRACTOR SHALL BE RESPONSIBLE TO MEET MINIMUM ROOF VENT REQUIREMENTS
6. GENERAL CONTRACTOR SHALL COORDINATE ALL ROOF ACCESSORIES INSTALLATION DETAILS PER MANUFACTURERS SPEC'S TO MAINTAIN THE WATERTIGHT SYSTEM & EXTENDED WARRANTY
7. SEE CIVIL SITE PLAN FOR BUILDING ORIENTATION. CARDINAL DIRECTIONS SHOWN FOR REFERENCE ONLY

LEGEND:

- ATTIC DRAFT STOP PARTITION.
- REMOVABLE ACCESS PANEL, MIN. 36" X 36"
- 1HR. FIRE RATED ATTIC ACCESS PANEL, MIN. 22"X36". COORDINATE WITH ROOF TRUSSES
- RIDGE VENTS
- ICE AND WATER SHIELD / SELF-ADHEARED MEMBRANE UNDER ROOF FELT, 24" BACK FROM FACE OF EXTERIOR WALL TO EDGE OF EVE AND 24" WIDE @ ALL RAKES, RIDGES, VALLEYS, HIPS. FLASHING AND UNDER ALL SHINGLE ROOFS.
- D.S. DOWNSPOUT
- OFF-RIDGE VENT
- OUTLINE OF WALLS
- L.B. 12x24 LOUVER (BELOW ROOF LINE) LOCATE 12" MIN. ABOVE ROOF SURFACE

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, retension, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234


THE MADISON
MADISON, AL

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #	5722


CLUBHOUSE ROOF PLAN

CH2.04


PLOTTED: 5/3/2022 3:03:45 PM




K1 CLUBHOUSE - ENLARGED MAIL KIOSK 2
1/2" = 1'-0"




E6 MAIL KIOSK ELEVATION C
3/8" = 1'-0"




G6 MAIL KIOSK ELEVATION B
3/8" = 1'-0"




K6 MAIL KIOSK ELEVATION A
3/8" = 1'-0"




B9 MAILBOX FRAMING DETAIL
3" = 1'-0"



B11 MAILBOX FRAMING - EXTRA SUPPORT
3" = 1'-0"



E10 MAIL BOX SECTION
1 1/2" = 1'-0"



K9 SECTION DETAIL AT BACK TO BACK MAILBOXES
1 1/2" = 1'-0"

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2019 These drawings are copyrighted and shall not be used for any purpose other than the specific project noted on these drawings. Any reproductions, extensions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA MICHAEL E. GOVE 8234 4/15/22 REGISTERED ARCHITECT

MICHAEL GOVE
8234


Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

THE MADISON
MADISON, AL


CLUBHOUSE - MAIL KIOSK INTERIOR ELEVATIONS

CH3.02


PLOTTED: 5/3/2022 3:03:49 PM




D2 CLUBHOUSE - RESTROOM B CALLOUT
1/2" = 1'-0" B3/ A1.01




A5 COMMON ISLAND ELEVATION
3/8" = 1'-0" D4/ CH3.04



D4 CLUBHOUSE - COMMON SINK PLAN
1/2" = 1'-0" H1/ CH2.01




D6 COMMON SINK ELEVATION
3/8" = 1'-0" D4/ CH3.04




D10 COMMON SINK SECTION
3/8" = 1'-0" D4/ CH3.04


RESTROOM ACCESSORY SCHEDULE			
REF #	DESCRIPTION	MFGR	MODEL NUMBER
01	48" GRAB BAR	BOBRICK	B-5806 X 42
02	36" GRAB BAR	BOBRICK	B-5806 X 36
03	TOILET SEAT COVER DISPENSER	American Specialties	B-4221
04	TOILET PAPER DISPENSER		
05	PAPER TOWEL DISPENSER	BOBRICK	B-43699
06	SOAP DISPENSER	BOBRICK	B-4112
07	SANITARY NAPKIN DISPOSAL	BOBRICK	B-270
08	FRAMED MIRROR	(BY OWNER/INT. DESIGNER)	(BY OWNER/INT. DESIGNER)
09	BABY CHANGING STATION	KOALA CARE	KB-208
10	VANITY LIGHT - 2 BULB	PROGRESS LIGHTING	P3262
11	ADA SINK		




K1 CLUBHOUSE - RESTROOM A CALLOUT
1/2" = 1'-0"




G5 ELEVATION E
3/8" = 1'-0" K1/ CH3.04




G6 ELEVATION F
3/8" = 1'-0" D2/ CH3.04




G9 ELEVATION G
3/8" = 1'-0" K1/ CH3.02




G10 ELEVATION H
3/8" = 1'-0" D2/ CH3.04




G11 ELEVATION J
3/8" = 1'-0" K1/ CH3.02




K6 ELEVATION A
3/8" = 1'-0" K1/ CH3.04



K8 ELEVATION B
3/8" = 1'-0" K1/ CH3.04



K9 ELEVATION C
3/8" = 1'-0" K1/ CH3.04



K11 ELEVATION D
3/8" = 1'-0" K1/ CH3.04

ISSUE HISTORY		
No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY		
No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH ARCHITECTS, INC. and are not to be used for any purpose other than the specific project noted on these drawings. Any reproductions, retains, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT


MICHAEL GOVE
8234

THE MADISON	Drawn: MB
	Checked: JK
	Approval: MG
MADISON, AL	Date: 04/15/2022
	Project #: 5722

CLUBHOUSE ENLARGED PLANS


CH3.04

PLOTTED: 5/3/2022 3:03:54 PM




C2 FRONT ELEVATION

3/16" = 1'-0" H1/ CH2.01




F2 REAR ELEVATION

3/16" = 1'-0" H1/ CH2.01



K2 SIDE ELEVATION 1

3/16" = 1'-0" H1/ CH2.01



K8 SIDE ELEVATION 2

3/16" = 1'-0" H1/ CH2.01

ELEVATION KEY NOTES:

1. FIBER CEMENT PANEL
2. FIBER CEMENT CORNER TRIM
3. BRICK
4. FIBER CEMENT SIDING 8" EXPOSURE
5. FIBER CEMENENT TRIM BAND
6. VINYL WINDOW SYSTEM - SEE SCHEDULE
7. DOWNSPOUT
8. METAL AWNING: BLDG A 9'-0", CLUB. 1'-8", MAINT. 4'-0", REMAINING BLDG HAVE 8'-0"
9. METAL GUARD RAIL
10. SIGNAGE/AREA - SIGNAGE DESIGN BY OTHERS - TO BE SUBMITTED LATER.
11. LAUNDRY / BATHROOM EXHAUST VENTS
12. ELECTRICAL METER CENTER - SEE ELECTRICAL
13. LIGHT FIXTURE - SEE ELECTRICAL
14. 5/4 X 3 1/2 FIBER CEMENT TRIM
15. 5/4 X 5 1/2 FIBER CEMENT TRIM
16. 5/4 X 7 1/2 FIBER CEMENT TRIM
17. 5/4 X 11 1/2 FIBER CEMENT TRIM
18. COLUMN
19. PILASTER
20. ALUM. WRAP FASCIA
21. DECORATIVE FEATURE
22. 6" X 9" OPENING
23. ASPHALT ROOF SHINGLES
24. STANDING SEAM METAL ROOF
25. 6" PREFINISHED METAL RAIN GUTTER
26. EXTERIOR WALL LIGHT. SEE ELECTRICAL
27. ELECTRICAL PANEL. REFER TO ELECTRICAL DWGS.
28. ROOF VENT
29. ROOF RIDGE
30. BRACKET

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, extensions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH

2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT


MICHAEL GOVE
8234

THE MADISON	Drawn: MB
MADISON, AL	Checked: JK
	Approval: MG
	Date: 04/15/2022
	Project #: 5722

CLUBHOUSE EXTERIOR ELEVATIONS

CH4.01


PLOTTED: 5/3/2022 3:04:00 PM




C2 LONGITUDINAL SECTION A
3/16" = 1'-0" H1/ CH2.01



F2 LONGITUDINAL SECTION B
3/16" = 1'-0" H1/ CH2.01



F9 SECTION C
3/16" = 1'-0" H1/ CH2.01



J2 SECTION A
3/16" = 1'-0" H1/ CH2.01



J8 SECTION B
3/16" = 1'-0" H1/ CH2.01

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are and shall remain the property of FUGLEBERG KOCH - AA26002103, and are not to be used in any form for any specific project not specifically authorized in writing by them.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234


THE MADISON
MADISON, AL

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722


CLUBHOUSE BUILDING SECTIONS

CH5.01


PLOTTED: 5/3/2022
3:04:05 PM




D1 OUTSIDE CORNER (BRICK)
1 1/2" = 1'-0" H1/ CH2.01




B3 OUTSIDE CORNER (SIDING)
1 1/2" = 1'-0" H1/ CH2.01




B8 INSIDE CORNER (SIDING)
1 1/2" = 1'-0" H1/ CH2.01




F1 INSIDE CORNER (BRICK)
1 1/2" = 1'-0" H1/ CH2.01




F8 INSIDE CORNER (SIDING)
1 1/2" = 1'-0" K1/ CH3.02




D8 TYPICAL DETAIL @ (SIDING)
1 1/2" = 1'-0"



D3 INSIDE CORNER (SIDING)
1 1/2" = 1'-0" H1/ CH2.01



H1 COLUMN PLAN DETAIL
1 1/2" = 1'-0" H1/ CH2.01



H3 INT. WALL AT BDA RM
1 1/2" = 1'-0"

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA MICHAEL E. GOVE 8234 4/15/22 REGISTERED ARCHITECT

MICHAEL GOVE
8234


THE MADISON
MADISON, AL

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722


CLUBHOUSE PLAN DETAILS

CH6.01


PLOTTED: 5/3/2022 3:04:08 PM




C1 ROOF EAVE AT GABLE DETAIL
1 1/2" = 1'-0" J2/ CH5.01




C3 TYP. ROOF VENT EAVE DETAIL
1 1/2" = 1'-0" C2/ CH5.01




C5 ROOF VENT EAVE DETAIL @ LOGIA
1 1/2" = 1'-0"




C7 SECTION WALL DETAIL
1 1/2" = 1'-0" J8/ CH5.01




C9 ENLARGED FACIA DETAIL
3" = 1'-0" C3/ CH6.02




F1 ROOF VENT DETAIL
1 1/2" = 1'-0"




F3 ROOF VENT PIPE DETAIL
1 1/2" = 1'-0"




F5 ROOF VALLEY DETAIL
1 1/2" = 1'-0" F2/ CH5.01




F7 ENLARGED RIDGE DETAIL
3" = 1'-0" H2/ CH2.04




F9 ENLARGED RIDGE VENT DETAIL
3" = 1'-0" H2/ CH2.04




H1 ATTIC ACCESS DETAIL
1 1/2" = 1'-0"



H2 FOUNDATION DETAIL - BRICK
1" = 1'-0" C2/ CH5.01




H5 COLUMN BASE
1 1/2" = 1'-0"



G7 DRAFTSTOP ACCESS PANEL
1 1/2" = 1'-0"

H7 FOUNDATION DETAIL @ LOGIA
1 1/2" = 1'-0"



H8 WALL SECTION - BRICK @ CAP
1 1/2" = 1'-0" C2/ CH5.01

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103 and are issued only for the specific project noted on these drawings. Any reproductions, retainer, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-8595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA MICHAEL E. GOVE 8234 4/15/22 REGISTERED ARCHITECT

MICHAEL GOVE
8234

THE MADISON
MADISON, AL

Drawn:	MB
Checked:	JK
Approval:	MC
Date:	04/15/2022
Project #:	5722


CLUBHOUSE SECTION DETAILS

CH6.02

PLOTTED: 5/3/2022 3:04:11 PM

DOOR SCHEDULE

DOOR					GLAZING	FRAME		DOOR	HARDWARE	
TYPE	WIDTH	HEIGHT	THICKNESS	MATERIAL	TYPE	TYPE	MATERIAL	RATING	SET	REMARKS
CH01	3' - 0"	6' - 8"	1 3/8"	FG/GLASS	TEMP	A	HM		C1	SINGLE SWING
CH03	3' - 0"	8' - 0"	1 3/4"	WD	-	D	WD		C3	
CH06	3' - 0"	8' - 0"	1 3/4"	HM	-	D	HM		C2	
CH07	3' - 0"	8' - 0"	1 3/4"	WD	TEMP	C	WD		C5	
CH09	3' - 0"	8' - 0"	1 3/4"	WD/GLASS	TEMP	E	WD		C3	
CH26	3' - 0"	9' - 0"	1 3/4"	FG/GLASS	-	C	HM		C4	
CH27	4' - 0"	6' - 8"	1 1/2"	WD	-	F	HM			



CLUBHOUSE - DOOR TYPES
1/4" = 1'-0"

DOOR NOTES:

A. ALL FIRE DOORS AND FRAMES TO HAVE APPROVED CLOSERS AND LATCHING MECHANISMS.

B. THERSHOLDS AT EXTERIOR DOORS ARE NO HIGHER THAN 1/2" MAX.

C. VERIFY ROUGH OPENING REQUIRED WITH DOOR FRAME MANUFACTURER.

D. PROVIDE WEATHERSTRIPING AT ALL EXTERIOR DOORS.

E. DOOR MANUFACTURER SHALL PROVIDE CERTIFICATION, SIGNED AND SEAL BY A REGISTERED ALABAMA PROFESSIONAL ENGINEER THAT:

1- DOORS WILL BE ABLE TO WITHSTAND REQUIRED WIND LOADS AND PRESSURE.

2- TO SUPPLY TYPE AND NUMBER OF FASTENERS REQUIRED TO SECURE FRAME TO HEAD, JAMBS OF ALL DOOR OPENINGS.

HARDWARE NOTES:


A. REFER TO SPECIFICATIONS FOR HARDWARE GROUPS. ALL HARDWARE TO MEET INTERNATIONAL BUILDING CODE REQUIREMENTS AND MEET FAIR HOUSING GUIDELINES FOR ACCESSIBLE AND USABLE DOORS.

B. PRIMARY ENTRY DOORS OF DWELLING UNIT EXTERIOR SIDE, PUBLIC AND COMMON USED DOORS MUST PROVIDE 32" CLEAR WIDTH AND HAVE 1/2" THRESHOLDS.


C. BALCONY DOOR THRESHOLD TO NOT EXCEED 4" FOR IMPERVIOUS CONSTRUCTION OF THE WET SIDE.

D. ALL UNITS AT GROUND LEVEL SHALL HAVE LEVER TYPE HARDWARE ON ALL DOORS. IF CLOSER IS PROVIDED, SHALL NOT REQUIRED MORE THAN 5 LBF. TO OPERATE AND CLOSE UNLESS REQUIRED BY LOCAL FIREAUTHORITY.


B8 CASED OPENING JAMB DETAIL
3" = 1'-0"




D6 EXTERIOR DOOR HEAD DETAIL
3" = 1'-0"




D8 INTERIOR DOOR HEAD DETAIL
3" = 1'-0"




F6 EXTERIOR DOOR JAMB DETAIL
3" = 1'-0"



F8 INTERIOR DOOR JAMB DETAIL
3" = 1'-0"



H6 EXTERIOR DOOR THRESHOLD DETAIL
3" = 1'-0"



H8 INTERIOR DOOR THRESHOLD DETAIL
3" = 1'-0"

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, extensions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234

THE MADISON
MADISON, AL


Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

DOOR SCHEDULE AND DETAILS

CH7.01

PLOTTED: 5/3/2022 3:04:14 PM

CLUBHOUSE WINDOW SCHEDULE											
MARK	QTY	WINDOW UNIT WIDTH	WINDOW UNIT HEIGHT	Head Height	WINDOW UNIT OPERATION	GLAZING TYPE	GLAZING THICKNESS	U VALUE	SHGC	FRAME MATERIAL	REMARKS
P		2' - 10"	2' - 10"	12' - 3"							
Q		3' - 0"	6' - 0"	15' - 6"	FIXED			.35	.40		
R		3' - 0"	6' - 0"	9' - 0"				0.34	0.27		
S		6' - 4"	3' - 0"								
T		3' - 0"	1' - 8"	8' - 8 1/2"	FIXED			.35	.40		



CLUBHOUSE - WINDOW TYPES
1/4" = 1'-0"

NOTES:

A. VERIFY ROUGH OPENING REQUIRED WITH WINDOW MANUFACTURER.

B. WINDOW MANUFACTURER SHALL PROVIDE CERTIFICATION, SIGNED AND SEAL BY A REGISTERED **ALABAMA** PROFESSIONAL THAT:


1- WINDOWS WILL BE ABLE TO WITHSTAND REQUIRED WIND LOADS AND PRESSURE.

2- TO SUPPLY TYPE AND NUMBER OF FASTENERS REQUIRED TO SECURE FRAME TO HEAD, JAMBS & SILL OF ALL WINDOW OPENINGS.


C. PROVIDE SEALANT AT ALL SCREW-HOLES PROVIDED FOR FASTENING PRIOR TO FASTENER INSTALLATION.

D. WINDOWS UNITS SHALL BE ANCHOR THROUGH THE JAMB, ANCHORS SHALL BE SECURELY FASTENED IN TO THE STRUCTURAL MATERIAL


E. PROVIDE TEMPERED GLASS AT ALL WINDOWS LOWER SASH IF SILL HEIGHT IS BELOW 2 FEET, WITHIN 3'-0" OF PATIO DOORS, OR AS OTHERWISE NOTED.




B7 TYP. WINDOW CENTER JAMB DETAIL
3" = 1'-0"




B9 WINDOW HEAD DETAIL - PANEL
3" = 1'-0"




D9 TRANSOM WINDOW HEAD/ SILL
3" = 1'-0"



F9 WINDOW JAMB DETAIL
3" = 1'-0"



H8 WINDOW SILL DETAIL AT BRICK
3" = 1'-0"



H9 WINDOW SILL DETAIL - SIDING
3" = 1'-0"

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submittal

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

STATE OF ALABAMA
MICHAEL E. GOVE
8234
4/15/22
REGISTERED ARCHITECT

MICHAEL GOVE
8234

Drawn:	MB
Checked:	JK
Approval:	MG
Date:	04/15/2022
Project #:	5722

THE MADISON
MADISON, AL

CLUBHOUSE WINDOW DETAILS AND SCHEDULES

CH7.02

PLOTTED: 5/3/2022 3:04:18 PM

GENERAL NOTES

1. IT IS THE CONTRACTORS SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURE AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENT PARTS DURING ERECTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF WHATEVER TEMPORARY BRACING, GUYS OR TIE-DOWNS MAY BE NECESSARY.

CODES AND SPECIFICATIONS

A. GENERAL BUILDING CODE:
1. INTERNATIONAL BUILDING CODE 2018.

B. CONCRETE:
1. BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE (ACI 318-19)
2. SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS (ACI 301-16).

DESIGN LOADS

A. DESIGN LIVE LOADS

ROOF	20 PSF
ELEVATED FLOORS	40 PSF
BALCONY, CORRIDORS AND BREEZE WAYS	100 PSF
STAIRS	100 PSF

B. WIND LOADS:
1) BASIC WIND SPEED (ULTIMATE) = 115 MPH
2) IMPORTANCE FACTOR = 1.0
3) WIND EXPOSURE C.
4) INTERNAL PRESSURE COEFFICIENT ;0.18 FULLY ENCLOSED STRUCTURE
5) COMPONENTS AND CLADDING: +34.7 PSF AND -45.4 PSF FOR DESIGN WIND PRESSURES.

C. SEISMIC LOADS:

1) SEISMIC DESIGN CATEGORY	B
2) SDS	0.26
3) SD1	0.117
4) SMS	0.337
5) SDS	0.225

FOUNDATIONS

1. FOUNDATION DESIGN IS BASED ON AN ALLOWABLE SOIL BEARING PRESSURE OF 2000 PSF AS RECOMMENDED IN THE FOUNDATION INVESTIGATION PREPARED BY GEOSERVICES, LLC (PROJECT NO. 21-0759) AUGUST 3, 2021.
2. PLACE FOOTINGS/SLAB ON COMPACTED SOIL. FOLLOW RECOMMENDATIONS OF SOILS REPORT.
3. VERIFY BEARING CAPACITY BY TESTING PRIOR TO SLAB PLACEMENT. SUBMIT REPORTS TO ARCHITECT.

CAST-IN-PLACE CONCRETE

1. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS, HAVE A SLUMP OF 4" PLUS OR MINUS 1", AND HAVE 2-4% AIR ENTRAINMENT.
2. ALL REINFORCING STEEL SHALL BE NEW DOMESTIC DEFORMED BILLET STEEL CONFORMING TO ASTM A-615 GRADE 60.
3. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH "THE BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" ACI 318-19.
4. ALL REINFORCING DETAILS SHALL CONFORM TO "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES" ACI 315-18.
5. CONTRACTOR SHALL VERIFY LOCATIONS OF ALL OPENINGS, SLEEVES, ANCHOR BOLTS, INSERTS, ETC., AS REQUIRED BY OTHER TRADES BEFORE CONCRETE IS PLACED.
6. CONTRACTOR SHALL PROVIDE SPACERS, CHAIRS, BOLSTERS, ETC., NECESSARY TO SUPPORT REINFORCING STEEL.
7. ALL SLABS SHALL BE POURED MONOLITHICALLY, EXCEPT FOR REQUIRED CONSTRUCTION JOINTS.
8. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCEMENT:

   3"---------CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH.
   1-1/2"--------ALL OTHER CASES.

9. HORIZONTAL SLAB BARS SHALL BE BENT 1'-6" AROUND CORNERS, OR PROVIDE CORNER BARS WITH A 2'-0" LAP ON EACH LEG.
10. TESTING LABORATORY SHALL SUBMIT ONE COPY OF ALL CONCRETE TEST REPORTS DIRECTLY TO THE POST TENSION ENGINEER ARCHITECT-SEE SPECS.

WOOD CONSTRUCTION

1. WOOD CONSTRUCTION SHALL CONFORM TO THE NDS "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION", LATEST EDITION.
2. ALL WALL STUDS AND MISC. WOOD FRAMING SHALL BE NO.2 SOUTHERN YELLOW PINE. STUDS FOR LOAD BEARING WALLS SHALL BE AS FOLLOWS:

EXTERIOR WALLS	2x6'S @ 16"O.C. (U.N.O)
INTERIOR WALLS	2x6'S @ 16"O.C. (U.N.O)

   ALL LOAD BEARING WALLS SHALL HAVE MIDSPAN HORIZONTAL BLOCKING SPACED AT 48" O.C. INSTALLED BEFORE WALLS ARE LOADED.
   ALL NON-LOAD BEARING PARTITIONS SHALL CONSIST OF 2x4 STUDS SPACED AT 24" O.C. 2x4 STUDS DO NOT NEED TO BE DOUBLED AT THE FIRST FLOOR FOR NON-LOAD BEARING WALLS.
3. PLACE A SINGLE PLATE AT THE BOTTOM AND A DOUBLE PLATE AT THE TOP OF ALL STUD WALLS. 2x SOLE PLATES AT THE EDGES OF SLABS SHALL BE ATTACHED TO THE SLAB WITH SIMPSON MAS MUDSILL ANCHORS (WITH 6 10d NAILS) AT 32" O.C.. AT INTERIOR STUD WALLS PROVIDE EITHER HILTI ZF72 (WITH 2 7/8" LENGTH, 5/64" THICK WASHERS) POWDER DRIVEN FASTENERS AT 8" ON CENTER, OR 1/2" DIAMETER ANCHOR BOLTS WITH 6" EMBEDMENT, AT 32" ON CENTER.
   RED-HEAD FASTENERS OF EQUIVALENT SIZES MAY BE USED. ALL OTHER SUBSTITUTIONS MUST BE APPROVED BY ADVANCED STRUCTURAL ENGINEERING PRIOR TO INSTALLATION.
   SEE THE SHEAR WALL SCHEDULE BELOW FOR SPECIAL SOLE PLATE ATTACHMENT
4. STUDS SHALL BE PACKED AT ALL ANGLES, CORNERS, AROUND ALL OPENINGS AND AT SHEAR WALLS. SEE SCHEDULES, UL ASSEMBLIES AND ARCH. DETAILS FOR REQUIREMENTS.
5. WOOD LINTELS OVER OPENINGS SHALL BE AS NOTED PER DETAIL 1/S5.02 . NAIL MULTIPLE STUDS TOGETHER WITH 16d NAILS @ 12" O.C. EACH PLY.
6. WALL SHEATHING SHALL BE: (SEE SHEAR WALL SCHEDULE S1.02 FOR REQUIREMENTS AT SHEAR WALLS.)

   AT INTERIOR WALLS PROVIDE 5/8" GYPSUM WALLBOARD (SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS) EACH SIDE OF STUDS, NAILED WITH 5d COOLER NAILS AT 7" O.C. (USE 6d COOLER NAILS FOR 5/8" WALLBOARD) AT ALL SUPPORTS. PROVIDE SOLID 2x BLOCKING AT ALL SHEET EDGES. BLOCKING IS NOT REQUIRED AT NON-LOAD BEARING PARTITIONS.

   AT EXTERIOR WALLS SHEATH THE INTERIOR FACE OF WALLS WITH 5/8" GYPSUM WALLBOARD AS NOTED ABOVE FOR INTERIOR WALLS. SHEATH THE EXTERIOR FACE OF WALLS WITH 7/16" C-DX PLYWOOD (OR 7/16" O.S.B.), NAILED WITH 8d NAILS AT 6" O.C. AT ALL EDGE SUPPORTS, AND 8d NAILS AT 6" O.C. AT ALL INTERMEDIATE SUPPORTS. PROVIDE SOLID DOUBLE 2x BLOCKING AT ALL SHEET EDGES.
   SHEARWALL SCHEDULE NOTE 5.
7. ALL WOOD IN CONTACT WITH CONCRETE OR EXPOSED TO WEATHER SHALL BE PRESSURE TREATED.
8. ROOF SHEATHING SHALL BE 15/32" C - D PLYWOOD OR 15/32" O.S.B., NAILED WITH 8d NAILS AT 6" O.C. AT SUPPORTED EDGES, AND 8d NAILS AT 12" O.C. AT INTERMEDIATE SUPPORTS. PROVIDE ONE PLYWOOD CLIP PER SPAN BETWEEN SHEET EDGES. PROVIDE SOLID 2x BLOCKING BETWEEN SUPPORTS AT ALL HIPS, RIDGES, VALLEYS, AND CHANGES IN ROOF SLOPE.
9. ALL LUMBER SHALL BE STAMPED WITH THE GRADE MARK OF AN APPROVED GRADING AGENCY.
10. NAILING SCHEDULE:

CONNECTION	COMMON NAIL	NUMBER OR SPACING
SOLE PLATE TO TRUSS OR BLOCKING	16d	8" O.C.
STUD TO SOLE PLATE, TOE NAIL	8d	4
DOUBLE STUDS, FACE NAIL	16d	24" O.C.
DOUBLE TOP PLATES, FACE NAIL	16d	16" O.C.
TOP PLATES LAPS AND INTERSECTIONS	16d	3
TRUSSES, LAPS OVER WALLS, FACE NAIL	16d	4
BUILT-UP CORNER STUDS	16d	12" O.C.
STUDS TO SOLE PLATE, END NAIL	16d	2

   WHERE WOOD BEAMS/HEADERS ABUT WOOD COLUMNS, PROVIDE SIMPSON "HHUC" CONNECTORS WITH ALL NAILS SPECIFIED BY THE MANUFACTURER.

   AT ALL WALLS SUPPORTING ROOF TRUSSES PROVIDE UPLIFT STRAPPING/CONNECTORS SHOWN IN THE TYPICAL WALL ELEVATION 1/S5.02. OR ALTERNATE: HURRY-BOLT
11. SYSTEM OR EQUAL. - SUBMIT ENGINEERED SHOP DRAWINGS FOR REVIEW.
12. ALL LOAD BEARING WALLS SHALL HAVE MIDSPAN HORIZONTAL BLOCKING SPACED AT 48" O.C. INSTALLED BEFORE WALLS ARE LOADED.
    ALL NON-LOAD BEARING PARTITIONS SHALL CONSIST OF 2x4 STUDS SPACED AT 24" O.C. 2x4 STUDS DO NOT NEED TO BE DOUBLED AT THE FIRST FLOOR FOR NON-LOAD BEARING WALLS.
13.

PREFABRICATED WOOD TRUSSES

1. ALL PREFABRICATED WOOD TRUSSES SHALL BE SECURELY FASTENED AT EACH END TO THEIR SUPPORTING WALLS OR BEAMS AS SHOWN IN THE TYPICAL WALL ELEVATION 1/S5.02
2. PREFABRICATED WOOD TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF THE "NATIONAL DESIGN SPECIFICATION FOR STRESS-GRADE LUMBER AND ITS FASTENERS" AS RECOMMENDED BY THE NATIONAL FOREST PRODUCTS ASSOCIATION.
3. TRUSS MEMBERS AND CONNECTIONS SHALL BE DESIGNED (WITH A MAXIMUM ALLOWABLE STRESS INCREASE FOR LOAD DURATION OF 25% FOR ROOF TRUSSES ONLY) TO WITHSTAND THE LIVE LOADS GIVEN IN THE NOTES AND TOTAL DEAD LOAD.
4. TRUSS MANUFACTURER SHALL SUBMIT SHOP DRAWINGS AND DESIGN NOTES WITH A ALABAMA REGISTERED ENGINEER'S SEAL FOR APPROVAL BY THE ARCHITECT. DESIGN NOTES TO INCLUDE THE RATED LOAD CAPACITY OF THE CONNECTORS USED TO SECURE THE MEMBERS, CERTIFICATION OF THE CONNECTOR CAPACITIES AND MANUFACTURER'S LICENSE TO FABRICATE TRUSSES UTILIZING THE CONNECTOR SYSTEM PROPOSED.
5. THE CONTRACTOR SHALL APPROVE FABRICATION AND INSTALLATION DRAWINGS SHOWING SIZE, SHAPE AND LAYOUT PRIOR TO SUBMITTAL FOR REVIEW BY THE ARCHITECT AND BEFORE FABRICATION HAS BEGUN.
6. BRIDGING FOR PRE-ENGINEERED TRUSSES SHALL BE AS REQUIRED BY TRUSS MANUFACTURER, AND THE LOCAL BUILDING CODE, UNLESS NOTED ON PLANS. ALSO WHERE HEEL HEIGHT ON BOTTOM CHORD BEARING TRUSSES EXCEEDS 11" PROVIDE CONTINUOUS 2x4 LET IN.
7. DESIGN LOADS - DEAD LOADS:

FLOOR TRUSSES	BOTTOM CHORD	8 PSF
	TOP CHORD (APTS)	15 PSF
OUTSIDE TRUSSES	BOTTOM CHORD	8 PSF
	TOP CHORD	45 PSF
ROOF TRUSSES	BOTTOM CHORD	10 PSF
	TOP CHORD	10 PSF (SHINGLE)
	TOP CHORD	12 PSF (TILE)
	TOP CHORD (AT OVERBUILT AREAS)	5 PSF ADDITIONAL

8. ALL SIMPSON TRUSS ANCHORS SHOWN ON DRAWINGS SHALL BE VERIFIED FOR LOADS SHOWN ON WOOD TRUSS DESIGN CALCULATIONS. THEREFORE, ANCHOR SIZES AND TYPES ARE SUBJECT TO CHANGE BY ADVANCED STRUCTURAL ENGINNERING II.

FASTENER SUBSTITUTIONS:

ALL NAILS ARE COMMON NAILS, UNLESS NOTED OTHERWISE. THE FOLLOWING FASTENERS ARE ACCEPTABLE SUBSTITUTIONS. THE ALTERNATE FASTENERS SHALL BE SPACED AT THE SAME SPACING AS THE SCHEDULED FASTENERS.

SCHEDULED FASTENER	ALTERNATE FASTENER
8d COMMON NAIL	8d RING SHANK NAIL 8d SCREW SHANK NAIL 0.131 P-NAIL
10d COMMON NAIL	10d RING SHANK NAIL 10d SCREW SHANK NAIL 0.148 P-NAIL
16d COMMON NAIL	16d RING SHANK NAIL 16d SCREW SHANK NAIL
6d COOLER NAIL	#6 x 1 1/4" TYPE S OR W DRYWALL SCREW

SHOP DRAWING SUBMITTALS

A. ALL SHOP DRAWINGS SHALL BE REVIEWED AND STAMPED BY THE GENERAL CONTRACTOR PRIOR TO SUBMITTAL. ALL SUBMITTALS SHALL BE PROVIDED FOR THE ENGINEER REVIEW A MINIMUM OF TWO WEEKS PRIOR TO CONSTRUCTION OR REQUIRED DELIVERY OF MATERIALS. THE ENGINEER SHALL BE PROVIDED A MINIMUM OF (10) BUSINESS DAY TO REVIEW SUBMITTALS. THE CONTRACTOR SHALL MAKE NO CLAIMS FOR DELAY FOR SUBMITTALS NOT PROVIDED IN ACCORDANCE WITH THIS REQUIRED REVIEW PERIOD OR NOT OTHERWISE SUBMITTED IN A TIMELY MANNER.

B. THE GENERAL CONTRACTOR SHALL SUBMIT FOR ENGINEER REVIEW SHOP DRAWINGS FOR THE FOLLOWING ITEMS:
1. STRUCTURAL STEEL
2. REINFORCING STEEL (*).
3. PRE-ENGINEERED WOOD TRUSSES (*).
4. CONCRETE MIX DESIGNS
5. POST-TENSION CABLE SHOP DRAWINGS WITH CALCULATIONS (*).
6. CMU WALL.
7. PRE-ENGINEERED STAIRS WITH CALCULATIONS.

   ITEMS MARKED (*) SHALL HAVE SHOP DRAWINGS SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF ALABAMA. ITEMS MARKED (#) SHALL BE SUBMITTED FOR ENGINEERS RECORD ONLY.

C. MANUFACTURER'S LITERATURE: SUBMIT TWO COPIES OF MANUFACTURER'S LITERATURE FOR ALL MATERIALS AND PRODUCTS USED IN CONSTRUCTION ON THE PROJECT.


WOOD HEADER/BEAM SCHEDULE			
TYPE	HEADER/BEAM	TYPE	HEADER/BEAM
H-1	DOUBLE 2x8 FOR 4" WALL TRIPLE 2x6 FOR 6" WALL	H-4	(2) 1 3/4" x 11 7/8" LVL
H-2	DOUBLE 2x10 FOR 4" WALL TRIPLE 2x8 FOR 6" WALL	H-5	(2) 2x12
H-3	DOUBLE 2x12 FOR 4" WALL TRIPLE 2x10 FOR 6" WALL	H-6	(2) 1 3/4" x 16" LVL
H-3B	TRIPLE 2x12	H-7	(3) 1 3/4" x 16" LVL

1. PROVIDE WOOD HEADERS OVER ALL LOAD BEARING OPENINGS. IF NO HEADER IS SPECIFIED, PROVIDE H-3 AT WALLS SUPPORTING TRUSSES, AND H-1 AT OTHER WALLS.
2. AT DOUBLE OR TRIPLE 2x HEADER/BEAMS PROVIDE A 1/2" PLYWOOD (OR O.S.B.) SPACER BETWEEN MEMBERS.
3. NAIL ALL MULTI-MEMBER HEADERS AND BEAMS TOGETHER WITH 12d NAILS AT 12" O.C. TOP AND BOTTOM, EACH SIDE, STAGGERED.

ADDITIONAL NOTES

1. WATERPROOFING DESIGN IS NOT IN THE STRUCTURAL SCOPE OF WORK, HENCE NO DETAILS OF FLASHING, FLOOR, SLOPE AND STEP, NOR ANY OTHER WATERPROOFING MEASURES HAVE BEEN INCLUDED IN OUR DRAWINGS. IF SLOPE AND FLOOR STEPS ARE SHOWN ON OUR DRAWINGS, THEY SHALL BE USED ONLY AS A REFERENCE. FLOOR SLOPE AND STEPS SHALL FOLLOW ARCHITECTURAL DRAWINGS.
2. CONTRACTOR SHALL VERIFY THAT THE TRUSS LAYOUT SUPPLIED BY THE TRUSS MANUFACTURER MATCHES THE TRUSS LAYOUT SHOWN ON THE STRUCTURAL DRAWINGS. IF THERE IS ANY DISCREPANCY BETWEEN TRUSS LAYOUT SHOWN ON TRUSS SHOP DRAWINGS AND TRUSS LAYOUT SHOWN STRUCTURAL DRAWINGS, CONTRACTOR SHALL STOP CONSTRUCTION AND INFORM IN WRITING THE ENGINEER OF RECORD. CONTRACTOR SHALL WAIT FOR ENGINEER OF RECORD RESPONSE IN WRITING PRIOR TO START OF CONSTRUCTION.
3. EACH PLY OF EVERY MULTIPLE-PLY GIRDER TRUSS SHALL BE NAILED TOGETHER PER TRUSS MANUFACTURER SPECIFICATIONS.
4. ALL STUCCO AND/OR VENEER DESIGNS ARE NOT IN THE SCOPE OF WORK FOR THE STRUCTURAL ENGINEER.
5. PAVER AND SIDE WALK DESIGNS ARE NOT IN THE SCOPE OF WORK FOR THE STRUCTURAL ENGINEER.
6. CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS BETWEEN ARCHITECTURAL AND STRUCTURAL DRAWINGS. INFORM ARCH/ENG IF DIMENSIONS DO NOT MATCH. CONTRACTOR SHALL GET A RESPONSE FROM ARCHITECT/ENGINEER IN WRITING TO RESOLVE THE PROBLEMS PRIOR TO STARTING CONSTRUCTION.
7. BUILDING MAINTENANCE SUCH AS PAINTING AND SEALING ETC. IS THE HOME OWNER SOLELY RESPONSIBLE.
8. CONTRACTOR TO PROVIDE CRACK ISOLATION MEMBRANE OVER SLAB AT AREAS TO BE TILED PRIOR TO INSTALLATION OF FLOOR TILE.
9. ALL REBAR SHOWN ON ALL DRAWING DETAILS AND SECTIONS IS CONTINUOUS UNLESS NOTICE OTHERWISE.
10. THE SECTIONS SHOWN ON THE DESIGN DRAWINGS INDICATE THE TYPICAL SECTIONS WHICH ARE APPLIED TO ALL SIMILAR BUILDING CONDITIONS.
11. DEVELOPER OR G.C. SHOULD HIRE DELEGATED ENGINEERS TO SUBMIT SHOP DRAWINGS WITH CALCULATIONS TO ENGINEER OF RECORD FOR REVIEW SUCH AS TRUSSES, STEEL FRAMING AND CONNECTION, METAL STUD FRAMING, STEEL STAIRS, RAILING, POST TENSION MEMBERS, PRECAST STRUCTURES AND ETC.

ROOF FASTENING ZONES
GABLE ROOF



HIP ROOF

ROOF SHEATHING FASTENING SCHEDULE:
NOTE: USE 8d RING SHANK NAILS IN ZONE

PANEL EDGES	PANEL FIELD
① NAILS 6" O.C.	① NAILS 6" O.C.
② NAILS 6" O.C.	② NAILS 6" O.C.
③ NAILS 4" O.C.	③ NAILS 4" O.C.

WINDOW & DOOR WINDOW PRESSURES 115 MPH WIND ZONE EXPOSURE C BUILDING CATAGORY II		
OPENING SIZE	INTERIOR ZONE	EXTERIOR ZONE**
10 SQFT	+36.4 / -39.5	+36.4 / -48.8
20 SQFT	+34.7 / -37.8	+34.7 / -45.4
50 SQFT	+32.6 / -35.5	+32.6 / -41.2
100 SQFT	+30.9 / -34.0	+30.9 / -37.8
**END ZONE IS DEFINED AS AN AREA WITHIN 6' FROM THE EDGE OF THE BUILDING		

STANDARD WINDOWS AND DOORS WILL GENERALLY FALL INTO THE 10 TO 20 SQ. FT. CATEGORY.
STANDARD DOUBLE SLIDING GLASS DOOES WILL GENERALLY FALL INTO THE 20 TO 50 SQ. FT. CATEGORY.
STANDARD DOUBLE GARAGE DOORS WILL GENERALLY FALL INTO THE 50 TO 100 SQ. FT. CATEGORY

WATERPROOFING FOR THIS BUILDING IS THE SOLE RESPONSIBILITY OF THE BUILDER/CONTRACTOR/ARCHITECT, HENCE NO DETAILS OF FLASHING, FLOOR, SLOPE AND STEP, NOR ANY OTHER WATERPROOFING MEASURES HAVE BEEN INCLUDED IN OUR DRAWINGS. IF SLOPE AND FLOOR STEPS ARE SHOWN ON OUR DRAWINGS, THEY SHALL BE USED ONLY AS A REFERENCE. FLOOR SLOPE AND STEPS SHALL FOLLOW ARCHITECTURAL DRAWINGS.

FASTENER SCHEDULES:

ALL NAILS ARE RING SHANK NAILS, UNLESS NOTED OTHERWISE.

SCHEDULED FASTENER

8d RINK SHANK NAIL (0.131 x 2 1/2")	12d RINK SHANK NAIL (0.148 x 3 1/4")
10d RING SHANK NAIL (0.148 x 3")	16d RING SHANK NAIL (0.162 x 3 1/2")

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH ARCHITECTS, INC. and may not be used in whole or in part for any purpose whatsoever without the express written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 - 407-677-5565 Fax 407-730-2999
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 26652

ALABAMA LICENSED No. 26652 PROFESSIONAL ENGINEER
4/26/2022

THE ROBERT MADISON
MADISON, ALABAMA

Drawn:	CW
Checked:	CW
Approval:	MX
Date:	02-20-22
Project #:	XXX-XXX

GENERAL NOTES

CS1.01

PLOTTED:

CONNECTOR SCHEDULE
SIMPSON

#	SIMPSON OR EQUAL	FASTENERS	UPLIFT(lbs.)	WOOD TO:	USP
1	H10	(8) 8d	990	WOOD	N/A
2	HTS20	(24) 10d x 1-1/2	1450	WOOD	HTW20
3	LTS12	(12) 10d x 1-1/2	775	WOOD	LTW12
4	H3	(4) 8d	455	WOOD	RT7
5	LTT20B	(10) 12d INTO STUDS	1750 (NAILS)	CONCRETE, WOOD	LTS20B
6	HTT16	(18) 12d	4175 (NAILS)	CONCRETE, WOOD	HTT16
7	SP-1 SP-4	(10) 10d (6) 10d x 1-1/2	585 735	WOOD (BOTT OF STUD) WOOD (TOP OF STUD)	SPT22 SPT4
7	THA/THAC TYP	PER SIMPSON CATALOG	PER SIMPSON CATALOG	SELECTION BASE ON TRUSS WIDTH AND HEIGHT	MSH TYP
8	CS16	(22) 10d	1650	11" MIN AT EA END FOR WOOD	RS150
9	MAS	(6) 10d x 1-1/2	1005	SLAB, STEMWALL	FA3
10	HCP2 HCP4	(12) 10d x 1-1/2 (16) 10d	605 1000	FOR 2x MEMBER FOR 4x MEMBER	N/A N/A
11	A35	(12) 8d x1 1/2	450 SHEAR	WOOD	MPA1
12	CC44, ECCU44 CC66, ECCU66	(4) 5/8d BOLTS (6) 5/8d BOLTS	1465 (UPLIFT) 3660 (UPLIFT)	ECCU44 AT BEAM END ECCU66 AT BEAM END	KCC44, KECCU44 KCC66, KECCU66
13	PC/EPC TYP	PER SIMPSON CATALOG	PER SIMPSON CATALOG	SELECTION BASE ON POST AND BEAM WIDTH	PCM/EPCM TYP
14	ECCLL44 ECCLL66	BOLTS AS REQ	1465 (UPLIFT) 3660 (UPLIFT)	ECCLLU44 FOR 4x4 POST ECCLLU66 FOR 6x6 POST	KECCLL44 KECCLL66
15	ABU44 ABU66	(12) 12d 5/8 ANCHOR BOLT	2200	ABU44 FOR 4x4 POST ABU44 FOR 4x4 POST	PAU44 PAU66
16	HUC410	(18) 12d FOR WOOD	1510	CONCRETE, MASONRY, WOOD FOR 4x10 BM	HD410IF
17	HUC412	(22) 12d FOR WOOD	1510	CONCRETE, MASONRY, WOOD FOR 4x12 BM	HD412IF
18	LUS TYP	PER SIMPSON CATALOG	PER SIMPSON CATALOG	LUS24 FOR 2x6, LUS26 FOR 2x8, LUS28 FOR 2x10, ETC.	JUS TYP

NOTE: USE TRUSS SHOP DRAWINGS TO DETERMINE UPLIFT REQUIREMENTS. PROVIDE TRUSS ANCHOR THAT PROVIDES AN UPLIFT CAPACITY EQUAL TO OR GREATER THAN THE UPLIFT INDICATED ON THE TRUSS SHOP DRAWINGS. INSTALL ALL TRUSS ANCHORS PER THE MANUFACTURER'S REQUIREMENTS.

SHEARWALL SCHEDULE

TYPE	SHEATHING	SHEATHING NAILING	FND CONN EACH END OF WALL				FND SOLE PLATE ATTACHMENT
	FND-ROOF	FND-ROOF	CONNECTOR	FND BOLT-12" EMBED DBL NUT EA END	ATTACH TO STUDS	REQ'D STUDS AT END OF WALL	
1	1/2" C-DX PLYWOOD *1	8d NAILS @ 4" O.C.	HD5B	3/4" DIA	(2) 3/4" DIA	(2) 2x6 OR WD POST	1/2" DIAx 7" EMB. A. BOLTS @ 32" O.C.
2	5/8" GYPSUM WALLBOARD	6d COOLER NAILS @ 6" O.C.	HD5B	3/4" DIA	(2) 3/4" DIA	(3) 2x6	1/2" DIAx 7" EMB. A. BOLTS @ 32" O.C.

*1 SHEATH EXTERIOR FACE WITH PLYWOOD SCHEDULED, AND THE INTERIOR FACE OF STUDS AS SPECIFIED IN THE GENERAL NOTES FOR INTERIOR WALLS.

NOTES:

1 ALL HD AND CS FASTENERS ARE AS MANUFACTURED BY THE SIMPSON STRONG-TIE COMPANY, INC, OR EQUAL.

2 WHERE SCHEDULED ADDITIONAL STUDS AT THE ENDS OF SHEAR WALLS ARE INTERRUPTED AT TRUSS BEARING, PROVIDE SOLID BLOCKING IN THE TRUSS SPACE TO MATCH THE STUDS SCHEDULED FOR THE LOWER FLOOR.

3 WHERE SCHEDULED SHEATHING CANNOT EXTEND FULL HEIGHT OF WALL, PROVIDE SHEATHING OR BLOCKING BETWEEN FLOOR TRUSSES AT ALL SHEARWALLS.


4 SHEATHING SHALL EXTEND FULL HEIGHT OF SHEARWALLS. STAGGER SHEATHING HORIZONTAL JOINTS SO THEY DO NOT FALL AT HORIZONTAL JOINT BETWEEN DOUBLE TOP PLATES.

5 WHEREVER THE SHEATHING OF A SHEAR WALL IS INTERRUPTED (I.E. BY AN INTERSECTING WALL) IN THE VERTICAL PLANE, THE SCHEDULED "ADD'L STUD AT END OF WALL" AND HOLDDOWN ANCHORS SHALL BE PROVIDED AT THE END OF THE SHEATHING (ONE EACH SIDE OF THE INTERRUPTION). THE QUANTITY OF SHEARWALL CALLOUTS ON THE PLANS MAY NOT ACCURATELY REFLECT THE NUMBER OF HOLDDOWNS REQUIRED BECAUSE OF THIS. THE CONTRACTOR MUST FIRST DETERMINE WHERE THE SHEARWALL SHEATHING WILL BE INTERRUPTED BEFORE DETERMINING THE NUMBER HOLDDOWNS REQUIRED.


6 WHERE BOLTS ARE CALLED OUT FOR HOLDDOWN ANCHORS, THE BOLTS SHALL BE THROUGH BOLTS CONFORMING TO ASTM A307.

7 7/16" O.S.B. MAY BE USED IN LIEU OF THE 1/2" C-DX PLYWOOD SHEATHING.


8 ANCHOR BOLTS SHALL ALL HAVE 3" HOOKS. A36 ALL THREAD RODS, DRILLED AND EPOXY GROUTED INTO FOOTINGS, MAY BE SUBSTITUTED FOR ANCHOR BOLTS CAST IN PLACE. ALL THREAD RODS SHALL HAVE SAME EMBEDMENT DEPTH AS ANCHOR BOLTS.



2 TYP. HOLDOWN ARRAGEMENTS AT CORNER
SCALE 3/4" = 1'-0"




1 ROOF SHEATHING LAYOUT
SCALE N. T. S.



1. ALL HORIZONTAL & VERTICAL JOINTS SHALL OCCUR OVER FRAMING & SHALL BE ATTACHED IN THE SPACING SHOWN ON SHEARWALL SCHEDULE @ SHEARWALLS. SOLID 2X BLOCKING OR FRAMING MEMBER SHALL BE AT ALL PANEL EDGES.

2. FOLLOW SHEATHING ORIENTATION DIAGRAM (BELOW). BOTTOM PLATE OF FIRST FLOOR FRAMING SHALL BE ATTACHED TO FOUNDATION WITH MAS CONNECTORS OR ANCHOR BOLTS AS SCHEDULED.

4 PLYWOOD/OSB SHEATHING JOINT LOCATION
SCALE 3/4" = 1'-0"



3 SECTION
SCALE 3/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN

REVISION HISTORY

No.	Date	Description

© 2021 These drawings, and the ideas and designs incorporated herein, as an instrument of service are and shall remain the property of Fugleberg Koch and are not to be used in whole or part for any other project without the written authorization of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
TO THE BEST OF MY KNOWLEDGE, THE BUILDING DESIGN PLANS AND SPECIFICATIONS COMPLY WITH BUILDING STRUCTURAL DESIGN CODE. THE SIGNING AND SEALING OF THE PLANS AND SPECIFICATIONS ARE ONLY FOR THE BUILDING'S STRUCTURAL COMPONENTS AFFECTED BY WIND, LIVE AND GRAVITY LOADS.
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 (407) 730-2999 Fax
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 26652

ALABAMA LICENSED No. 28652 PROFESSIONAL ENGINEER
11/26/2021

Drawn:	CW
Checked:	CW
Approval:	MK
Date:	02-20-22
Project #:	XXX-XXX

THE ROBERT MADISON
MADISON, ALABAMA


SHEAR SCHEDULE AND DETAILS

CS1.02

PLOTTED:

PLAN NOTES:

1. SEE GENERAL NOTES ON SHEETS CS1.01 & CS1.02.
2. DO NOT SCALE DRAWINGS. SEE ARCH'L. DRAWINGS FOR ADDITIONAL DIMENSIONS NOT SHOWN, VERIFY ALL DIMENSIONS WITH ARCH'L. DRAWINGS PRIOR TO START OF CONSTRUCTION. IF DISCREPANCIES SHOULD OCCUR – CONTACT THE ARCHITECT IN WRITING FOR CLARIFICATION BEFORE PROCEEDING.
3. 4" (TOTAL) CONCRETE SLAB REINFORCED WITH 6x6–W1.4xW1.4 W.W.F. OVER 10 MIL VAPOR BARRIER ON COMPACTED SUBGRADE. COORDINATE ALL SLAB SLOPES, DEPRESSIONS AND LIMITS THERE OF WITH ARCH'L. DRAWINGS (FOR ACTUAL TOP OF SLAB ELEVATIONS, SEE ARCH'L. AND / OR CIVIL DRAWINGS)
4. PRIOR TO CONCRETE PLACEMENT PROVIDE TERMITE SOIL TREATMENT PER LOCAL BUILDING CODE.
5. ◯ INDICATES WOOD STUD SHEAR WALL TYPE, AND SHADING INDICATES EXTENT OF SHEAR WALL. SEE THE SHEAR WALL SCHEDULE ON SHEET CS1.02 FOR SHEAR WALL INFORMATION.
6. THE MAX. SPACING OF CONTROL JOINT FOR ENCLOSURE SPACE SHALL BE 20'–0" O.C., AND FOR OPEN SPACE SHALL BE 8'–0" O.C. COORD. W/ FLOOR COVERING PLACEMENT. SEND SUBMITTAL TO ARCHITECT FOR REVIEW.
7. SEE ARCH'L. DRAWINGS FOR LOCATIONS / LIMITS AND CONSTRUCTION INFORMATION OF INTERIOR NON–BEARING PARTITION WALLS NOT SHOWN ON PLAN. SEE GENERAL NOTES.
8. COORDINATE ALL SLAB (TOPPING) SLOPES AND DEPRESSIONS WITH ARCH'L. DRAWINGS. (FOR ACTUAL TOP OF SLAB ELEVATIONS, SEE ARCH'L. DRAWINGS)
9. SEE MECHANICAL DRAWINGS FOR LOCATION (ON PLANK) OF MECHANICAL UNITS. H.C. MANUFACTURER / SUPPLIER TO DESIGN FOR UNIT WEIGHT. AS REQUIRED VERIFY WEIGHTS WITH MECHANICAL DRAWINGS.
10. DIMENSIONS ARE FOR EDGE OF SLAB. SEE DETAILS FOR CLARIFICATION.



1 FOUNDATION PLAN
SCALE: 3/16" = 1'–0"

FOOTING SCHEDULE		
MARK	SIZE WIDTH x LENGTH x DEPTH	REINFORCEMENT BOTTOM
WF–1.33A	1'–4"xCONT.x12"	(2)–#5's CONT.
WF–1.5A	2'–0"xCONT.x12"	(3)–#5's CONT. #5's @ 48" O.C. TRANSVERSE
WF–1.5	1'–6"xCONT.x2'–2"	(3)–#5's CONT. #5's @ 48" O.C. TRANSVERSE
F–2.5	2'–6"x2'–6"x2'–2"	(3)–#5's EA WAY
F–3.0	3'–0"x3'–0"x2'–2"	(4)–#5's EA WAY
F–3x5	3'–0"x5'–0"x2'–2"	(4)–#5's EA WAY

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN
1	04/15/22	PERMIT SUBMISSION

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH + ALDOSH PA, and are issued only for the specific project noted on these drawings. Any reproduction, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fugleberg koch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
TO THE BEST OF MY KNOWLEDGE, THE CALCULATIONS AND SPECIFICATIONS SHOWN + WITH BUILDING STRUCTURAL DESIGN CODE, THE DESIGN + AND SEALING OF THE PLANS AND SPECIFICATIONS ARE ONLY FOR THE BUILDING'S STRUCTURAL COMPONENTS AFFECTED BY WIND, LIVE AND GRAVITY LOADS.
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 – 407–677–5565 Fax 407–730–2999
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 26652

ALABAMA LICENSED No. 26652 PROFESSIONAL ENGINEER
4/26/2022

THE ROBERT MADISON
MADISON, ALABAMA

Drawn:	CW
Checked:	CW
Approval:	MX
Date:	02-20-22
Project #:	XXX-XXX


FOUNDATION PLAN

CS2.01

PLOTTED:

PLAN NOTES:

1. SEE GENERAL NOTES ON SHEET CS1.01 & CS1.02.
2. DO NOT SCALE DRAWINGS. SEE ARCH'L. DRAWINGS FOR ADDITIONAL DIMENSIONS NOT SHOWN, VERIFY ALL DIMENSIONS WITH ARCH'L. DRAWINGS PRIOR TO START OF CONSTRUCTION. IF DISCREPANCIES SHOULD OCCUR – CONTACT THE ARCHITECT IN WRITING FOR CLARIFICATION BEFORE PROCEEDING.
3. SEE ARCH'L. DRAWINGS FOR LOCATIONS/LIMITS AND CONSTRUCTION INFORMATION OF INTERIOR NON-BEARING PARTITION WALLS NOT SHOWN ON PLAN. SEE GENERAL NOTES (SHEET CS1.01) FOR ADDITIONAL WALL FRAMING INFORMATION.
4. PROVIDE WOOD HEADER OVER ALL OPENINGS IN WOOD WALLS (COORD. EXACT SIZE, LOCATION AND ELEVATIONS WITH ARCH'L. DRAWINGS) IF NO HEADER TYPE HAS BEEN CALL-OUT ON PLAN, PROVIDE WOOD HEADER BASED ON HEADER SCHEDULE SHOWN ON CS1.01 SHEET.
5. PRE-ENGINEERED WOOD TRUSSES & MISCELLANEOUS WOOD FRAMING SPACED AT 24" O.C.(MAX).
6. O.B. INDICATES OVER-BUILT PRE-ENG. TRUSS.
7. G.T. INDICATES GIRDER TRUSS.
8. THE REQUIRED NUMBER OF FASTENERS FOR CONNECTORS SUCH AS NAILS TO WOOD MEMBERS, SEE SIMPSON CATALOG.
9. SEE THE GENERAL NOTES FOR ROOF SHEATHING INFORMATION, AND FOR WOOD TRUSS TYPES.
10. TRUSS ENGINEER TO DESIGN TRUSS TO INCORPORATE LOADS FROM MECHANICAL UNITS.
11. PROVIDE MIN. DOUBLE WOOD STUDS UNDRE WOOD HEADER, WOOD BEAM, F.G.T., G.T. TO THE FTG. U.N.O.
12. PROVIDE L 4x4x1/4 STEEL FOR BRICK VENEER OPENING WITH 4" BEARING MINIMUM, AND ATTACH L4x4x1/4 TO HEADER AND WOOD STUDS BEHIND WITH 1/2 DIA x 5" LG LAG SCREWS @ 32" O.C.
13. PROVIDE HORIZONTAL BRICK TIES @ 16" O.C. AND VERTICAL BRICK TIES @ 24" O.C.



1 ROOF FRAMING PLAN

SCALE: 3/16" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project cited on these drawings. Any reproduction, revision, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-8595
www.fuglebergkoch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
TO THE BEST OF MY KNOWLEDGE, THE BUILDING DESIGN PLANS AND SPECIFICATIONS COMPLY WITH BUILDING CODE REQUIREMENTS AND ACCEPTED ENGINEERING PRACTICE. THE DESIGNS OF THE PLANS AND SPECIFICATIONS ARE ONLY FOR THE BUILDING'S STRUCTURAL COMPONENTS AFFECTED BY WIND, LIVE AND GRAVITY LOADS.
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 – 407-677-5565 Fax 407-730-2999
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 26652


ALABAMA LICENSED No. 26652 PROFESSIONAL ENGINEER
11/24/2021

THE ROBERT MADISON	Drawn: CW
MADISON, ALABAMA	Checked: CW
	Approval: MX
	Date: 02-20-22
	Project #: XXX-XXX


ROOF FRAMING PLAN

CS3.01


PLOTTED:




1 FOOTING AT BRICK FACING
SCALE 3/4" = 1'-0"



1B FOOTING w/o BRICK FACING
SCALE 3/4" = 1'-0"




2 SECTION
SCALE 3/4" = 1'-0"




3 DEPRESSED SLAB DETAIL
SCALE 3/4" = 1'-0"


VERIFY ALL MIN. FOOTING DEPTHS W/ SOIL REPORT REQUIREMENTS.



4 SECTION
SCALE 3/4" = 1'-0"




5 SECTION
SCALE 3/4" = 1'-0"



CORNERS INTERSECTIONS

6 TYP. HORIZ. REINF'S. AT FTGS.
SCALE 3/4" = 1'-0"




CONTROL JOINT CONSTRUCTION JOINT


NOTE:

1. CONSTRUCTION JOINTS MAYBE USED IN LIEU OF CONTROL JOINTS.
2. JOINT PLACEMENT REQUIREMENTS:
   FOR INCLOSED / INTERIOR AREAS. 20'-0" O.C. (MAX.) EACH WAY
   FOR OUTSIDE / EXTERIOR AREAS. 8'-0" O.C. (MAX.) EACH WAY
   WHERE TOP OF SLAB SURFACES ARE TO BE FINISHED WITH TILE – GENERAL CONTRACTOR IS TO COORDINATE JOINT LOCATIONS WITH THAT OF TILE MORTAR JOINTS.


7 TYPICAL CONTROL JOINT DETAIL
SCALE 3/4" = 1'-0"



8 SECTION
SCALE 3/4" = 1'-0"



9 SECTION
SCALE 3/4" = 1'-0"



10 SECTION
SCALE 3/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN

REVISION HISTORY

No.	Date	Description

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
TO THE BEST OF MY KNOWLEDGE, THE BUILDING DESIGN PLANS AND SPECIFICATIONS COMPLY WITH BUILDING STRUCTURAL DESIGN CODE. THE SIGNING AND SEALING OF THE PLANS AND SPECIFICATIONS ARE ONLY FOR THE BUILDING'S STRUCTURAL COMPONENTS AFFECTED BY WIND, LIVE AND GRAVITY LOADS.
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 (407-730-2999 Fax)
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 26652

ALABAMA LICENSED No. 26852 PROFESSIONAL
4/28/2022

THE ROBERT MADISON
MADISON, ALABAMA


Drawn:	CW
Checked:	CW
Approval:	MK
Date:	02-20-22
Project #:	XXX-XXX

SECTIONS AND DETAILS


CS5.01

PLOTTED:


THESE PLANS, and are issued only for the specific project noted on these drawings. Any reproduction, revisions, or modifications of these documents without the expressed written consent of Fuglebergh Koch is prohibited by law.




1 TYPICAL STUD WALL HOLDOWN
SCALE 3/4" = 1'-0"




2 SECTION
SCALE 3/4" = 1'-0"




3 TYP. TRUSS TO FRAME WALL
SCALE 3/4" = 1'-0"



3B SECTION
SCALE 3/4" = 1'-0"




4 TYPICAL SECTION AT GABLE END TRUSSES
SCALE 3/4" = 1'-0"



5 SECTION
SCALE 3/4" = 1'-0"

"L" BRACING REQUIREMENTS


STUD SPACING	NO "L" BRACE	(1) 2x4 "L" BRACE	(2) 2x4 "L" BRACE	(2) 2x6 "L" BRACE
16"	0'-0" - 4'-5"	4'-5" - 8'-0"	8'-0" - 11'-5"	11'-5" - 15'-6"
24"	0'-0" - 4'-0"	4'-0" - 6'-10"	6'-10" - 8'-10"	8'-10" - 12'-8"




6 STANDARD GABLE END BRACING DETAIL
SCALE 3/4" = 1'-0"

NOTES:


1. THIS DETAIL APPLIES AT ALL EXTERIOR WALLS AND INTERIOR SHEARWALLS.



7 TYP. TOP PLATE SPLICE
SCALE 3/4" = 1'-0"



8 STRAP OVER FRAMING
SCALE N. T. S.



9 SECTION
SCALE 3/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproduction, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
TO THE BEST OF MY KNOWLEDGE THE BUILDING DESIGN PLANS AND SPECIFICATIONS COMPLY WITH BUILDING STRUCTURAL DESIGN CODE. THE SIGNING AND SEALING OF THE PLANS AND SPECIFICATIONS ARE ONLY FOR THE STRUCTURAL COMPONENTS AFFECTED BY WIND, LIVE AND GRAVITY LOADS.
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 — 407-677-5565 Fax 407-730-2999
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 29652

ALABAMA LICENSED No. 29652 PROFESSIONAL ENGINEER
4/26/2022


Drawn:	CW
Checked:	CW
Approval:	MX
Date:	02-20-22
Project #:	XXX-XXX

THE ROBERT MADISON
MADISON, ALABAMA


SECTIONS AND DETAILS

CS5.02


PLOTTED:




1 REAR PARTAL ELEVATIION
SCALE N.T.S.




3 TYP. TRUSS BRACING AT PERPENDICULAR SHEAR WALL
SCALE 3/4" = 1'-0"




3 TYP. SHEARWALL SECTION AT ROOF
SCALE 3/4" = 1'-0"




10 SECTION
SCALE 3/4" = 1'-0"



11 SECTION
SCALE 3/4" = 1'-0"



12 SECTION
SCALE 3/4" = 1'-0"



13 EXTERIOR SHEARWALL SECTION @ ROOF
SCALE 3/4" = 1'-0"

MINIMUM WALL AND HEADER STUD REQUIREMENTS

UPLIFT CONNECTION REQUIREMENT AT POINTS 'A'(TOP AND BOTTOM OF HEADER STUDS. UPLIFT CONNECTION IS REQUIRED AT EACH END OF HEADER AND AT BOTTOM OF HEADER STUDS IN ADDITION TO CONNECTORS AT WALL STUDS

		MAXIMUM HEADER SPAN (FEET)					
		3	6	9	12	15	
		NUMBER OF HEADER STUDS SUPPORTING END OF HEADER					
		1 *	2	2	2	2	
UNSUPPORTED WALL HEIGHT	STUD SPACING	NUMBER OF FULL LENGTH STUDS AT EACH END OF HEADER					
10'-6" OR LESS	16"	2	2	3	3	3	
GREATER THAN 10'-6"	16"	2	4	4	6	6	

*THE HEADER STUD SHALL NOT BE REQUIRED IF THE HEADER IS SUPPORTED BY A SUITABLE FRAMING ANCHOR

14 HEADER AND BEAM STUD SCHEDULE
SCALE 3/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	09/30/21	SCHEMATIC DESIGN

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AADG0103, and are issued only for the specific project noted on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103
CONSULTANT

ASE ENGINEERING SERVICES, INC.
STRUCTURAL DESIGN GROUP
TO THE BEST OF MY KNOWLEDGE, THE BUILDING DESIGN PLANS AND SPECIFICATIONS COMPLY WITH BUILDING STRUCTURAL DESIGN CODE. THE SIGNING AND SEALING OF THE PLANS AND SPECIFICATIONS ARE ONLY FOR THE BUILDING GRAVITY LOADS. COMPONENTS AFFECTED BY WIND, LIVE
10244 East Colonial Drive, Suite 202
Orlando, Florida 32817 — 407-677-5565 Fax 407-730-2999
Certificate of Authorization No. 25873
Wenyi Hu P.E.
Alabama No. 26652

ALABAMA LICENSED No. 26652 PROFESSIONAL ENGINEER
4/26/2022

THE ROBERT MADISON	Drawn: CW
MADISON, ALABAMA	Checked: CW
	Approved: MX
	Date: 02-20-22
	Project #: XXX-XXX

SECTIONS AND DETAILS

CS5.03

PLOTTED:

ABBREVIATIONS

ABV	ABOVE
ADJ	ADJUSTABLE
AF	AIRFOIL
AFF	ABOVE FINISHED FLOOR
AC	AIR CONDITIONER
ACU	AIR CONDITIONING UNIT
AHU	AIR HANDLING UNIT
AP	ACCESS PANEL
BAS	BUILDING AUTOMATION SYSTEM
BI	BACKWARD INCLINE
BLDG	BUILDING
BHP	BRAKE HORSEPOWER
BTUH	BRITISH THERMAL UNIT PER HOUR
BDD	BACKDRAFT DAMPER
CD	CONDENSATE DRAIN
CFM	CUBIC FEET PER MINUTE
CLG	CEILING
CHW	CHILLED WATER
CHWR	CHILLED WATER RETURN
CHWS	CHILLED WATER SUPPLY
CWR	CONDENSER WATER RETURN
CWS	CONDENSER WATER SUPPLY
CONC	CONCRETE
COND	CONDENSATE
CONT	CONTINUOUS
CO	CARBON MONOXIDE
COP	COEFFICIENT OF PERFORMANCE
CU	CONDENSING UNIT
DB	DRYBULB
DWDI	DOUBLE WIDTH, DOUBLE INLET
DWGS	DRAWINGS
DX	DIRECT EXPANSION
EF	EXHAUST FAN
EXH	EXHAUST
EA	EACH
EAT	ENTERING AIR TEMPERATURE
EER	ENERGY EFFICIENCY RATIO
ELECT	ELECTRICAL
ENT	ENTERING
EQ	EQUAL
ER	EXHAUST REGISTER
EWT	ENTERING WATER TEMPERATURE
FC	FORWARD CURVED
FCU	FAN COIL UNIT
FD	FIRE DAMPER
FL	FLOOR
FLEX	FLEXIBLE CONNECTOR OR DUCT
FPM	FEEL PER MINUTE
F/S	COMBINATION FIRE AND SMOKE DAMPER
FT. H_2O	FEET WATER GAUGE
F	DEGREES FAHRENHEIT
GA	GAUGE
GAL	GALLON
GALV	GALVANIZED
GPM	GALLONS PER MINUTE
HP	HORSEPOWER
HTWR	HIGH TEMPERATURE HOT WATER RETURN
HTWS	HIGH TEMPERATURE HOT WATER SUPPLY
HW	HOT WATER
HWR	HOT WATER RETURN
HWS	HOT WATER SUPPLY
HVAC	HEATING VENTILATION AND AIR CONDITIONING
HV	HEATING AND VENTILATING
IN.WG	INCHES WATER GAUGE
KW	KILOWATTS
LAT	LEAVING DIFFUSER
LD	LINEAR DIFFUSER
LWT	LEAVING WATER TEMPERATURE
MAX	MAXIMUM
MBH	1000 X BTUH
MIN	MINIMUM
MD	MANUAL VOLUME DAMPER
M	MOTORIZED DAMPER
MZ	MULTI-ZONE
N.T.S.	NOT TO SCALE
OA	OUTSIDE AIR
OBMVD	OPPOSED BLADE MANUAL VOLUME DAMPER
OPD	OPEN DRIP PROOF
PROP	PROPELLER
PCR	PRE-CONDITIONED AIR SYSTEM RETURN WATER
PCS	PERCENT
PD	PRESSURE DROP
PERF. PL.	PERFORATED PLATE
PLBG	PLUMBING
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAUGE
RA	RETURN AIR
RD	RADIATION DAMPER
REG	REGISTER
REQ'D	REQUIRED
RG	RETURN AIR GRILLE
RH	RELATIVE HUMIDITY
RPM	REVOLUTIONS PER MINUTE
RR	RETURN AIR REGISTER
RTU	ROOFTOP UNIT
SA	SUPPLY AIR
SF	SUPPLY FAN
SD	SMOKE DETECTOR
SDMP	SMOKE DAMPER
SQ.FT.	SQUARE FOOT
SR	SUPPLY REGISTER
STR	STARTER
SWSI	SINGLE WIDTH, SINGLE INLET
SZ	SINGLE ZONE
TEFC	TOTALLY ENCLOSED FAN COOLED
TEMP	TEMPERATURE
TG	TRANSFER GRILLE
T/O	TRANSFER OPENING ABOVE CEILING
T'STAT	THERMOSTAT
TYP	TYPICAL
VFDC	VARIABLE FREQUENCY DRIVE
VAV	VARIABLE AIR VOLUME
VS	VARIABLE SPEED
W	WATTS
W/	WITH
W/O	WITHOUT
WB	WETBULB
ZD	ZONE DAMPER

GENERAL NOTES

1. INSTALL EQUIPMENT AND MATERIALS IN COMPLIANCE WITH MANUFACTURER'S MINIMUM CLEARANCE REQUIREMENTS AND RECOMMENDATIONS.
2. COMPLY WITH THE LATEST EDITIONS OF NFPA AND THE LATEST ADOPTED EDITION INTERNATIONAL BUILDING CODE (MECHANICAL, PLUMBING, GAS AND ENERGY CONSERVATION).
3. ALL MATERIALS SHALL FIT THE SPACE AVAILABLE. VERIFY DIMENSIONS AND CLEARANCES ON BUILDING PLANS PRIOR TO COMMENCING WORK.
4. AN INDEPENDENT TEST AND BALANCE CONTRACTOR (TABC) SHALL BE HIRED BY THE GENERAL CONTRACTOR.
5. TABC IS RESPONSIBLE FOR TESTING AND BALANCING OF AIR SYSTEMS IN ACCORDANCE WITH AABC GUIDELINES. A TEST AND BALANCE REPORT SHALL BE SUBMITTED TO THE ARCHITECT FOR APPROVAL.
6. PROVIDE 45 DEGREE BRANCH TAKE-OFF PER SMACNA FIG. 2-8 ON ALL RECTANGULAR DUCT TAKE-OFFS.
7. ALL DUCTWORK TAKE-OFFS AND/OR BRANCH DUCTWORK SHALL BE PROVIDED WITH BALANCING DAMPERS (REMOTE IF IN HARD CEILING AREAS).
8. CONTRACT SHALL MAINTAIN ALL RATED FIRE, SMOKE AND MEMBRANE ASSEMBLIES (EVEN IF NOT NOTED ON PLANS). PROVIDE AND INSTALL FIRE/SMOKE/RADIATION DAMPERS AT ALL RATED PENETRATIONS AND PROVIDE DUCT MOUNTED HINGED ACCESS DOORS. THIS APPLIES FOR ALL FIRE/SMOKE/RADIATION DAMPERS.
9. CONTRACTOR SHALL COORDINATE VOLTAGE AND PHASE OF EACH PIECE OF EQUIPMENT WITH THE ELECTRICAL CONTRACTOR PRIOR TO ORDERING AND SHALL COORDINATE WITH ALL OTHER TRADES PRIOR TO OR INSTALLING EQUIPMENT AND MATERIALS.
10. COORDINATE ALL HVAC SYSTEM DRAWINGS WITH EXISTING/NEW TRUSS TO AVOID INTERFERENCE BETWEEN MECHANICAL SYSTEMS AND ROOF STRUCTURE. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH TRUSS INTERFERENCE THAT OCCURS IN THE FIELD DURING CONSTRUCTION. COORDINATE IN ADVANCE. DUCT SIZES MAY BE REVISED TO FIT TRUSS SYSTEM SO LONG AS THE EQUIVALENT INSIDE CROSS SECTIONAL AREA IS NOT DECREASED.
11. GAUGES AND CONSTRUCTION FOR DUCTWORK SHALL CONFORM TO THE LATEST EDITION OF SMACNA'S HVAC DUCT CONSTRUCTION STANDARDS.
12. TRANSITION RECTANGULAR DUCTWORK ON BOTTOM AND SIDES. MAINTAIN TOP OF DUCTWORK LEVEL AND HIGH AS POSSIBLE. FLEXIBLE DUCT RUN-OUTS TO CEILING DIFFUSERS SHALL BE AS STRAIGHT AS POSSIBLE AND FREE OF SAGS AND KINKS. FLEX DUCT SHALL BE THE SAME SIZE AS THE DIFFUSER NECK IT SERVES.
13. ALL DUCT TRANSITIONS FROM SQUARE TO ROUND SHALL BE SMOOTH SQUARE TO ROUND TRANSITIONS. SPIN-IN FITTINGS AT THE END OF CAPPED DUCTS ARE NOT ACCEPTABLE. DUCT DIMENSIONS SHOWN ARE INSIDE CLEAR DIMENSIONS.
14. THE CONTRACTOR SHALL FULFILL ALL REQUIREMENTS OF THE CONTRACT DOCUMENTS AND SHALL COMPLETE THE WORK SHOWN ON THESE DRAWINGS. ALL SYSTEMS SHALL BE FINISHED, TESTED AND BALANCED, ADJUSTED, AND PROVEN TO BE FULLY OPERATIONAL AND USEABLE.
15. ADJUST ALL DIFFUSERS IN CORRIDORS OR WITHIN THREE (3) FEET OF A WALL TO PROVIDE 2-WAY OR 3-WAY BLOW AWAY FROM OR PARALLEL TO WALLS. ALL DIFFUSERS SHALL HAVE 4-WAY BLOW UNLESS NOTED OTHERWISE.
16. PORTIONS OF DUCTWORK VISIBLE THROUGH GRILLES AND REGISTERS IN FINISHED AREAS SHALL BE PAINTED FLAT BLACK.
17. ALL DAMPERS IN AND ABOVE CEILING SHALL BE ACCESSIBLE. CONTRACTOR SHALL COORDINATE ALL ACCESS PANELS IN CEILINGS OR WALLS WITH ARCHITECTURAL REFLECTED CEILING PLANS AND INTERIOR DRAWINGS FOR PROPER LOCATION.
18. MOUNT THERMOSTATS WHERE INDICATED ON PLANS 48" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE. IN HANDICAPPED ACCESSIBLE AREAS, MOUNT CONTROLS AT 48" (MAXIMUM) ABOVE FINISHED FLOOR.
19. COORDINATE DUCTWORK AND PIPING WITH PLUMBING, FIRE PROTECTION AND ELECTRICAL. MAKE OFFSETS AND TRANSITIONS TO COORDINATE WITH OTHER TRADES WITHOUT ANY ADDITIONAL EXPENSE TO THE CONTRACT.
20. SEAL ALL TRANSVERSE JOINTS AND FITTINGS WITH DUCT SEALER.
21. TRAP AND ROUTE CONDENSATE DRAINS LINES, FULL SIZE OF UNIT CONNECTION, AS INDICATED. SLOPE 1/8" PER FOOT.
22. ALTERNATE MANUFACTURERS AND MODELS WILL BE REVIEWED. THERE MAY BE ARCHITECTURAL, STRUCTURAL AND ELECTRICAL CHANGES RESULTING FROM THE ALTERNATES. THE COST OF IMPLEMENTING AND ENGINEERING THESE CHANGES SHALL BE BORNE BY THE MECHANICAL SUBCONTRACTOR.
23. PIPE AND DUCT ROUTING SHOWN IS SCHEMATIC. PROVIDE ANY ADDITIONAL OFFSETS AND FITTINGS, INCLUDING DIVIDED DUCTS, REQUIRED FOR PROPER INSTALLATION AND TO MAINTAIN CLEARANCES AS ENCOUNTERED IN THE FIELD.
24. COORDINATE CEILING MOUNTED AIR DEVICE LOCATION WITH REFLECTED CEILING PLAN AND OTHER TRADES.
25. ALL CONTROL WIRING AND CONDUIT SHALL COMPLY WITH NEC DIVISION 16 SPECIFICATIONS.
26. PROVIDE MATERIALS WHICH HAVE A FLAME SPREAD RATING OF 25 OR LESS AND A SMOKE DEVELOPED RATING OF 50 OR LESS WHEN TESTED IN ACCORD WITH ASTM E84.
27. SLEEVE AND FIRE STOP PENETRATIONS THROUGH FIRE RATED SYSTEMS TO MAINTAIN RATING OF SYSTEM. USE MINIMUM GALVANIZED STEEL GAUGE DUCT AS REQUIRED TO MAINTAIN RATING OF SYSTEM.
28. WHERE THE EXHAUST DUCT IS CONCEALED WITHIN THE BUILDING CONSTRUCTION, THE EQUIVALENT LENGTH OF THE DUCT SHALL BE IDENTIFIED ON A PERMANENT LABEL OR TAG. THE LABEL OR TAG SHALL BE LOCATED WITHIN 6 FEET OF THE EXHAUST DUCT CONNECTION.
29. CONTRACTOR TO ORDER ALL FIRE/SMOKE DAMPERS WITH INTEGRAL SMOKE DETECTORS AND END STOP INDICATOR OPTIONS. VERIFY VOLTAGE WITH ELECTRICAL DRAWINGS. IF BUILDING IS EQUIPPED WITH FIRE ALARM SYSTEM ALL FIRE/SMOKE DAMPERS WILL BE CONNECTED TO BUILDING FIRE ALARM SYSTEM.
30. ALL MECHANICAL EQUIPMENT SHALL BE THOROUGHLY CLEANED OF ALL DIRT, OIL, CONCRETE, ETC. ANY DENTS, SCRATCHES OR OTHER VISIBLE BLEMISHES SHALL BE CORRECTED AND THE APPEARANCE OF THE EQUIPMENT MADE "LIKE NEW" AND TO THE SATISFACTION OF THE ARCHITECT/ENGINEER. UPON COMPLETION, AND BEFORE FINAL ACCEPTANCE OF THE WORK, ALL DEBRIS, RUBBISH, LEFTOVER MATERIALS, TOOLS AND EQUIPMENT SHALL BE REMOVED FROM THE SITE. PROTECTION OF WORK UNTIL FINAL ACCEPTANCE: PROTECT ALL MATERIALS AND EQUIPMENT FROM DAMAGE, ENTRANCE OF DIRT AND CONSTRUCTION DEBRIS FROM THE TIME OF INSTALLATION UNTIL FINAL ACCEPTANCE. ANY MATERIALS AND EQUIPMENT WHICH ARE DAMAGED SHALL BE REPAIRED TO "AS NEW" CONDITION OR REPLACED AT THE DIRECTION OF THE ARCHITECT/ENGINEER. WHERE FACTORY FINISHES OCCUR AND DAMAGE IS MINOR, FINISHES MAY BE TOUCHED UP. IF, IN THE OPINION OF THE ARCHITECT/ENGINEER THE DAMAGE IS EXCESSIVE, FACTORY FINISH SHALL BE REPLACED TO "NEW" CONDITION.
31. DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT AND EXTENT OF WORK. EXACT LOCATIONS AND ARRANGEMENT OF MATERIALS AND EQUIPMENT SHALL BE DETERMINED, WITH THE ACCEPTANCE OF THE ARCHITECT/ENGINEER, AS WORK PROGRESSES TO CONFORM IN THE BEST POSSIBLE MANNER WITH THE SURROUNDINGS AND WITH THE ADJOINING WORK OF OTHER TRADES. WHERE LOCATIONS OF EQUIPMENT, DEVICES OR FIXTURES ARE CONTROLLED BY ARCHITECTURAL FEATURES, ESTABLISH SUCH LOCATIONS BY REFERRING TO DIMENSIONS ON ARCHITECTURAL DRAWINGS AND NOT BY SCALING DRAWINGS.
32. IN CASE OF DIFFERENCES BETWEEN DRAWINGS AND SPECIFICATIONS, OR WHERE DRAWINGS AND SPECIFICATIONS ARE NOT CLEAR OR DEFINITE, THE SUBJECT SHALL BE REFERRED TO ARCHITECT/ENGINEER FOR CLARIFICATION AND INSTRUCTIONS.
33. ANY INTERRUPTION OF EXISTING MECHANICAL AND ELECTRICAL SERVICES SHALL BE COORDINATED IN ADVANCE WITH THE OWNER'S REPRESENTATIVE. THIS INCLUDES, BUT IS NOT LIMITED TO, SERVICES PROVIDING CHILLED WATER, ELECTRICITY, OR OTHER CRITICAL SYSTEMS AS MAY BE PERTINENT TO THIS PARTICULAR PROJECT. SERVICE INTERRUPTION TIMES AND DURATION OF INTERRUPTION OF SERVICES SHALL BE DECIDED BY THE OWNER. PROVIDE APPROPRIATE PROVISIONS (SUCH AS ISOLATION SHUT-OFF VALVES, DAMPERS, END CAPS, AND SIMILAR ITEMS) AS NECESSARY TO ACCOMMODATE THE REQUIRED SERVICE INTERRUPTIONS. IF SHUTDOWNS CANNOT BE ACCOMMODATED, PROVIDE MEANS FOR "WET" TAPPING OR "HOT" TAPPING OF PIPING SYSTEMS.
34. ALL MAIN DUCTWORK SHOWN PER PLAN IS TO BE SHEET METAL OR DUCT BOARD. ALL DUCT BOARD INSTALLATIONS ARE TO BE APPROVED BY BUILDING OWNER PRIOR TO MATERIAL PURCHASE.
35. FIRE & FIRE/SMOKE DAMPERS ARE REQUIRED TO BE UL LISTED AND APPROVED FOR THE ASSEMBLIES LISTED ON THE ARCHITECTURAL DRAWINGS. THESE DAMPERS MUST ALSO BE REVIEWED AND APPROVED BY THE ARCHITECT PRIOR TO ORDERING.

ENERGY CALCULATION VALUES

ROOF:	R-38
WALLS:	R-21
WINDOWS:	
SHGC:	0.25
U VALUE:	U-0.30
VLT:	0.5
DOORS:	R-2.85
FLOORS:	R-10

NOTE:

THIS PROJECT HAS MET THE MINIMUM ENERGY CODE REQUIREMENTS AND HAS BEEN DESIGNED TO THE MINIMUM VALUES NOTED. ALL MATERIALS USED IN THE CONSTRUCTION OF THIS PROJECT MUST MEET OR EXCEED THE MINIMUM VALUES NOTED PER THE LATEST ADOPTED EDITION OF THE INTERNATIONAL BUILDING CODE AND INTERNATIONAL ENERGY CODE.

NOTE:

GENERAL NOTES ON THIS MECHANICAL SHEET ARE FOR GENERAL REFERENCE PURPOSES ONLY. ALL OF THESE NOTES MAY NOT BE USED FOR THIS PROJECT.

LEGEND

- SUPPLY DIFFUSER (4-WAY)
- RETURN OR OUTDOOR AIR GRILLE
- EXHAUST GRILLE
- SUPPLY DUCT UP SECTION (RECTANGULAR)
- RETURN DUCT UP SECTION (RECTANGULAR)
- EXHAUST DUCT UP SECTION (RECTANGULAR)
- SUPPLY DUCT DOWN SECTION (RECTANGULAR)
- RETURN DUCT DOWN SECTION (RECTANGULAR)
- EXHAUST DUCT DOWN SECTION (RECTANGULAR)
- SUPPLY DUCT UP SECTION (ROUND)
- SUPPLY DUCT DOWN SECTION (ROUND)
- LINEAR SLOT DIFFUSER
- EXISTING LINEAR SLOT DIFFUSER (LIGHT LINETYPE)
- A/B — RECTANGULAR DUCTWORK WITH TAKE-OFF, BALANCING DAMPER AND INSULATED FLEXIBLE ROUND DUCT. SAME SIZE AS DIFFUSER INLET UNLESS NOTED OTHERWISE. FIRST DIMENSION IS THAT OF SIDE SHOWN
- A ø — ROUND DUCTWORK
- CONICAL FITTING WITH DAMPER ON BRANCH CONNECTION TO RECTANGULAR MAIN (PROVIDE DAMPER IN LOW PRESSURE DUCTWORK ONLY)
- EXISTING DUCTWORK TO REMAIN (LIGHT LINETYPE)
- R — DUCT OFFSETS UP (RISE) IN DIRECTION INDICATED
- D — DUCT OFFSETS DOWN (DROP) IN DIRECTION INDICATED
- OPPOSED BLADE VOLUME DAMPER (OBD)
- MANUAL DAMPER
- FLEXIBLE DUCT CONNECTION
- FIRE/RADIATION DAMPER WITH ACCESS PANEL
- COMBINATION FIRE/SMOKE DAMPER WITH ACCESS PANEL
- EXISTING DUCTWORK TO BE REMOVED (DASHED LINETYPE)
- DUCT MOUNTED SMOKE DETECTOR PROVIDED AND WIRED BY ELECTRICAL CONTRACTOR AND INSTALLED IN DUCT BY MECHANICAL CONTRACTOR. REFER TO SPECIFICATIONS FOR CONTROL REQUIREMENTS.
- A-100 — AIR DEVICE TAG (MARK-CFM)
- SIDEWALL TRANSFER GRILLE
- SIDEWALL SUPPLY REGISTER
- SIDEWALL RETURN GRILLE OR OUTSIDE AIR LOUVER
- SIDEWALL EXHAUST GRILLE
- TS — WALL MOUNTED DDC TEMPERATURE SENSOR MOUNT 4'-0" ABOVE FINISHED FLOOR
- T — WALL MOUNTED THERMOSTAT MOUNT 4'-0" ABOVE FINISHED FLOOR
- C — WALL MOUNTED CO SENSOR MOUNT 4'-0" ABOVE FINISHED FLOOR
- H — WALL MOUNTED DDC HUMIDITY SENSOR MOUNT 4'-0" ABOVE FINISHED FLOOR
- H^S — WALL MOUNTED HUMIDISTAT SENSOR MOUNT 4'-0" ABOVE FINISHED FLOOR
- A/B — PHOTO DETAIL OR SECTION IDENTIFICATION TARGET A = DETAIL NUMBER B = SHEET NUMBER ON WHICH DETAIL IS LOCATED
- RD — RADIATION DAMPER INSTALLED IN AIR DEVICE
- RD — RADIATION DAMPER INSTALLED IN DUCT
- ELBOW WITH TURNING VANES

- X — REFERENCE NOTES
- X — REFERENCE NOTE – MULTI-DISCIPLINE SHEETS
- FLOW DIRECTION
- INDICATES POINT OF CONNECTION BETWEEN NEW AND EXISTING
- POINT OF DISCONNECT
- CWS — CONDENSER WATER SUPPLY PIPING
- CWR — CONDENSER WATER RETURN PIPING
- BCWS — BUILDING CONDENSER WATER SUPPLY PIPING
- BCWR — BUILDING CONDENSER WATER RETURN PIPING
- CHWS — CHILLED WATER SUPPLY PIPING
- CHWR — CHILLED WATER RETURN PIPING
- HWS — HEATING WATER SUPPLY PIPING
- HWR — HEATING WATER RETURN PIPING
- CD — CONDENSATE DRAIN PIPING
- R — REFRIGERANT PIPING
- FS — FLOW SENSOR
- SP — STATIC PRESSURE TRANSMITTER ASSEMBLY
- L=1/4W, MIN. 4" — RECTANGULAR BRANCH DUCT CONNECTION. (PROVIDE BALANCING DAMPER AT ALL BRANCH CONNECTIONS)
- TEE (PLAN, UP, DOWN)
- ELBOW (PLAN, UP, DOWN)
- VALVE
- TWO WAY MOTORIZED CONTROL VALVE
- THREE WAY MOTORIZED CONTROL VALVE
- PRESSURE REDUCING VALVE
- FLOW CONTROL VALVE
- BALL VALVE FOR PIPING 2-INCHES AND SMALLER, BUTTERFLY VALVE FOR PIPING 2-1/2 INCHES AND LARGER
- BUTTERFLY VALVE
- CHECK VALVE
- STRAINER
- BALANCE VALVE WITH INTEGRAL TAPS FOR CONNECTION OF DIFFERENTIAL PRESSURE METER. VALVE SHALL HAVE NAMEPLATE INDICATING WATER FLOW RATE VERSUS VALVE PRESSURE DROP
- A — AUTOMATIC FLOW CONTROL VALVE WITH INTEGRAL TEMPERATURE AND PRESSURE TEST PORTS
- UNION
- VENTURI FLOW METER
- PRESSURE AND/OR TEMPERATURE PORT
- THERMOMETER
- PRESSURE GAUGE WITH GAUGE COCK
- FLEXIBLE CONNECTION
- PRESSURE RELIEF VALVE
- OPENING IN WALL ABOVE CEILING
- AHU-3 — EQUIPMENT TYPE, MARK — EQUIPMENT TAG
- UC — 1" DOOR UNDER CUT. ARROW INDICATES DIRECTION OF FLOW
- FLEX DUCT

NOTE:

SYMBOLS SHOWN ON THIS MECHANICAL LEGEND ARE FOR REFERENCE PURPOSES ONLY. ALL OF THESE SYMBOLS MAY NOT BE USED FOR THIS PROJECT.

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2015 These documents and their contents are the property of FUGLEBERG KOCH - AADD02103, and are loaned only for the specific project noted on these drawings. Any reproductions, versions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL. 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

LICENSED ARCHITECT No. 13885 PROFESSIONAL BRIAN S. MARSHALL

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

SYMBOL LEGEND & GENERAL NOTES MECHANICAL

CHM0.01

GENERAL NOTES:

1. CONTRACTOR TO VERIFY ALL MECHANICAL EQUIPMENT SELECTED FITS WITHIN DESIGNATED SPACE SHOWN ON MECHANICAL PLANS AND PROVIDES THE CORRECT CLEARANCES REQUIRED BY THE MANUFACTURER.
2. CONTRACTOR SHALL COORDINATE VOLTAGE, PHASE AND REQUIRED MOCP FOR EACH PIECE OF EQUIPMENT WITH THE ELECTRICAL CONTRACTOR PRIOR TO ORDERING.
3. IF PRODUCTS/EQUIPMENT ARE VALUE ENGINEERED OR SUBSTITUTED IT IS THE CONTRACTORS RESPONSIBILITY TO FIELD COORDINATE ALL NEW PRODUCTS/EQUIPMENT REQUIREMENTS WITH OTHER DISCIPLINES/TRADES.

OUTSIDE AIR CALCULATIONS (AMENITIES AREA)

CLASSIFICATION	OCC. FACTOR OCCUPANCY/ 1000 SQFT. (PERSONS)	ASHRAE 62.1 VALUES PER TABLE 6.2.2.1 Rp	Ra	SPACE AREA (SQFT) Az	SPACE LOAD (PERSONS) Pz	OUTDOOR AIR REQUIRED (CFM)	OUTDOOR AIR SUPPLIED (CFM)
AHU-1.C							
GATHERING ROOM	120	5	0.06	787	28**	187.22	190
GAME ROOM	20	7.5	0.18	366	6**	110.88	115
CORRIDOR	–	–	0.06	79	–	4.74	5
AHU-2.C							
LOBBY	30	7.5	0.06	216	6	54.96	60
RECEPTION	30	5	0.06	205	6	42.3	45
OFFICE	5	5	0.06	142	3	23.52	25
CORRIDOR	–	–	0.06	59	–	3.54	5
MAIL KIOSK	2	10	0.12	422	1	60.64	65
WORK ROOM	5	5	0.06	94	2	15.64	20
TOTAL	–	–	–	2,370*	49	444.94	530

NOTES:
1. REQUIRED OUTDOOR VENTILATION AIR VALUES TAKEN FORM ASHRAE 62.1, TABLE 6.2.2.1.
   VENTILATION BREATHING ZONE FORMULA: Vbz = Rp * Pz + Ra * Az
   Pz = OCCUPANCY FACTOR * SPACE AREA
2. OUTSIDE AIR CALC. REFERENCES CHAPTER 15 OF THE 2020 EDITION OF THE OF THE FLORIDA BUILDING BUILDING CODE (MECHANICAL).

*AREA DOES NOT INCLUDE RESTROOMS.
**FIXED NUMBER OF SEATING PER PLAN.

AIR DEVICE SCHEDULE (AMENITIES AREA)

MARK	DESCRIPTION	FACE SIZE	NECK	MATERIAL	MANUFACTURER & MODEL NO.	NOTES
AA	LOUVERED FACE SUPPLY DIFFUSER – CEILING	14"x10"	SEE PLAN	STEEL	TRUAIRE 401	1.
AB	LOUVERED FACE SUPPLY DIFFUSER – CEILING	10"x6"	SEE PLAN	STEEL	TRUAIRE 401	1.
AC	SQUARE FACE DIFFUSER – SUPPLY	12"x12"	SEE PLAN	STEEL	TRUAIRE 170	1.
AD	LOUVERED FACE RETURN GRILLE	18"x18"	SEE PLAN	STEEL	TRUAIRE 170	1.
AE	LOUVERED FACE RETURN GRILLE	12"x12"	SEE PLAN	STEEL	TRUAIRE 170	1.

NOTES:
1. COORIDINATE SURFACE FINISHES WITH ARCHITECTURAL DRAWINGS.

FAN SCHEDULE (CLUBHOUSE)

MARK	AREA SERVED	TYPE	CFM	T.S.P.	HP/WATTS	RPM	VOLTS/PH	SONES	WEIGHT	MANUFACTURER & MODEL NO.	NOTES
EF-1.C	MEN'S RR	CEILING	71	0.25	8.5 WATTS	1,112	120/1ø	0.5	11.9	PANASONIC FV-0511VK2	1. & 2.
EF-2.C	WOMEN'S RR	CEILING	71	0.25	8.5 WATTS	1,112	120/1ø	0.5	11.9	PANASONIC FV-0511VK2	1. & 2.
EF-3.C	RESTROOM	CEILING	71	0.25	8.5 WATTS	1,112	120/1ø	0.5	11.9	PANASONIC FV-0511VK2	1. & 2.

NOTES:
1. PROVIDE WITH VIBRATION ISOLATORS, INTEGRAL BACKDRAFT DAMPER, MOTION SENSOR (FV-MSVK1), MULTI-SPEED MODULE (FV-VS15VK1) AND WALL CAP.
2. EXHAUST FAN TO OPERATE ON OCCUPANCY SENSOR (ACCESSORY TO FAN).

CLUBHOUSE & COMMON AREAS DX SPLIT AIR HANDLING UNIT SCHEDULE

MARK	LOCATION SERVED	FAN: TOTAL AIR FLOW (CFM)	OUTSIDE AIR FLOW (CFM)	EXTERNAL STATIC PRESS. (IN.WG.)	DRIVE TYPE	HP	COOLING COIL: ENTERING AIR TEMP. (F° DB/WB)	LEAVING AIR TEMP. (F° DB/WB)	TOTAL CAPACITY (BTUH)	FILTERS: TYPE	EFFICIENCY	THICKNESS	ELECTRIC HEATING COIL: NO. OF STAGES	TOTAL KW	VOLTAGE/ PHASE	SINGLE POINT UNIT ELEC. REQUIREMENTS: SINGLE CIRCUIT MCA	SINGLE CIRCUIT MOCP	UNIT INFORMATION: UNIT SIZE (H"xW"xD")	OPERATING WEIGHT (LBS.)	MANUFACTURER	MODEL NUMBER	MOUNTING	NOTES
AHU-1.C	GATHERING/GAME ROOM	1,600	310	0.8	DIRECT	1	80.0/67.0	56.0/54.0	48,000	THROWAWAY	25%-30%	1"	1	10	208/1ø	52.0	60	58"x25"x21"	167	GOODMAN OR EQUAL	ASPT49D14*	METAL STAND	1., 2., 3. & 4.
AHU-2.C	LOBBY, RECEPTION OFFICES	1,400	220	0.8	DIRECT	3/4	80.0/67.0	56.0/54.0	42,000	THROWAWAY	25%-30%	1"	1	8	208/1ø	41.0	45	54"x21"x21"	144	GOODMAN OR EQUAL	ASPT47C14*	METAL STAND	1., 2., 3. & 4.

NOTES:
1. PROVIDE COMPLETE WITH PULL TYPE DISCONNECT SWITCH (PROVIDED BY DIVISION 16) AND HONEYWELL TH8321WF1001 7-DAY PROGRAMMABLE THERMOSTAT AND INTEGRAL HUMIDISTAT.
2. ROUTE AND SIZE REFRIGERANT LINES PER MANUFACTURER'S REQUIREMENTS.
3. PROVIDE CONDENSATE OVERFLOW SWITCH SAFE-T SWITCH MODEL SS2 OR EQUIVALENT.
4. PROVIDE WITH MOTORIZED OUTSIDE AIR DAMPER. DAMPER TO BE INTERLOCKED WITH AHU AND BALANCED PER OUTSIDE AIR SCHEDULE.

CLUBHOUSE & COMMON AREAS DX SPLIT CONDENSING UNIT SCHEDULE (STRAIGHT COOL)

MARK	LOCATION	COMPRESSOR: OUTDOOR DESIGN TEMP. (F°)	QTY.	CAPACITY STEPS %	CONDENSER FANS: QTY.	NOMINAL HP	ELECTRICAL: VOLTAGE/ PHASE	COMPRESSOR RLA EACH	CONDENSER FANS: QTY.	FLA (EA.)	MCA	MOCP	SEER	UNIT INFORMATION: UNIT SIZE (H"xW"xD")	OPERATING WEIGHT (LBS.)	MANUFACTURER	MODEL NUMBER	NOTES
CU-1.C	GROUND	95°	1	100	1	1/4	208/1ø	19.9	1	1.30	26.2	45	14.0	36"x36"x36"	220	GOODMAN OR EQUAL	GSX140481*	1. & 2.
CU-2.C	GROUND	95°	1	100	1	1/6	208/1ø	16.7	1	0.95	21.8	35	14.0	36"x29"x29"	189	GOODMAN OR EQUAL	GSX140431*	1. & 2.

NOTES:
1. PROVIDE COMPLETE WITH PULL TYPE DISCONNECT SWITCH (PROVIDED BY DIVISION 16), TIME DELAY RELAY AND ANTI-SHORT CYCLE TIMER.
2. MOUNT AND SECURE CONDENSING UNITS PER DETAILS PROVIDED.

FLEX DUCT SCHEDULE

CFM	FLEX SIZE
0 – 35	4"ø
36 – 60	5"ø
61 – 100	6"ø
101 – 140	7"ø
141 – 210	8"ø
211 – 280	9"ø
281 – 400	10"ø
401 – 600	12"ø
601 – 900	14"ø
901 – 1,300	16"ø
1,300 – 1,700	18"ø

AIR BALANCE

EXHAUST:

EF-1.C	71 CFM
EF-2.C	71 CFM
EF-3.C	71 CFM
EXHAUST TOTAL:	213 CFM

MAKEUP AIR:

AHU-1.C	310 CFM
AHU-2.C	220 CFM
MAKEUP TOTAL:	530 CFM

BUILDING PRESSURE = +317
(WITH ALL FANS ACTIVATED)

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - ARCHITECTS, and are issued only for the specific project cited on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.


FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E


JLC 22.0023.00

STATE OF FLORIDA — No. 73885 — PROFESSIONAL ENGINEER — MICHAEL A. BARRETT

THE MADISON	Drawn: MJR/SMB
HUNTSVILLE, AL	Checked: BLS/AJB
	Approval: BLS/AJB
	Date: 04/15/2022
	Project #: 5722
SCHEDULES MECHANICAL	
CHM3.01	




11 NTS **CEILING EXHAUST FAN SUPPORT DETAIL FIRE RATED CEILING**



NOTES:

1. EXTEND FLEXIBLE DUCT INSULATION TO DUCT/DIFFUSER PANEL INSULATION AND SEAL WITH MASTIC.
2. MINIMUM 1-1/2" WIDE 22 GAUGE GALVANIZED STRAP HANGER WITH HEMMED EDGES PER SMACNA FIGURE 3-10.
3. FLEXIBLE AIR DUCT SHALL BE FULLY EXTENDED AND NOT COMPRESSED WITH ELBOW RADIUS NO LESS THAN R/D=1.0.


10 NTS **FLEXIBLE DUCT DETAIL**




NOTES:

1. MAXIMUM SPACING BETWEEN HANGER LOCATIONS SHALL BE 5'-0".
2. STRAPS SHALL BE MINIMUM 1-1/2".
3. REFER TO SMACNA AND FLORIDA MECHANICAL CODE FOR ADDITIONAL REQUIREMENTS.
4. FOR COMMERCIAL PROJECTS MAX FLEX DUCT LENGTH TO BE 12'-0".
5. FOR MULTI-FAMILY PROJECTS FLEX DUCT LENGTH HAS NO MAXIMUM LIMIT.


9 NTS **FLEX DUCT HANGER DETAIL**



8 NTS **ROOF CAP DETAIL**




7 NTS **CONDENSATE DRAIN TERMINATION DETAIL**



NOTES:


1. TYPICAL FOR: LOW PRESSURE AND HIGH PRESSURE CONNECTION TO MAIN DUCT, FAN TERMINAL UNITS, VARIABLE AIR VOLUME UNITS, AND DIFFUSERS.
2. DRAWBANDS SHALL BE EQUIVALENT TO PANDUIT PLT-H.

6 NTS **FLEXIBLE DUCT CONNECTION DETAIL**




2 PIECE HEAVY DUTY PLASTIC WALL CAP, PRIMEX MODEL WC-4 OR EQUAL. PROVIDE FACTORY INSTALLED BACKDRAFT DAMPER FOR DRYER VENT AND RESTROOM EXHAUST FANS. REMOVE BACKDRAFT DAMPER FOR USE AS OUTSIDE AIR INTAKE. FOR DRYER APPLICATIONS USE THE NO BIRD SCREEN (NS) MODEL. PAINT TO OWNERS SPEC.

4 NTS **TYPICAL WALL JACK DETAIL**




5 NTS **REFRIGERANT SLEEVE DETAIL**



NOTES:

1. CONDENSATE DRAIN SHALL BE PIPED FULL SIZE OF UNIT CONNECTION.
2. CONDENSATE PANS SHALL BE INSTALLED WITH ADEQUATE PITCH TO ENSURE POSITIVE DRAINAGE OF ACCUMULATED CONDENSATE.
3. TRAP CONDENSATE AND DISCHARGE PER PLAN.


3 NTS **CONDENSATE DRAIN DETAIL**



NOTES:

A. PROVIDE ALL EXPOSED INSULATED SUCTION LINES WITH SEAL TACK COATING, ALUMINUM JACKETING OR OTHER APPROVED PROTECTIVE MEANS.
B. CONTROL THERMOSTAT WIRING TO BE WRAPPED NEATLY AROUND LIQUID LINE AND INSULATED SUCTION LINE.

2 NTS **GROUND MOUNTED CONDENSING UNIT PIPING DETAIL (REFRIGERANT & ELECTRICAL BELOW GRADE)**



1 NTS **VERTICAL AHU DETAIL (CLUBHOUSE)**

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY


No.	Date	Description

© 2016 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103 and are issued only for the specific project shown herein. Any reproduction, re-use, or modification of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL. 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00



THE MADISON
HUNTSVILLE, AL

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

DETAILS MECHANICAL

CHM4.01

COMcheck Software Version COMcheckWeb
Envelope Compliance Certificate

Project Information

Energy Code:	2018 IECC
Project Title:	The Madison - Clubhouse
Location:	Madison (Madison), Alabama
Climate Zone:	3a
Project Type:	New Construction
Vertical Glazing / Wall Area:	22%

Construction Site:

Owner/Agent:
Ron Leichtner
Rohdie Schoolhouse, LLC
52 Vanderbilt New York
New York, New York 10017
(212) 682-5784

Designer/Contractor:
Adam Barney
Joseph Lawrence & Co
1180 Harwood Ave
Suite 3000, Florida 32714
(321) 972-4466

Additional Efficiency Package(s)
Credits: 1.0 Required 1.0 Proposed
Reduced Lighting Power, 1.0 credit

Building Area	Floor Area
1-Multifamily : Nonresidential	2243

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U-Factor(a)
Roof: Attic Roof, Wood Joists, [Bldg. Use 1 - Multifamily]	7539	38.0	0.0	0.027	0.027
Floor: Unheated Slab-On-Grade, Vertical 2 ft., [Bldg. Use 1 - Multifamily] (c)	306	---	10.0	0.540	0.540
NORTH					
Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Multifamily]	1468	21.0	0.0	0.062	0.064
Door: Glass (over 50% glazing): Metal Frame, Entrance Door, Perf. Specs.: Product ID N/A, SHGC 0.40, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	19	---	---	0.450	0.770
Window: Metal Frame: Operable, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	194	---	---	0.300	0.600
Window: Metal Frame: Fixed, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	131	---	---	0.300	0.460
EAST					
Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Multifamily]	733	21.0	0.0	0.062	0.064
Window: Metal Frame: Operable, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	112	---	---	0.300	0.600
Window: Metal Frame: Fixed, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	52	---	---	0.300	0.460
SOUTH					
Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Multifamily]	1467	21.0	0.0	0.062	0.064
Door: Glass (over 50% glazing): Metal Frame, Entrance Door, Perf. Specs.: Product ID N/A, SHGC 0.40, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	59	---	---	0.450	0.770
Window: Metal Frame: Operable, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	147	---	---	0.300	0.600
Window: Metal Frame: Fixed, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	131	---	---	0.300	0.460
WEST					
Ext. Wall: Wood-Framed, 16in. o.c., [Bldg. Use 1 - Multifamily]	655	21.0	0.0	0.062	0.064
Door: Glass (over 50% glazing): Metal Frame, Entrance Door, Perf. Specs.: Product ID N/A, SHGC 0.40, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	19	---	---	0.450	0.770
Door: Uninsulated Single-Layer Metal, Swinging, [Bldg. Use 1 - Multifamily]	64	---	---	1.200	0.610
Window: Metal Frame: Operable, Perf. Specs.: Product ID N/A, SHGC 0.25, PF 0.50, [Bldg. Use 1 - Multifamily] (b)	73	---	---	0.300	0.600

(a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.
(b) Fenestration product performance must be certified in accordance with NFRC and requires supporting documentation.
(c) Slab-On-Grade proposed and budget U-factors shown in table are F-factors.

Envelope PASSES: Design 18% better than code

Envelope Compliance Statement

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed envelope systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Adam J. Barney, P.E. — Name - Title
Signature
04/18/2022 — Date

COMcheck Software Version COMcheckWeb
Interior Lighting Compliance Certificate

Project Information

Energy Code:	2018 IECC
Project Title:	The Madison - Clubhouse
Project Type:	New Construction

Construction Site:

Owner/Agent:
Ron Leichtner
Rohdie Schoolhouse, LLC
52 Vanderbilt New York
New York, New York 10017
(212) 682-5784

Designer/Contractor:
Adam Barney
Joseph Lawrence & Co
1180 Harwood Ave
Suite 3000, Florida 32714
(321) 972-4466

Additional Efficiency Package(s)
Credits: 1.0 Required 1.0 Proposed
Reduced Lighting Power, 1.0 credit

Allowed Interior Lighting Power

A Area Category	B Floor Area (ft2)	C Allowed Watts / ft2	D Allowed Watts
1-Multifamily	2243	0.61	1373
		Total Allowed Watts =	1373

Proposed Interior Lighting Power

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixture	D Fixture Watt.	E (C X D)
1-Multifamily				
LED: CA: LED Other Fixture Unit 16W:	1	36	19	684
LED: CC: LED Other Fixture Unit 25W:	1	2	19	38
LED: CD: LED Other Fixture Unit 16W:	1	3	17	51
LED: P1: LED Other Fixture Unit 50W:	1	2	32	64
LED: P2: LED Other Fixture Unit 50W:	1	4	32	128
LED: P3: LED Other Fixture Unit 50W:	1	8	32	256
LED: CF1: LED Other Fixture Unit 28W:	1	4	27	108
LED: EM: LED Other Fixture Unit 6.5W: Exemption:Emergency lighting automatically off during normal business operation	1	12	3	Exempt
			Total Proposed Watts =	1329

Interior Lighting PASSES: Design 3% better than code

Interior Lighting Compliance Statement

Compliance Statement: The proposed interior lighting design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed interior lighting systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Blake L. Suddeth, P.E. — Name - Title
Signature
04/18/2022 — Date

COMcheck Software Version COMcheckWeb
Exterior Lighting Compliance Certificate

Project Information

Energy Code:	2018 IECC
Project Title:	The Madison - Clubhouse
Project Type:	New Construction
Exterior Lighting Zone	2 (Residentially zoned area (LZ2))

Construction Site:

Owner/Agent:
Ron Leichtner
Rohdie Schoolhouse, LLC
52 Vanderbilt New York
New York, New York 10017
(212) 682-5784

Designer/Contractor:
Adam Barney
Joseph Lawrence & Co
1180 Harwood Ave
Suite 3000, Florida 32714
(321) 972-4466

Allowed Exterior Lighting Power

A Area/Surface Category	B Quantity	C Allowed Watts /	D Tradable Wattage	E Allowed Watts (B X C)
Entry canopy	593 ft2	0.25	Yes	148
Pedestrian and vehicular entrances and exits	18 ft of	14	Yes	252
		Total Tradable Watts (a) =		400
		Total Allowed Watts =		400
		Total Allowed Supplemental Watts (b) =		400

(a) Wattage tradeoffs are only allowed between tradable areas/surfaces.
(b) A supplemental allowance equal to 400 watts may be applied toward compliance of both non-tradable and tradable areas/surfaces.

Proposed Exterior Lighting Power

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixture	D Fixture Watt.	E (C X D)
Entry canopy (593 ft2): Tradable Wattage				
LED: CA: LED Other Fixture Unit 16W:	1	7	19	133
LED: EM: LED Other Fixture Unit 6.5W: Exemption:Emergency lighting automatically off during normal business operation	1	4	3	Exempt
Pedestrian and vehicular entrances and exits (18 ft of door width): Tradable Wattage				
LED: CW: LED Other Fixture Unit 16W:	1	4	20	80
			Total Tradable Proposed Watts =	213

Exterior Lighting PASSES: Design 73% better than code

Exterior Lighting Compliance Statement

Compliance Statement: The proposed exterior lighting design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed exterior lighting systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Blake L. Suddeth, P.E. — Name - Title
Signature
04/18/2022 — Date

COMcheck Software Version COMcheckWeb
Mechanical Compliance Certificate

Project Information

Energy Code:	2018 IECC
Project Title:	The Madison - Clubhouse
Location:	Madison (Madison), Alabama
Climate Zone:	3a
Project Type:	New Construction

Construction Site:

Owner/Agent:
Ron Leichtner
Rohdie Schoolhouse, LLC
52 Vanderbilt New York
New York, New York 10017
(212) 682-5784

Designer/Contractor:
Adam Barney
Joseph Lawrence & Co
1180 Harwood Ave
Suite 3000, Florida 32714
(321) 972-4466

Additional Efficiency Package(s)
Credits: 1.0 Required 1.0 Proposed
Reduced Lighting Power, 1.0 credit

Mechanical Systems List

Quantity — System Type & Description

1 AHU-1.C (Single Zone):
Cooling: 1 each - Split System, Capacity = 48 kBtu/h, Air-Cooled Condenser, Unknown Economizer
Proposed Efficiency = 14.00 SEER, Required Efficiency: 13.00 SEER
Fan System: FAN SYSTEM 1 -- Compliance (Motor nameplate HP and fan efficiency method) : Passes

Fans:
FAN 1 Supply, Constant Volume, 1600 CFM, 1.8 motor nameplate hp, 93.0 fan efficiency grade, 98.0 total fan efficiency, 98.0 design fan efficiency , fan exception: Fan array <= 5 total HP

1 AHU-2.C (Single Zone):
Cooling: 1 each - Split System, Capacity = 48 kBtu/h, Air-Cooled Condenser, Unknown Economizer
Proposed Efficiency = 14.00 SEER, Required Efficiency: 13.00 SEER
Fan System: FAN SYSTEM 2 -- Compliance (Motor nameplate HP and fan efficiency method) : Passes

Fans:
FAN 2 Supply, Constant Volume, 1400 CFM, 0.8 motor nameplate hp, 93.0 fan efficiency grade, 98.0 total fan efficiency, 98.0 design fan efficiency , fan exception: Fan array <= 5 total HP

1 Water Heater:
Electric Storage Water Heater, Capacity: 38 gallons w/ Circulation Pump
Proposed Efficiency: 0.92 SL, %/h (if > 12 kW), Required Efficiency: 1.01 SL, %/h (if > 12 kW)

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Adam J. Barney, P.E. — Name - Title
Signature
04/18/2022 — Date

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2018 These documents are the property of FUGLEBERG KOCH and may not be used in any way without the express written consent of Fugleberg Koch is prohibited by law. Visual contact with these documents shall constitute proof of knowledge of the protection of FUGLEBERG KOCH's rights in these documents. Submission or distribution of these documents to meet official regulatory requirements or for other purposes in connection with the intended project is not to be construed as publication in derogation of FUGLEBERG KOCH's rights. Any reproduction, unauthorized use or alteration of these documents without the express written permission of FUGLEBERG KOCH is strictly forbidden. Re-use of these documents on other projects without the express written permission of FUGLEBERG KOCH is strictly forbidden and will be at user's sole risk and without liability to FUGLEBERG KOCH and user shall indemnify and hold harmless FUGLEBERG KOCH from all claims arising from such re-use. These documents are licensed for use only by the specific project noted on these drawings. Any reproductions, re-uses, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL. 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

ENERGY CALCULATIONS MECHANICAL

CHM5.01

ELECTRICAL SYMBOL LEGEND

NOTE:
SYMBOLS SHOWN ARE FOR REFERENCE PURPOSES ONLY. ALL OF THESE SYMBOLS MAY NOT BE USED FOR THIS PROJECT.

WIRING AND POWER

- WALL OUTLET BOX AND SINGLE RECEPTACLE
- WALL OUTLET BOX AND DUPLEX RECEPTACLE
- TWO GANG WALL OUTLET BOX AND (2) DUPLEX RECEPTACLES
- WALL OUTLET BOX AND DUPLEX RECEPTACLE MOUNTED ABOVE COUNTER
- WALL OUTLET BOX AND DUPLEX RECEPTACLE WITH TOP HALF SWITCHED
- WALL OUTLET BOX AND DUPLEX RECEPTACLE CONNECTED TO EMERGENCY SYSTEM
- CEILING OUTLET BOX AND SINGLE RECEPTACLE
- CEILING OUTLET BOX AND DUPLEX RECEPTACLE
- WALL OUTLET BOX AND GFCI DUPLEX RECEPTACLE
- WALL OUTLET BOX AND GFCI DUPLEX RECEPTACLE MOUNTED ABOVE COUNTER
- S — WALL OUTLET BOX AND DUPLEX SAFETY RECEPTACLE
- T — WALL OUTLET BOX AND DUPLEX TWIST-LOCK RECEPTACLE
- WP — WALL OUTLET BOX AND GFCI DUPLEX RECEPTACLE WITH WEATHERPROOF COVER
- WALL OUTLET BOX AND SPECIAL PURPOSE OUTLET AS NOTED ON PLANS
- FLUSH FLOOR OUTLET BOX WITH DUPLEX RECEPTACLE
- FLUSH FLOOR OUTLET BOX WITH (2) DUPLEX RECEPTACLES
- FLUSH FLOOR OUTLET BOX WITH DUPLEX RECEPTACLE AND TELECOMMUNICATIONS OUTLET
- FLUSH WALL JUNCTION BOX AND BLANK PLATE
- JUNCTION BOX AND BLANK PLATE ABOVE CEILING
- SURFACE MOUNTED JUNCTION BOX AND BLANK PLATE
- WP — SURFACE MOUNTED WEATHERPROOF JUNCTION BOX AND COVER
- PB — FLUSH GRADE FIBER COMPOSITE PULL BOX AS NOTED
- MOTOR CONNECTION AS NOTED
- FLUSH SHUNT-TRIP BUTTON, MOUNTED 80" TO TOP
- CONTROL AND/OR POWER EQUIPMENT CONNECTION
- TIME CLOCK
- PHOTO CELL
- DISCONNECT SWITCH, SIZE AS NOTED
- 120/208V BRANCH CIRCUIT PANELBOARD, SURFACE MOUNTED
- 120/208V BRANCH CIRCUIT PANELBOARD, FLUSH MOUNTED
- 277/480V BRANCH CIRCUIT PANELBOARD
- T — TRANSFORMER
- AUTOMATIC TRANSFER SWITCH
- A-3 — BRANCH CIRCUIT HOMERUN WITH PANEL NAME AND CIRCUIT NUMBER, QUANTITY OF ARROWHEADS DENOTES QUANTITY OF BRANCH CIRCUITS
- BRANCH CIRCUIT WIRING, PROVIDE QUANTITY OF CONDUCTORS REQUIRED FOR CIRCUITING AND SWITCHING INDICATED ON PLANS
- POWER LEG ONLY (NO SWITCH LEG BETWEEN ROOMS)
- CONDUIT CAPPED OFF
- CONDUIT CONTINUED
- CONDUIT RUN UP
- CONDUIT RUN DOWN
- GROUND OR GROUND ROD AS NOTED

LIGHTING AND SWITCHING

- CEILING MOUNTED LIGHT FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- CEILING MOUNTED RECESSED DOWNLIGHT FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- CEILING MOUNTED RECESSED WALLWASH FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- CEILING MOUNTED "CLOSE TO CEILING" FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- PENDANT MOUNTED LIGHT FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- TRACK LIGHT FIXTURE WITH HEADS AS REQUIRED, REFER TO LIGHT FIXTURE SCHEDULE
- WALL MOUNTED LIGHT FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- CEILING MOUNTED LIGHT FIXTURE WITH EMERGENCY BACKUP
- CEILING MOUNTED RECESSED DOWNLIGHT FIXTURE WITH EMERGENCY BACKUP
- WALL MOUNTED LIGHT FIXTURE WITH EMERGENCY BACKUP
- WALL MOUNTED EMERGENCY BATTERY LIGHT FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- CEILING MOUNTED EMERGENCY BATTERY LIGHT FIXTURE, REFER TO LIGHT FIXTURE SCHEDULE
- CEILING MOUNTED EXIT SIGN WITH EMERGENCY BACKUP, REFER TO LIGHT FIXTURE SCHEDULE
- WALL MOUNTED EXIT SIGN WITH EMERGENCY BACKUP, REFER TO LIGHT FIXTURE SCHEDULE
- COMBINATION EXIT SIGN AND EMERGENCY LIGHT FIXTURE WITH BATTERY BACKUP
- Sa — WALL OUTLET BOX AND SINGLE POLE SWITCH ('a' INDICATES SWITCH LEG)
- S3 — WALL OUTLET BOX AND THREE-WAY SWITCH
- SF — WALL OUTLET BOX AND FAN CONTROL SWITCH
- SD — WALL OUTLET BOX AND DIMMER SWITCH AS REQUIRED FOR LOAD SERVED
- SD3 — WALL OUTLET BOX AND THREE-WAY DIMMER SWITCH
- SM — WALL OUTLET BOX WITH SINGLE POLE MANUAL MOTOR STARTER SWITCH
- SO — WALL OUTLET BOX AND DUAL TECHNOLOGY OCCUPANCY SENSOR
- ST — WALL OUTLET BOX AND DIGITAL TIMECLOCK SWITCH FOR AUTOMATIC CONTROL
- OS — CEILING OUTLET BOX AND DUAL TECHNOLOGY OCCUPANCY SENSOR
- DL — CEILING OUTLET BOX AND DAYLIGHT HARVESTING SENSOR

FIRE ALARM SYSTEM LEGEND

- F — MANUAL PULL STATION
- cd — WALL MOUNTED HORN WITH STROBE (cd=CANDELA RATING)
- WP — WALL MOUNTED HORN WITH STROBE IN WEATHERPROOF ENCLOSURE
- CEILING MOUNTED HORN WITH STROBE
- M — WALL MOUNTED MINI HORN
- M — WALL MOUNTED MINI HORN WITH STROBE
- WALL MOUNTED VOICE EVACUATION SPEAKER WITH STROBE
- CEILING MOUNTED VOICE EVACUATION SPEAKER WITH STROBE
- WALL MOUNTED STROBE
- SMOKE DETECTOR
- CO — SMOKE AND CARBON MONOXIDE COMBINATION DETECTOR
- DUCT MOUNTED SMOKE DETECTOR
- HEAT DETECTOR
- REMOTE DUCT DETECTOR INDICATOR LIGHT AND TEST SWITCH (NUMBER INDICATES QUANTITY)
- R — FAN SHUT-DOWN RELAY
- D — ELECTROMAGNETIC DOOR RELEASE DEVICE
- SMOKE DAMPER (PROVIDE BY MECHANICAL, CONNECTED BY ELECTRICAL)
- FP — FIREMAN'S PHONE JACK
- TS — SPRINKLER SYSTEM SUPERVISORY SWITCH CONNECTION
- FS — SPRINKLER SYSTEM FLOW SWITCH CONNECTION
- CM — CONTROL MODULE
- MM — MONITOR MODULE
- LB — LOCK BOX
- FACP — FIRE ALARM CONTROL PANEL
- FATC — FIRE ALARM TERMINAL CABINET
- FAAP — FIRE ALARM ANNUNCIATOR PANEL
- DACT — DIGITAL ALARM COMMUNICATOR TRANSMITTER

TELECOMMUNICATION SYSTEM LEGEND

- COMBINATION TELECOMMUNICATIONS/DATA WALL OUTLET BOX AND BLANK PLATE WITH MIN. 3/4"C. TO ACCESSIBLE CEILING SPACE. COORDINATE OUTLET REQUIREMENTS WITH OWNER.
- TELECOMMUNICATIONS WALL OUTLET BOX AND BLANK PLATE FOR WALL MOUNTED TELEPHONE WITH MIN. 3/4"C. TO ACCESSIBLE CEILING SPACE. COORDINATE OUTLET REQUIREMENTS WITH OWNER.
- DATA WALL OUTLET BOX AND BLANK PLATE WITH MIN. 3/4"C. TO ACCESSIBLE CEILING SPACE. COORDINATE OUTLET REQUIREMENTS WITH OWNER.
- FLUSH FLOOR OUTLET BOX WITH POWER DEVICE AND TELECOMMUNICATIONS OUTLET WITH MIN. 3/4"C. TO ACCESSIBLE CEILING SPACE.
- WAP — CEILING OUTLET BOX AND BLANK PLATE WITH MIN. 3/4"C. TO TTB FOR WIRELESS ACCESS POINT. COORDINATE OUTLET REQUIREMENTS WITH OWNER.
- TV — COMBINATION TELECOMMUNICATIONS/TELEVISION WALL OUTLET BOX AND BLANK PLATE. COORDINATE OUTLET AND CABLING REQUIREMENTS WITH OWNER.
- 3/4" PLYWOOD TELEPHONE TERMINAL BOARD, SIZE AS SHOWN ON PLANS.
- TTC — TELEPHONE TERMINAL CABINET, SIZE AS NOTED ON PLAN.

GENERAL NOTES

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70), AND THE LATEST ADOPTED EDITION OF THE INTERNATIONAL BUILDING CODE.
2. CONTRACTOR SHALL FIELD VERIFY ALL CONDITIONS AND COORDINATE WITH ALL EQUIPMENT MANUFACTURER/INSTALLERS PRIOR TO BIDDING.
3. ALL ELECTRICAL MATERIALS, DEVICES, APPLIANCES, AND EQUIPMENT SHALL BE LABEL LISTED BY AN APPROVED THIRD-PARTY TESTING AGENCY.

BUILDING:

4. INSTALLATION HEIGHT OF EQUIPMENT (TO CENTERLINE) ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE SHALL BE:

   RECEPTACLE = 18"
   CLOCK = 7'-6"
   SWITCH = 44"
   MODULAR JACK FOR WALL MOUNTED TELEPHONE = 48"
   MODULAR TELEPHONE JACK = 18"
   TELEVISION OUTLET = 84"
   COMPUTER OUTLET = 18"
   CALL SWITCH = 44"
   REMOTE TEST STATION FOR DUCT DETECTOR = 52"
   C = ABOVE COUNTER BACKSPLASH, COORDINATE WITH ARCHITECTURAL ELEVATIONS AND MILLWORK.

5. ALL CONDUIT AND WIRING SHALL BE CONCEALED IN WALLS OR ABOVE CEILINGS UNLESS NOTED OTHERWISE OR APPROVED BY THE ARCHITECT/ENGINEER. ALL DEVICE OUTLET BOXES SHALL BE RECESSED UNLESS NOTED OTHERWISE OR APPROVED BY THE ARCHITECT/ENGINEER. WHERE APPROVED OR NOTED SURFACE METAL RACEWAY AND DEVICE BOXES SHALL BE USED IN LIEU OF CONDUIT AND CONCEALED BOXES AT NO EXTRA COST TO THE OWNER.
6. ALL CONDUIT ROUTING SHOWN IS APPROXIMATE ONLY. CONTRACTOR SHALL FIELD VERIFY FINAL ROUTE WITH ALL OTHER TRADES AND CONDITIONS IN FIELD PRIOR TO ROUGH-IN.
7. CONDUIT RUNS SHOWN ARE SCHEMATIC AND DO NOT INDICATE THE NECESSARY FITTINGS AND JUNCTION BOXES THAT ARE INCLUDED IN THE SCOPE OF THE WORK.
8. CONTRACTOR SHALL PERMANENTLY IDENTIFY ALL WIRING WITH THE SOURCE AND CIRCUIT AT ALL ELECTRICAL EQUIPMENT, PULL AND JUNCTION BOXES AND ELECTRICAL TERMINATIONS PROVIDED OR ASSOCIATED WITH THIS CONSTRUCTION.
9. COORDINATE EXACT LOCATION OF LIGHTING FIXTURES IN MECH. ROOMS/SPACES WITH DUCTWORK INSTALLER PRIOR TO ROUGH-IN. LOCATE BELOW DUCTWORK(8'-0" AFF MINIMUM) CENTERED IN ROOM AS MUCH AS POSSIBLE.
10. COORDINATE EXACT INSTALLATION REQUIREMENTS OF OUTLETS IN MILLWORK WITH ARCHITECTURAL DRAWINGS, APPROVED SHOP DRAWINGS AND MILLWORK INSTALLER PRIOR TO ROUGH-IN.
11. VERIFY EXACT LOCATION OF ALL MECHANICAL EQUIPMENT WITH MECHANICAL INSTALLER PRIOR TO ROUGH-IN.
12. REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF ALL LIGHT FIXTURES.
13. PROVIDE NYLON PULLSTRINGS IN ALL EMPTY CONDUITS.
14. COORDINATE THE EXACT LOCATION OF ALL ELECTRICAL EQUIPMENT LOCATED IN ELEVATOR MACHINE ROOMS, SHAFTS AND PITS. LOCATE EQUIPMENT AS REQUIRED TO MEET APPLICABLE CODES.PROVIDE AUTOMATIC DISCONNECTION OF THE ELEVATOR MAIN POWER SUPPLY (PER ANSI A17.1, RULE 102.2 1987 ED.) PRIOR TO ACTIVATION OF AUTOMATIC SPRINKLER LOCATED WITHIN THE ELEVATOR MACHINE ROOM, PIT OR SHAFT. COORDINATE WITH FIRE PROTECTION AND FIRE ALARM INSTALLER.
15. COORDINATE THE REQUIRED SIZE OF ALL CIRCUIT BREAKERS FEEDING EQUIPMENT, (I.E. MOTORS, HVAC, KITCHEN EQUIPMENT, SPECIAL PURPOSE OUTLETS, ELEVATORS, OWNER FURNISHED EQUIPMENT ETC.) WITH APPROVED EQUIPMENT SHOP DRAWINGS AND OWNER REPRESENTATIVES PRIOR TO ORDERING PANELBOARDS. BREAKERS SHALL BE SIZED PER THE NEC, THE EQUIPMENT NAME PLATE AND MANUFACTURERS RECOMMENDATIONS.
16. ALL DIMMED CIRCUITS SHALL BE PROVIDED WITH DEDICATED NEUTRALS FOR EACH DIMMER AND PHASE CONDUCTOR THROUGHOUT THE ENTIRE CIRCUIT.
17. THE POWER COMPANY SHALL BE CONTACTED WITHIN 10 DAYS OF THE AWARD OF THE CONTRACT BY THE CONTRACTOR TO VERIFY THE ACTUAL AVAILABLE SHORT CIRCUIT FAULT CURRENT (AIC) AT THE TRANSFORMER SECONDARY BUSHINGS. THE CONTRACTOR SHALL PROVIDE ELECTRICAL DISTRIBUTION AND UTILIZATION EQUIPMENT AND PANELBOARDS WHICH HAVE AIC/WITHSTAND RATINGS GREATER THAN THE AVAILABLE AIC AT EACH POINT IN THE ELECTRICAL SYSTEM.
18. VISIT THE EXISTING FACILITY AND CAREFULLY EXAMINE THOSE PORTIONS OF THE BUILDING AND SITE AFFECTED BY THIS WORK BEFORE SUBMITTING PROPOSALS, SO AS TO BECOME FAMILIAR WITH THE EXISTING CONDITIONS AND DIFFICULTIES THAT WILL AFFECT EXECUTION OF THE WORK. SUBMISSION OF A PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT SUCH EXAMINATION HAS BEEN MADE AND LATER CLAIMS FOR LABOR, EQUIPMENT OR MATERIALS REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WILL NOT BE RECOGNIZED.
19. CONTRACTOR SHALL INCLUDE IN HIS BID THE TRANSPORT AND DISPOSAL OR RECYCLING OF ALL WASTE MATERIALS GENERATED BY THIS PROJECT IN ACCORDANCE WITH ALL RULES, REGULATIONS AND GUIDELINES APPLICABLE.
20. PANEL SCHEDULES INDICATE CIRCUIT DESIGNATIONS ONLY. CONTRACTOR TO PROVIDE MATERIALS AS REQUIRED WHEN NEUTRALS ARE SHARED TO COMPLY WITH NEC REQUIREMENTS. ALL SINGLE PHASE MULTIWIRE BRANCH CIRCUITS SHALL BE FED VIA A TWO POLE BREAKER OR TWO SINGLE POLE BREAKERS WITH AN IDENTIFIED HANDLE TIE. ALL THREE PHASE MULTIWIRE BRANCH CIRCUITS SHALL BE FED VIA A THREE POLE BREAKER OR THREE SINGLE POLE BREAKERS WITH AN IDENTIFIED HANDLE TIE (PER NEC 210.4B).
21. PER NEC 110.22; PROVIDE PERMANENT LABELING FOR ALL SERIES RATED PANEL ENCLOSURES TO READ AS FOLLOWS: CAUTION – SERIES COMBINATION SYSTEM RATED _____ AMPERES. IDENTIFIED REPLACEMENT COMPONENTS REQUIRED.
27. ELECTRICAL CONTRACTOR SHALL PROVIDE FULL LIGHTNING PROTECTION SYSTEM FOR THIS PROJECT PER NFPA 780.

GROUNDING:

28. ALL METAL RACEWAYS, INCLUDING CONDUIT, WIRE TROUGHS, WIREMOLD, ETC., SHALL BE GROUNDED. ALL CONNECTIONS IN METAL RACEWAYS SHALL BE COMPLETED IN SUCH A MANNER AS TO MAINTAIN A CONTINUOUS PATH TO GROUND THROUGHOUT THE ENTIRE LENGTH OF THE RACEWAY.

WIRING:

29. UNLESS NOTED OTHERWISE ON THE DRAWINGS OR ON THE EQUIPMENT WIRING SCHEDULE, EACH BRANCH CIRCUIT HOME RUN SHALL BE THREE (3) #12 AWG THHN/THWN (1 HOT, 1 NEUTRAL & 1 EQUIPMENT GROUND) IN 3/4" EMT CONDUIT. PROTECT EACH CIRCUIT WITH A 20 AMPERE, 1-POLE OVERCURRENT DEVICE UNLESS NOTED OTHERWISE. COMBINED NEUTRALS ARE NOT PERMITTED.

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - ACADEMIC. All rights reserved. Any reproduction, re-modification of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL. 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

ALABAMA LICENSED No. 31127 PROFESSIONAL ENGINEER BRADLEY L. SUMMERLIN

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE SYMBOL LEGEND & GENERAL NOTES ELECTRICAL

CHE2.00

GENERAL NOTES:

A. DO NOT SCALE ELECTRICAL DRAWING FOR ANY DIMENSIONS.

B. ALL WORK SHALL COMPLY WITH THE 2017 NATIONAL ELECTRICAL CODE, NATIONAL, STATE AND LOCAL CODES. PROVIDE GROUNDING AND BONDING PER NEC 250.


C. SEE SINGLE LINE DIAGRAM FOR FEEDER WIRE AND CONDUIT SIZE. ALL CIRCUITS NOT SIZED ON DRAWING SHALL BE INSTALLED TO MEET MINIMUM SIZE REQUIRED BY NEC. ALL CONDUCTORS SHALL HAVE AN EQUIPMENT GROUND WIRE SIZED PER NEC.

D. FIELD VERIFY EXACT LOCATION OF ALL DEVICES AND EQUIPMENT PRIOR TO ROUGH IN.

E. ALL 125V, 15A AND 20A RECEPTACLES INSTALLED IN CLUBROOMS, CONFERENCE ROOMS, MULTIPURPOSE ROOMS, AND OTHER ASSEMBLY OCCUPANCIES AS LISTED PER NEC 518.2 SHALL BE LISTED TAMPER-RESISTANT PER NEC 406.12.

REFERENCE NOTES: ⟨X⟩

1. ELECTRICAL CONTRACTOR SHALL COORDINATE DISCONNECT AND FUSE REQUIREMENTS FOR MECHANICAL UNIT WITH MECHANICAL CONTRACTOR AND EQUIPMENT MANUFACTURER PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED. COORDINATE LOCATION OF DISCONNECT WITH OWNER AND MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN. LOCATE AS REQUIRED TO MAINTAIN NEC CLEARANCES.
2. PROVIDE 120V RECEPTACLE AND TELEVISION OUTLET FOR WALL MOUNTED TELEVISION. COORDINATE LOCATION AND MOUNTING HEIGHT WITH OWNER/EQUIPMENT INSTALLER PRIOR TO ROUGH-IN.
3. CONNECT FRACTIONAL HORSEPOWER EXHAUST FAN TO LOCAL LIGHTING CIRCUIT. FAN SHALL BE CONTROLLED BY INDIVIDUAL SWITCH. REFER TO MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL SERVICE EQUIPMENT LOCATION. REFER TO POWER RISER DIAGRAM FOR ADDITIONAL INFORMATION.
5. PROVIDE RECESSED KNOX BOX FOR FIRE DEPARTMENT BUILDING ACCESS. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH OWNER AND FIRE DEPARTMENT PRIOR TO ROUGH-IN.
6. ELECTRICAL CONTACTOR SHALL PROVIDE (1) 8"X8" JUNCTION BOX WITH COVERPLATE ON EACH FLOOR OF BUILDING FOR FUTURE DAS SYSTEM IF REQUIRED. PROVIDE 1"C. (EMPTY W/ PULLSTRING) BETWEEN ALL JUNCTION BOXES FOR FUTURE DAS SYSTEM WIRING. COORDINATE LOCATION OF JUNCTION BOXES WITH OWNER AND FIRE ALARM CONTRACTOR PRIOR TO ROUGH-IN. LABEL ALL JUNCTION BOXES, COVERPLATE AND CONDUIT AS REQUIRED FOR FUTURE IDENTIFICATION.
7. PROVIDE TWO-WAY COMMUNICATIONS BASE STATION AS REQUIRED BY 2018 NFPA 101 LIFE SAFETY CODE. COORDINATE LOCATION WITH OWNER AND AUTHORITY HAVING JURISDICTION. SYSTEM SHALL HAVE TIMED DIAL-OUT CAPABILITY TO A MONITORING LOCATION OR 911. SYSTEM SHALL INCLUDE BOTH AUDIBLE AND VISIBLE SIGNALS.
8. PROVIDE 2" UNDERGROUND CONDUIT FROM MASTER FACP TO SUB-PANEL FACP'S LOCATED IN BUIDLINDS. REFER TO FIRE ALARM RISER DIAGRAM FOR ADDITIONAL INFORMATION.
9. PROVIDE 120V QUAD RECEPTACLE AND DATA OUTLET FOR MAIL PARCEL PACKAGE SYSTEM. COORDINATE EXACT LOCATION AND CONNECTION REQUIREMENTS WITH ARCHITECT AND EQUIPMENT INSTALLER PRIOR TO ROUGH-IN.



K2 CLUBHOUSE - FLOOR PLAN - POWER & SYSTEMS
1/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH / ADDRESS, and are issued only for the specific project cited on these drawings. Any reproduction, revision, or modification of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

LICENSED PROFESSIONAL ENGINEER BLAKE L. SUDDETH No. 31122 STATE OF ALABAMA

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE
POWER & SYSTEMS

CHE2.01

GENERAL NOTES:

A. SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT FIXTURE LOCATIONS AND ORIENTATIONS.

B. REFER TO ARCHITECTURAL ELEVATIONS AND SECTIONS FOR ADDITIONAL LIGHTING FIXTURE MOUNTING DETAILS AND INFORMATION.

C. ALL EMERGENCY LIGHTING FIXTURES AND EXIT SIGNS SHALL BE CONNECTED "HOT" TO THE INDICATED LOCAL LIGHTING CIRCUIT.

D. VERIFY ALL MOUNTING HEIGHTS AND PENDANT LENGTHS WITH ARCHITECT AND ENGINEER PRIOR TO ORDERING FIXTURES.

E. EMERGENCY ILLUMINATION SHALL BE PROVIDED FOR A PERIOD OF 90 MINUTES IN THE EVENT OF FAILURE OF NORMAL LIGHTING. EMERGENCY LIGHTING FACILITIES SHALL BE ARRANGED TO PROVIDE INITIAL ILLUMINATION THAT IS AT LEAST AN AVERAGE OF 1 FOOTCANDLE (10 LUX) AND A MINIMUM AT ANY POINT OF 0.1 FOOTCANDLE (1 LUX) MEASURED ALONG THE PATH OF EGRESS AT FLOOR LEVEL. ILLUMINATION LEVELS SHALL BE PERMITTED TO DECLINE TO 0.6 FOOTCANDLE (6 LUX) AVERAGE AND A MINIMUM AT ANY POINT OF 0.06 FOOTCANDLE (0.6 LUX) AT THE END OF THE EMERGENCY LIGHTING TIME DURATION. A MAXIMUM-TO-MINIMUM ILLUMINATION UNIFORMITY RATIO OF 40:1 SHALL NOT BE EXCEEDED.

F. PROVIDE BLOCKING IN CEILING FOR LARGE LIGHT FIXTURES PER ID DRAWINGS.


G. ALL SWITCHES IN CLUBHOUSE TO BE DECORATIVE ROCKER SWITCHES.

REFERENCE NOTES: (X)

(1) CONNECT EXTERIOR LIGHTING FIXTURES VIA LIGHTING CONTACTOR 'LC1' FOR AUTOMATIC CONTROL OF FIXTURES. REFER TO DETAIL FOR ADDITIONAL INFORMATION.

(2) PROVIDE CEILING MOUNTED OCCUPANCY SENSOR FOR AUTOMATIC CONTROL OF ROOM LIGHTING. SENSOR SHALL OVERRIDE WALL CONTROL AND "TURN OFF" ROOM LIGHTS IF ROOM UNOCCUPIED FOR MORE THAN 20 MINUTES. PROVIDE ADDITIONAL SENSORS, RELAY PACKS, CONTROL WIRING, ETC. AS REQUIRED FOR COMPLETE COVERAGE OF ROOM AND CIRCUITS/SWITCH LEGS SHOWN. CONTROLS SHALL BE "MANUAL ON/AUTOMATIC OFF" WITH THE EXCEPTION OF RESTROOMS, PUBLIC CORRIDORS, AND LOBBIES. THESE AREAS SHALL BE FULLY AUTOMATIC ON/AUTOMATIC OFF" IN ACCORDANCE WITH THE 2020 INTERNATIONAL BUILDING CODE.

(3) PROVIDE WALL MOUNTED, DUAL TECHNOLOGY, LOW VOLTAGE VACANCY SENSOR, WATTSTOPPER #DW-100-24 (OR APPROVED SUBSTITUTION) FOR AUTOMATIC CONTROL OF LIGHTING. CONNECT LIGHTING IN SPACE AS SHOWN ON PLANS VIA WATTSTOPPER LIGHTING POWER PACK #BZ-200 (OR APPROVED SUBSTITUTION). PROVIDE ALL ADDITIONAL POWER PACKS, RELAYS, SENSORS AS REQUIRED FOR COMPLETE COVERAGE OF SPACE AND SWITCHING AS SHOWN ON PLANS. INSTALLATION SHALL COMPLY WITH 2020 INTERNATIONAL BUILDING CODE.



K2 CLUBHOUSE - FLOOR PLAN - LIGHTING
1/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2015 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project cited on these drawings. Any reproductions, versions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

ALABAMA REGISTERED PROFESSIONAL ENGINEER MARK L. SUDDUTH No. 31152

Drawn:	MJR/SMS
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE LIGHTING

CHE2.02

FEEDER SCHEDULE

- (A) 2 SETS [(4)#250 kcmil AL., IN 2-1/2"C.]
- (B) 2 SETS [(4)#250 kcmil AL., (1)#1/0 AWG AL. GND.]
- (C) (3)#1/0 AWG AL., IN 2"C.
- (D) (3)#1/0 AWG AL., (1)#6 AWG AL. GND., IN 2"C.
- (E) 2 SETS [(4)#250 kcmil AL., IN 2-1/2"C.]
- (F) 2 SETS [(4)#250 kcmil AL., (1)#1 AWG AL. GND., IN 2-1/2"C.]

ELECTRICAL SERVICE LOAD CALCULATION

PANEL 'CHA'	37.68 KVA
POOL PANEL	9.06 KVA
TOTAL	46.74 KVA = 129.83 AMPS

SERVICE ENTRANCE FEEDERS ARE SIZED FOR 400A

REFERENCE NOTES: ⟨X⟩

1. REFER TO SITE PLAN – ELECTRICAL, SHEET E1.01 FOR LOCATION OF UTILITY TRANSFORMER.
2. COORDINATE ALL CONNECTION REQUIREMENTS OF NEW SERVICE WITH LOCAL UTILITY COMPANY PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED.
3. PROVIDE HARD WIRED SURGE PROTECTIVE DEVICE OF SAME MANUFACTURER AS PANELBOARD.
4. PROVIDE 100A, 250V, 1ø, 3W, NEMA 3R, SERVICE ENTRANCE RATED DISCONNECT SWITCH FUSED AT 100AMPS FOR POOL PANEL. COORDINATE ALL REQUIREMENTS WITH UTILITY COMPANY PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED. PROVIDE PHENOLIC LABELING AT EACH DISCONNECT FOR SERVICE AS REQUIRED BY NEC.
5. PROVIDE 400A, 250V, 3ø, 4W, NEMA 3R, SERVICE ENTRANCE RATED DISCONNECT SWITCH FUSED AT 400AMPS. COORDINATE ALL REQUIREMENTS WITH UTILITY COMPANY PRIOR TO ROUGH-IN AND PROVIDE AS REQUIRED. PROVIDE PHENOLIC LABELING AT EACH DISCONNECT FOR SERVICE AS REQUIRED BY NEC.
6. PROVIDE NEMA 3R WIREWAY SIZED AS REQUIRED PER NEC. MINIMUM LENGTH TO BE 8'-0".
7. POOL PANEL TO BE PROVIDED BY POOL CONTRACTOR AND INSTALLED BY ELECTRICAL CONTRACTOR. COORDINATE LOCATION AND REQUIREMENTS WITH POOL CONTRACTOR PRIOR TO ROUGH-IN.
8. ELECTRICAL CONTRACTOR TO PROVIDE 20'-0" OF CONCRETE ENCASED ELECTRODE IN CONCRETE FOUNDATION AS REQUIRED BY NEC 250.52(A)(3). COORDINATE ALL REQUIREMENTS WITH GENERAL CONTRACTOR PRIOR TO ROUGH-IN.
9. BOND NEUTRAL AND GROUND SERVICE CONDUCTORS IN SERVICE DISCONNECT SWITCH PER NEC 250.
10. PROVIDE #6 AWG CU. GND. INTER-SYSTEM BONDING JUMPER TO INTER-SYSTEM BONDING TERMINAL PER NEC 250.94.

GENERAL NOTES:

A. DO NOT SCALE ELECTRICAL DRAWING FOR ANY DIMENSIONS.

B. ALL WORK SHALL COMPLY WITH THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL CODE, STATE, AND LOCAL CODES. PROVIDE GROUNDING AND BONDING PER NEC 250.

C. COORDINATE ALL WORK WITH LOCAL UTILITY COMPANY.


D. FEEDERS ARE DESIGNED FOR A MAXIMUM VOLTAGE DROP OF 2% AT DESIGN LOAD. BRANCH CIRCUITS ARE DESIGNED FOR A MAXIMUM VOLTAGE DROP OF 3% AT DESIGN LOAD.

E. PER NEC ARTICLE 110.24, ALL CONSTRUCTION DOCUMENTS SHALL PROVIDE A PERMANENT LABEL TO THE FRONT OF SERVICE EQUIPMENT ENCLOSURE STATING THE MAXIMUM AVAILABLE FAULT CURRENT IN AMPS, THE DATE CALCULATED, THE NOMINAL VOLTAGE AND THE FREQUENCY IN HERTZ, THE SERVICE EQUIPMENT BUS RATING IN AMPS, AND THE SCCR OF SERVICE EQUIPMENT IN AMPS. SIGNAGE SHALL BE ENGRAVED, LAMINATED ACRYLIC, OR MELAMINE LABEL, PUNCHED OR DRILLED FOR MECHANICAL FASTENERS WITH WHITE LETTERS ON A BLACK BACKGROUND, MINIMUM 1/16" THICK. MINIMUM LETTER HEIGHT SHALL BE 1/2".

F. PER NEC ARTICLE 110.16, ARC FLASH WARNING LABELS ARE TO BE INSTALLED ON ALL SWITCHBOARDS, PANELBOARDS, METER SOCKET ENCLOSURES, AND MOTOR CONTROL CENTERS THAT ARE LIKELY TO REQUIRE EXAMINATION, ADJUSTMENT, SERVICING, OR MAINTENANCE WHILE ENERGIZED. ARC FLASH WARNING LABELS SHALL MEET THE ARTICLE 110.21(B).

G. CONTRACTOR TO PROVIDE AND INSTALL ARC ENERGY REDUCTION MITIGATION SYSTEM AND DOCUMENTATION FOR ALL OVERCURRENT DEVICES RATED 1200A OR GREATER PER NEC 240.87.

NOTE:
FEEDERS ARE DESIGNED FOR A MAXIMUM VOLTAGE DROP OF 2% AT DESIGN LOAD.
BRANCH CIRCUITS ARE DESIGNED FOR A MAXIMUM VOLTAGE DROP OF 3% AT DESIGN LOAD.



G8 CLUBHOUSE POWER RISER DIAGRAM
NOT TO SCALE

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL. 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

ALABAMA LICENSED PROFESSIONAL ENGINEER MICHAEL L. SUDDUTH 31759

Drawn:	MJR/SMS
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE RISER DIAGRAM ELECTRICAL

CHE3.01

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project cited on these drawings. Any reproductions, variation, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

DESIGN OF FIRE ALARMS & DETECTION SYSTEMS

61G15-32.008 DESIGN OF FIRE ALARM AND DETECTION SYSTEM COMPLIANCE NOTES FOR APARTMENTS AND CLUBHOUSE:

APPLICABLE CODES: IBC INTERNATIONAL BUILDING CODE (2020) 7TH EDITION
FPC FIRE PREVENTION CODE (2018) 7TH EDITION
- NFPA 1 FIRE CODE (2018) FLORIDA EDITION
- NFPA 101 LIFE SAFETY CODE (2018) FLORIDA EDITION

NFPA 70 NATIONAL ELECTRICAL CODE (2017)
NFPA 72 NATIONAL FIRE ALARM & SIGNALING CODE (2016)
AHJ – MADISON, ALABAMA – LOCAL CODES & AMENDMENTS

(4) ENSURE MINIMUM DESIGN QUALITY OF FIRE ALARM SYSTEM AS FOLLOWS

A. DESIGN INTENT

1. SYSTEM TYPE: MASTER FIRE ALARM CONTROL PANEL LOCATED IN CLUBHOUSE SHALL BE AN ADDRESSABLE PANEL BY EDWARDS, HONEYWELL, NOTIFIER, SILENT KNIGHT, OR APPROVED EQUIVALENT. SUB-PANEL FACP'S IN EACH APARTMENT BUILDING SHALL BE ADDRESSABLE TYPES.
2. SEE SYMBOL LEGEND ON THIS SHEET.
3. SEE FIRE ALARM RISER DIAGRAM(S) THIS SHEET.
4. CABLING REQUIREMENTS:
   a. WIRING METHOD: THE SYSTEM WILL BE FREE WIRED USING APPROPRIATE STRAPS, TIES, FITTINGS, ETC. TO PREVENT DAMAGE TO THE WIRING.
   b. INITIATION CIRCUITS (LOOP): INITIATION LOOP CONDUCTORS SHALL BE WEST PENN #D991 FOR 3000'0" IN LENGTH AND LESS. WEST PENN #D995 SHALL BE USED FOR CIRCUITS OVER 3000'0" IN LENGTH. BELOW GRADE, WET OR DAMP LOCATION INSTALLED CABLE, INCLUDING CABLE INSTALLED ON THE TOP OF EXTERIOR WALKWAYS, SHALL BE WEST PENN AQUASEAL MULTI-CONDUCTOR (14 GAUGE), UNLESS NOTED OTHERWISE, SHALL BE INSTALLED IN CONDUIT.
   c. SIGNAL CIRCUITS: SIGNAL CIRCUITS SHALL BE #14 AWG THWN 19 STRAND COPPER (USE #12 AWG IF VOLTAGE DROP EXCEEDS MANUFACTURER'S SPECIFICATIONS).
   d. ANNUNCIATOR CIRCUITS: #14 AWG THWN 19 STRAND COPPER (USE #12 AWG IF VOLTAGE DROP EXCEEDS MANUFACTURER'S SPECIFICATIONS).
   e. EACH AND EVERY WIRE SHALL BE LABELED AT EACH END WITH SLC #, CHANNEL # OR SIGNAL #, EACH SEPARATE CIRCUIT, INITIATION, SIGNAL AND AUXILIARY SHALL HAVE A SPECIFIC NUMBER. LABEL EACH CONDUCTOR BY THIS CIRCUIT NUMBER AT THE CONTROL CONNECTIONS AND AT EACH TERMINAL CONNECTION IN THE TERMINAL CABINETS.
5. FIRE RATINGS REQUIRED FOR SURVIVABILITY: UNLESS NOTED OTHERWISE, PATHWAY SURVIVABILITY SHALL BE LEVEL 0 OR 1.

B. DEVICE LOCATIONS AND RELATED SYSTEMS

1. ALL INITIATION AND NOTIFICATION DEVICES ARE SHOWN ON ELECTRICAL POWER AND SYSTEMS PLANS WITHIN THIS ELECTRICAL DRAWING SET.
2. CONNECTIONS TO OTHER SYSTEMS: PROVIDE RELAYS FOR OTHER LOCAL CONTROL SUCH AS HVAC SHUTDOWN AND FIRE/SMOKE DAMPER RELEASE. RELAYS SHALL BE 10 AMP RATED RELAYS. UPON ACTIVATION OF THE FIRE ALARM SYSTEM, THE RELAY SHALL ACTIVATE AND SHUTDOWN THE CONTROLLED EQUIPMENT. LOCATE ALL RELAYS WITHIN 36" OF EQUIPMENT CONTROLLED. PROVIDE WEATHERPROOF UNITS WHERE INDICATED OR INSTALL IN WEATHERPROOF BOXES.

C. STROBE INTENSITY AND SPEAKER OUTPUT RATINGS

1. PER NFPA 72 SECTION 18.4.3 AUDIBLE SIGNALS SHALL BE AT LEAST 15dB ABOVE AVERAGE AMBIENT SOUND LEVEL OR 5dB ABOVE MAXIMUM SOUND LEVEL, WHICHEVER IS GREATER.
2. ALL VISUAL NOTIFICATION DEVICES SHALL HAVE CANDELA RATINGS AS INDICATED ON PLAN SHEET(S), PER NFPA 72 SECTION 18.5.5.4.
3. AUDIBLE APPLIANCES FOR SLEEPING AREAS SHALL PRODUCE A LOW FREQUENCY ALARM SIGNAL THAT COMPLIES WITH NFPA SECTION 18.4.5.3.
4. VISUAL FIRE ALARM NOTIFICATION APPLIANCES LOCATED IN SLEEPING AREAS SHALL HAVE AN INTENSITY LEVEL OF:
   - 110 CD WHERE TOP OF LENS IS INSTALLED GREATER THAN OR EQUAL TO 24 INCHES FROM THE CEILING
   - 177 CD WHERE TOP OF LENS IS INSTALLED LESS THAN 24 INCHES FROM THE CEILING

   AND SHALL NOT BE FURTHER THAN 16 FEET FROM THE PILLOW, IN ACCORDANCE WITH NFPA 72 SECTIONS 18.5.5.7.1-18.5.5.7.3.

D. CIRCUIT CLASSES

INITIATING DEVICE CIRCUITS – CLASS B. SIGNALING LINE CIRCUITS – CLASS B. NOTIFICATION APPLIANCE CIRCUIT – CLASS B.

E. FUNCTIONS – SEE FIRE ALARM MATRIX OF OPERATIONS THIS SHEET.

F. FIRE ALARM TYPE AND ZONING

1. FIRE ALARM SYSTEM IS AN ADDRESSABLE TYPE. SUB-PANELS ARE ADDRESSABLE TYPE.
2. INITIATING DEVICES SHALL BE ZONED BY BUILDING/FLOOR.
3. EVACUATION SIGNALS SHALL BE ZONED BY BUILDING.

G. SURGE PROTECTION

DITEX SURGE PROTECTION DEVICES DEVICES SHALL BE PROVIDED AT EACH CONNECTION TO MAIN POWER AND WHERE A CIRCUIT ENTERS/EXITS THE BUILDING. ALL SURGE/TRANSIENT SUPPRESSORS MUST BE CONNECTED TO APPROVED BUILDING GROUND.

H. ENVIRONMENTAL FACTORS

NO SPECIAL ENVIRONMENTAL FACTORS APPLY. FIRE ALARM DEVICES AND EQUIPMENT TO BE INSTALLED OUTDOORS IN EXTERIOR LOCATIONS SHALL BE SPECIFICALLY DESIGNED AND U.L. LISTED AS WEATHERPROOF AND WATERPROOF.

I. SITE PLAN

AN ELECTRICAL SITE PLAN HAS BEEN PROVIDED ON SHEET E1.01 INDICATING THE LOCATIONS OF MASTER FACP IN CLUBHOUSE AND SUB PANEL FACP'S IN APARTMENT BUILDINGS.

J. AREA SMOKE DETECTION

1. WHERE SMOKE DETECTORS ARE USED TO PROVIDE AREA COVERAGE, THEY SHALL BE LOCATED IN ACCORDANCE WITH NFPA 72 SECTION 17.7.3 "LOCATION AND SPACING" AND NFPA SECTION 29.8.3.4 "SPECIFIC LOCATION REQUIREMENTS" FOR THE APPLICABLE CONDITIONS.
2. SMOKE ALARMS AND SMOKE DETECTORS SHALL NOT BE LOCATED WHERE AMBIENT CONDITIONS, INCLUDING HUMIDITY AND TEMPERATURE, ARE OUTSIDE THE LIMITS SPECIFIED BY THE MANUFACTURER'S PUBLISHED INSTRUCTIONS.
3. SMOKE ALARMS AND SMOKE DETECTORS SHALL NOT BE LOCATED WITHIN UNFINISHED ATTICS OR GARAGES OR IN OTHER SPACES WHERE TEMPERATURES CAN FALL BELOW 40°F OR EXCEED 100°F.
4. SMOKE ALARMS AND SMOKE DETECTORS SHALL NOT BE INSTALLED WITHIN 10 FT FROM A STATIONARY OR FIXED COOKING APPLIANCE, UNLESS LISTED FOR INSTALLATION IN CLOSE PROXIMITY TO COOKING APPLIANCES OR MEETING THE ADDITIONAL CRITERIA LIST IN SECTION 29.8.3.4(4).
5. SMOKE ALARMS AND SMOKE DETECTORS SHALL NOT BE INSTALLED WITHIN 3 FT FROM THE FOLLOWING: A DOOR TO A BATHROOM CONTAINING A SHOWER OR TUB, SUPPLY AIR REGISTERS, AND/OR THE TIP OF THE BLADE OF A CEILING PADDLE FAN.

K. SMOKE STRATIFICATION – SMOKE STRATIFICATION IS NOT EXPECTED TO OCCUR IN THIS/THESE INTERIOR BUILDING(S).

L. PERFORMANCE BASED DESIGN (PBD) – THE DESIGN IS DERIVED FROM A PRESCRIPTIVE DESIGN BASIS.

M. EVACUATION SIGNAL – EVACUATION SIGNAL IS A GENERAL SIGNAL ☐ BY FLOOR ☒ BY BUILDING.

N. WIRING REQUIREMENTS

1. WIRING SHALL BE IN ACCORDANCE WITH NFPA 72 AND NFPA 70 ARTICLES 300, 760, 770, AND 800, AS APPLICABLE, UNLESS OTHERWISE NOTED.
2. PROTECTION AGAINST DAMAGE: INSTALL WIRING IN METAL RACEWAY, CONCEAL RACEWAY EXCEPT IN UNFINISHED SPACES AND AS INDICATED.
3. FIRE ALARM DEVICES AND EQUIPMENT TO BE INSTALLED OUTDOORS IN EXTERIOR LOCATIONS SHALL BE SPECIFICALLY DESIGNED AND U.L. LISTED AS WEATHERPROOF AND WATERPROOF. PROVIDE WEATHERPROOF NEOPRENE GASKETS BETWEEN WALL MOUNTING SURFACE AND FIRE ALARM DEVICE FOR ALL DEVICES MOUNTED OUTDOORS.

O. OPERATIONS AND MAINTENANCE PROCEDURES

1. PROVIDE THE SERVICES OF A FACTORY-AUTHORIZED SERVICE REPRESENTATIVE TO DEMONSTRATE THE SYSTEM AND TRAIN OWNER'S MAINTENANCE PERSONNEL AS SPECIFIED BELOW:
   a. TRAIN OWNER'S MAINTENANCE PERSONNEL IN THE LOCATION OF DEVICES, BOXES, PROCEDURES AND SCHEDULES INVOLVED IN OPERATING, TROUBLESHOOTING, SERVICING, AND PREVENTIVE MAINTAINING OF THE SYSTEM. PROVIDE A MINIMUM OF 4 HOURS' TRAINING. TRAINING SHALL INCLUDE A COMPLETE PROJECT WALKDOWN WITH OWNER'S AUTHORIZED REPRESENTATIVE TO IDENTIFY DEVICE LOCATIONS, JUNCTION BOX LOCATIONS AND SURGE SUPPRESSION MODULE LOCATIONS.
   b. SCHEDULE TRAINING WITH THE OWNER AT LEAST SEVEN WORKING DAYS IN ADVANCE.


(5) BATTERY CALCULATIONS AND VOLTAGE DROP CALCULATIONS

FIRE ALARM CONTRACTOR SHALL SUBMITTALS AND SHOP DRAWINGS WITH BATTERY CALCULATIONS AND VOLTAGE DROP (CIRCUIT ANALYSIS) CALCULATIONS BASED ON THE SPECIFIC EQUIPMENT INCLUDED IN THOSE SUBMITTALS AND SHOP DRAWINGS. CALCULATIONS SHALL BE COMPLETED USING THE EQUIPMENT MANUFACTURE'S DATA AND APPLICABLE NFPA 72 PROCEDURES.

(6) SYSTEM TEST AND DOCUMENTATION REQUIREMENTS

FIRE ALARM CONTRACTOR SHALL PERFORM THE TESTING LISTED BELOW AND PREPARE RECORDS PER NFPA 72 SECTION 14.6.

☒ INITIAL ACCEPTANCE TESTING SHALL BE IN ACCORDANCE WITH NFPA 72 SECTION 14.4.1 FOR ALL NEW APPLIANCE AND CIRCUITS.
☐ RE-ACCEPTANCE TESTING IN ACCORDANCE WITH NFPA 72 14.4.2 FOR MODIFICATIONS OF EXISTING CIRCUITS.
☒ AFTER INITIAL ACCEPTANCE TESTING, FIRE ALARM SYSTEM TESTING SHALL BE PERFORMED AND DOCUMENTED IN COMPLIANCE WITH THE PERIODIC FREQUENCIES AND METHODS AS SHOWN IN NFPA 72 TABLE 14.3.1.



FIRE ALARM SYSTEM RISER DIAGRAM

NO SCALE

FIRE ALARM RISER - GENERAL NOTES:

A. FIRE ALARM SYSTEM RISER DIAGRAM IS DIAGRAMMATICAL. SEE FLOOR PLANS FOR EXACT QUANTITIES OF DEVICES. WIRING SHALL BE AS RECOMMENDED BY SYSTEMS MANUFACTURER.

B. DO NOT SCALE ELECTRICAL DRAWING FOR ANY DIMENSIONS.

C. ALL WORK SHALL COMPLY WITH THE 2017 NATIONAL ELECTRICAL CODE, NATIONAL, STATE AND LOCAL CODES. PROVIDE GROUNDING AND BONDING PER NEC 250.

D. PROVIDE 120VAC SURGE SUPPRESSION AND LOW VOLTAGE FIRE ALARM CIRCUIT SURGE SUPPRESSION.

E. PROVIDE NOTIFICATION APPLIANCE CIRCUITS AND POWER SUPPLIES AS REQUIRED.

F. REFER TO POWER AND SYSTEMS FLOOR PLANS FOR FIRE ALARM EQUIPMENT COUNT.

G. PROVIDE 1" CONDUIT FROM FACP TO TTB.

H. ALL FIRE ALARM CIRCUITS SHALL BE IN CONDUIT WHERE REQUIRED BY CODE OR AHJ. PROVIDE ALL REQUIRED MONITORING AND CONTROL OF MECHANICAL UNITS AS REQUIRED BY AUTHORITY HAVING JURISDICTION.

I. VERIFY FIRE PROTECTION FLOW AND TAMPER SWITCH LOCATION WITH FIRE PROTECTION DRAWINGS. PROVIDE ALL REQUIRED MONITORING OF FIRE PROTECTION SYSTEM.

J. PER FFPC 6TH EDITION NFPA 1 SECTION 11.10 TWO-WAY RADIO COMMUNICATION ENHANCEMENT SYSTEMS: IN ALL NEW AND EXISTING BUILDINGS, MINIMUM RADIO SIGNAL STRENGTH FOR THE FIRE DEPARTMENT COMMUNICATIONS SHALL BE SHALL BE MAINTAINED AT A LEVEL DETERMINED BY THE AHJ.

K. CARBON MONOXIDE DETECTION SHALL BE PROVIDED NEAR GAS APPLIANCES AND WITHIN 10' OF SLEEPING AREAS IN BUILDINGS WITH FUEL BURNING APPLIANCES OR ATTACHED GARAGES, PER STATE STATUTES.

FIRE ALARM SYSTEM LEGEND

F	MANUAL PULL STATION
cd	WALL MOUNTED HORN WITH STROBE (cd=CANEDLA RATING)
WP	WALL MOUNTED HORN WITH STROBE IN WEATHERPROOF ENCLOSURE
	CEILING MOUNTED HORN WITH STROBE
M	WALL MOUNTED LOW FREQUENCY MINI HORN
M	WALL MOUNTED LOW FREQUENCY MINI HORN WITH STROBE
	WALL MOUNTED VOICE EVACUATION SPEAKER WITH STROBE
	CEILING MOUNTED VOICE EVACUATION SPEAKER WITH STROBE
	WALL MOUNTED STROBE
B	FIRE ALARM BELL
	SMOKE DETECTOR
CO	SMOKE AND CARBON MONOXIDE COMBINATION DETECTOR
	DUCT MOUNTED SMOKE DETECTOR
	HEAT DETECTOR
	REMOTE DUCT DETECTOR INDICATOR LIGHT AND TEST SWITCH
R	FAN SHUT-DOWN RELAY
D	ELECTROMAGNETIC DOOR RELEASE DEVICE
	SMOKE DAMPER (PROVIDE BY MECHANICAL, CONNECTED BY ELECTRICAL)
P	FIREMAN'S PHONE JACK
TS	SPRINKLER SYSTEM SUPERVISORY TAMPER SWITCH CONNECTION
FS	SPRINKLER SYSTEM FLOW SWITCH CONNECTION
CM	CONTROL MODULE
MM	MONITOR MODULE
LB	LOCK BOX
FACP	FIRE ALARM CONTROL PANEL
FATC	FIRE ALARM TERMINAL CABINET
FAAP	FIRE ALARM ANNUNCIATOR PANEL
DACT	DIGITAL ALARM COMMUNICATOR TRANSMITTER

		CONTROL UNIT ANNUNCIATION						NOTIFICATION	FIRE SAFETY CONTROL									
	SYSTEM INPUTS	A ACTUATE COMMON ALARM SIGNAL INDICATOR	B ACTUATE AUDIBLE ALARM SIGNAL	C ACTUATE COMMON SUPERVISORY SIGNAL INDICATOR	D ACTUATE AUDIBLE SUPERVISORY SIGNAL	E ACTUATE COMMON TROUBLE SIGNAL INDICATOR	F ACTUATE COMMON TROUBLE SIGNAL	G ACTUATE ALARM INDICATOR	H ACTUATE EVACUATION SIGNAL	I DISPLAY/PRINT CHANGE OF STATUS	J TRANSMIT FIRE ALARM SIGNAL TO SUPERVISING STATION	K TRANSMIT SUPERVISORY SIGNAL TO SUPERVISING STATION	L TRANSMIT TROUBLE SIGNAL TO SUPERVISING STATION	M RELEASE MAGNETICALLY HELD SMOKE DOORS	N RECALL ELEVATORS TO PRIMARY RECALL FLOOR	O RECALL ELEVATORS TO ALTERNATE RECALL FLOOR	P CLOSE SMOKE/FIRE DAMPERS IN RATED WALLS	Q SHUTDOWN AFFECTED ELEVATOR POWER	R SHUTDOWN AFFECTED AIR HANDLING UNIT(S)	S UNLOCK SECURED EGRESS EXITS
1	MANUAL FIRE ALARM BOXES	●	●				●	●	●	●	●			●						●
2	AREA SMOKE DETECTORS	●	●				●	●	●	●	●			●						●
3	IN-DUCT SMOKE DETECTORS			●	●					●		●					●		●	●
4	HEAT DETECTOR IN ELEVATOR SHAFT/PIT	●	●							●	●						●	●		●
5	ELEVATOR LOBBY SMOKE DETECTORS – FIRST FLOOR	●	●							●	●			●		●	●			●
6	ELEVATOR LOBBY SMOKE DETECTORS – UPPER FLOORS	●	●							●	●			●	●		●			●
7	WATER FLOW	●	●					●		●	●			●	●					●
8	SPRINKLER CONTROL VALVE			●	●					●		●								
9	OPEN CIRCUIT					●	●						●							
10	GROUND FAULT					●	●						●							
11	NOTIFICATION APPLIANCE CIRCUIT SHORT					●	●						●							

FIRE ALARM MATRIX OF OPERATIONS

NO SCALE

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - ALABAMA 2020, INC. and are issued only for the specific project noted on these drawings. Any reproduction, erasure, or modification of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO: 4050 - E

JLC 22.0023.00

ALABAMA LICENSED PROFESSIONAL ENGINEER No. 31422 BRANDON L. SUDDUTH

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE FIRE ALARM RISER DIAGRAM ELECTRICAL

CHE3.02

LIGHTING FIXTURE SCHEDULE - CLUBHOUSE

MARK	DESCRIPTION	MANUFACTURER	MODEL	VOLTS	LAMP QTY	LAMP WATTS	LAMP MODEL	FIXTURE WATTS
CA	6" RECESSED AIR-TIGHT, IC-RATED LED DOWNLIGHT WITH GALVANIZED STEEL HOUSING, CLEAR SEMI-SPECULAR REFLECTOR, DAMP LABEL RATED	H.E. WILLIAMS	6DR-TL-L20/835-DIM-UNV-OM-OF-CS-MWT-I-F1	120	1	19	LED	19
CC	1'x4' SURFACE OR PENDANT MOUNT WRAP FIXTURE AT UTILITY CLOSETS WITH FROSTED RIBBED ACRYLIC SHIELDING AND WHITE POLYESTER POWDER COAT FINISH	H.E. WILLIAMS	39-4-L30/835-A-DRV-120	120	1	25	LED	25
CD	DECORATIVE LED BATHROOM VANITY SCONCE	TBD	TBD	120	1	17	LED	17
CF1	52" INTERIOR CEILING FAN	TBD	TBD	120	–	–	–	55
CW	DECORATIVE EXTERIOR LED WALL SCONCE. UL WET LABEL RATED.	TBD	TBD	120	1	20	LED	20
P1	DECORATIVE LED PENDANT IN LOBBY	TBD	TBD	120	1	32	LED	32
P2	DECORATIVE LED PENDANT IN GAME ROOM	TBD	TBD	120	1	32	LED	32
P3	DECORATIVE LED PENDANT IN GATHERING ROOM	TBD	TBD	120	1	32	LED	32
EM	WALL MOUNTED EMERGENCY LIGHT WITH THERMOPLASTIC HOUSING, WHITE FINISH, TWIN HEADS AND BATTERY BACKUP.	BEGHELLI	PEH-T20	120	2	1.7	LED	3.4
EM2	WALL MOUNTED ECCO LUNA LED EMERGENCY LIGHT WITH CORROSION/FLAME/VANDAL RESISTANT POLYCARBONATE HOUSING, BATTERY BACKUP, UL WET LABEL RATED	BEGHELLI	EL-SE-205LED-120/277-W	120	2	5	LED	10
X1	UNIVERSAL FACE/MOUNT EXIT SIGN EXIT SIGN WITH WHITE THERMOPLASTIC HOUSING, RED LETTERS, BATTERY BACKUP, DAMP LABEL RATED	BEGHELLI	PX-R-HT-AT	120	–	–	LED	–
X3	UNIVERSAL FACE/MOUNT EXIT SIGN WITH SIDE MOUNTED EMERGENCY LIGHTING HEADS, WHITE THERMOPLASTIC HOUSING, RED LETTERS, BATTERY BACKUP.	BEGHELLI	XCL-R-U-W	120	–	–	LED	–

NOTES:
1. DIVISION 16 CONTRACTOR SHALL VERIFY ALL FIXTURE TYPES AND FINISHES WITH OWNER PRIOR TO ORDERING.

PANEL 'CHA' (SECTION 1)

LOCATION: ELEC. ROOM | VOLTAGE: 208Y/120V 3ø 4W | MIN. AIC RATING: 22K AIC | NOTES: PROVIDE TYPED WRITTEN DIRECTORY, PROVIDE GROUND & NEUTRAL BUS
TYPE: SQUARE-D, TYPE NQ | MAINS: 400A ☒ MLO ☐ MCB | MOUNTING: SURFACE
FED FROM: SERVICE DISC. | LUGS: ☐ SUB-FEED ☒ FEED-THRU | ENCLOSURE: NEMA 1

CKT	CIRCUIT DESCRIPTION	NOTES	BRANCH CIRCUIT #	NEUT	GND	COND	BKR	LOAD KVA	PHASE ø	LOAD KVA	BKR	BRANCH CIRCUIT #	NEUT	GND	COND	NOTES	CIRCUIT DESCRIPTION	CKT
1	FACP	2	12	12	12	1/2"	20/1	0.50	A	0.27	20/1	12	12	12	1/2"	1	LTG – EXTERIOR/MAIL	2
3	TTB		12	12	12	1/2"	20/1	0.36	B	0.08	20/1	12	12	12	1/2"	1	LTG – EXTERIOR	4
5	RCPTS – MECH/RR/CORRIDOR		12	12	12	1/2"	20/1	0.54	C	0.39	20/1	12	12	12	1/2"		LTG – ELEC/RR/OFFICE/WORK	6
7	PARCEL PACKAGE SYSTEM		12	12	12	1/2"	20/1	0.50	A	0.26	20/1	12	12	12	1/2"		LTG – GAMEROOM	8
9	RCPTS – WORKROOM		12	12	12	1/2"	20/1	0.36	B	0.55	20/1	12	12	12	1/2"		LTG – GATHERING ROOM	10
11	WORKROOM EQUIPMENT		12	12	12	1/2"	20/1	1.00	C	0.14	20/1	12	12	12	1/2"		LTG – RR/CORRIDOR	12
13	COPIER		12	12	12	1/2"	20/1	0.50	A	–	–	–	–	–	–		SPARE	14
15	RCPTS – WORKROOM/RECEPTION		12	12	12	1/2"	20/1	0.72	B	–	–	–	–	–	–		SPARE	16
17	RCPTS – RECEPTION		12	12	12	1/2"	20/1	0.72	C	–	–	–	–	–	–		SPARE	18
19	RCPTS – OFFICE/EXTERIOR		12	12	12	1/2"	20/1	0.90	A	–	–	–	–	–	–		SPARE	20
21	RCPTS – LOBBY/EXTERIOR		12	12	12	1/2"	20/1	0.90	B	–	–	–	–	–	–		SPARE	22
23	RCPTS – LOBBY		12	12	12	1/2"	20/1	0.72	C	–	–	–	–	–	–		SPARE	24
25	RCPTS – GAMEROOM		12	12	12	1/2"	20/1	0.90	A	–	–	–	–	–	–		SPARE	26
27	RCPTS – GAMEROOM/EXTERIOR		12	12	12	1/2"	20/1	1.08	B	–	–	–	–	–	–		SPARE	28
29	GAMEROOM EQUIPMENT		12	12	12	1/2"	20/1	1.00	C	–	–	–	–	–	–		SPARE	30
31	GAMEROOM EQUIPMENT		12	12	12	1/2"	20/1	1.00	A	–	–	–	–	–	–		SPARE	32
33	RCPTS – GAMEROOM COUNTER		12	12	12	1/2"	20/1	0.36	B	–	–	–	–	–	–		SPACE ONLY	34
35	RCPTS – GATHERING ROOM		12	12	12	1/2"	20/1	0.36	C	–	–	–	–	–	–		SPACE ONLY	36
37	RCPTS – GATHERING ROOM		12	12	12	1/2"	20/1	0.72	A	–	–	–	–	–	–		SPACE ONLY	38
39	RCPTS – CORRIDOR/GATHERING/EXT		12	12	12	1/2"	20/1	0.90	B	–	–	–	–	–	–		SPACE ONLY	40
41	EWC		12	12	12	1/2"	20/1	0.70	C	–	–	–	–	–	–		SPACE ONLY	42

EQUIPMENT SERVED	CONN. LOAD	L.F.	D.F.	DEMAND LOAD	
LIGHTING	1.68 KVA		125%	2.10 KVA	
RECEPTACLES – GENERAL	9.18 KVA		100%	9.18 KVA	
EQUIPMENT	5.56 KVA		100%	5.56 KVA	
PANELS (SECTION 2)	20.84 KVA		100%	20.84 KVA	
NOTES: 1) CONNECT VIA LIGHTING CONTACTOR 2) PROVIDE "LOCK OUT" STYLE BREAKER HANDLE PER NEC 422.31 3) SPLIT A/C, CONDENSING UNIT NOT INCLUDED IN LOAD CALC					TOTAL DEMAND LOAD: 37.68 KVA TOTAL AMPS: 104.67 AMPS

PANEL 'CHA' (SECTION 2)

LOCATION: ELEC. ROOM | VOLTAGE: 208Y/120V 3ø 4W | MIN. AIC RATING: 22K AIC | NOTES: PROVIDE TYPED WRITTEN DIRECTORY, PROVIDE GROUND & NEUTRAL BUS
TYPE: SQUARE-D, TYPE NQ | MAINS: 400A ☒ MLO ☐ MCB | MOUNTING: SURFACE
FED FROM: SERVICE DISC. | LUGS: ☐ SUB-FEED ☒ FEED-THRU | ENCLOSURE: NEMA 1

CKT	CIRCUIT DESCRIPTION	NOTES	BRANCH CIRCUIT #	NEUT	GND	COND	BKR	LOAD KVA	PHASE ø	LOAD KVA	BKR	BRANCH CIRCUIT #	NEUT	GND	COND	NOTES	CIRCUIT DESCRIPTION	CKT
43	EWH-1		10	10	10	3/4"	30/2	2.25	A	4.33	60/2	6	6	10	1.25"		AHU-1.C	44
45	–		10	–	–	–	–	2.25	B	4.33	–	6	–	–	–		–	46
47	CP-1		12	12	12	1/2"	15/1	0.86	C	3.41	45/2	8	8	10	1"		AHU-2.C	48
49	SPACE ONLY		–	–	–	–	–	–	A	3.41	–	8	–	–	–		–	50
51	SPACE ONLY		–	–	–	–	–	–	B	2.18	45/2	8	8	10	1"	3	CU-1.C	52
53	SPACE ONLY		–	–	–	–	–	–	C	2.18	–	8	–	–	–		–	54
55	SPACE ONLY		–	–	–	–	–	–	A	1.81	35/2	8	8	10	3/4"	3	CU-2.C	56
57	SPACE ONLY		–	–	–	–	–	–	B	1.81	–	8	–	–	–		–	58
59	SPACE ONLY		–	–	–	–	–	–	C	–	–	–	–	–	–		SPACE ONLY	60
61	SPACE ONLY		–	–	–	–	–	–	A	–	–	–	–	–	–		SPACE ONLY	62
63	SPACE ONLY		–	–	–	–	–	–	B	–	–	–	–	–	–		SPACE ONLY	64
65	SPACE ONLY		–	–	–	–	–	–	C	–	–	–	–	–	–		SPACE ONLY	66
67	SPACE ONLY		–	–	–	–	–	–	A	–	–	–	–	–	–		SPACE ONLY	68
69	SPACE ONLY		–	–	–	–	–	–	B	–	–	–	–	–	–		SPACE ONLY	70
71	SPACE ONLY		–	–	–	–	–	–	C	–	–	–	–	–	–		SPACE ONLY	72
73	SPACE ONLY		–	–	–	–	–	–	A	–	–	–	–	–	–		SPACE ONLY	74
75	SPACE ONLY		–	–	–	–	–	–	B	–	–	–	–	–	–		SPACE ONLY	76
77	SPACE ONLY		–	–	–	–	–	–	C	–	–	–	–	–	–		SPACE ONLY	78
79	SPACE ONLY		–	–	–	–	–	–	A	–	30/3	10	10	10	3/4"		SURGE PROTECTIVE DEVICE (SPD)	80
81	SPACE ONLY		–	–	–	–	–	–	B	–	–	10	–	–	–		–	82
83	SPACE ONLY		–	–	–	–	–	–	C	–	–	10	–	–	–		–	84

EQUIPMENT SERVED	CONN. LOAD	L.F.	D.F.	DEMAND LOAD	
LIGHTING	– KVA		125%	– KVA	
RECEPTACLES – GENERAL	– KVA		100%	– KVA	
EQUIPMENT	20.84 KVA		100%	20.84 KVA	
NOTES: 1) CONNECT VIA LIGHTING CONTACTOR 2) PROVIDE "LOCK OUT" STYLE BREAKER HANDLE PER NEC 422.31 3) SPLIT A/C, CONDENSING UNIT NOT INCLUDED IN LOAD CALC					TOTAL DEMAND LOAD: 20.84 KVA LOAD CARRIED OVER TO FIRST SECTION

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2018 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103. and are issued only for the specific project noted on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL. 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

ALABAMA LICENSED PROFESSIONAL ENGINEER BRADLEY L. SCHOOLEY NO. 31127

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE SCHEDULES ELECTRICAL

CHE4.01

LEGEND

- DIRECTION OF FLOW IN PIPE
- PITCH PIPE DOWN IN DIRECTION OF ARROW
- PIPE UP
- PIPE DOWN
- EJ — EXPANSION JOINT
- FLEXIBLE PIPE CONNECTOR
- BALL VALVE
- CHECK VALVE, HORIZONTAL SWING
- GATE VALVE
- BUTTERFLY VALVE
- GLOBE VALVE
- BALANCING VALVE
- BC — BALANCING COCK
- STRAINER, Y-TYPE AND BLOWOFF VALVE
- RV — PRESSURE RELIEF VALVE (WATER)
- PRV — PRESSURE REDUCING VALVE
- MAV — MANUAL AIR VENT
- SOLENOID VALVE
- VALVE OS & Y
- CAPPED LINE
- SAN — SANITARY SEWER (ABOVE GRADE)
- SAN — SANITARY SEWER (BELOW GRADE)
- DOMESTIC COLD WATER
- BP — BOOSTED PRESSURE DOMESTIC COLD WATER
- DOMESTIC HOT WATER
- DOMESTIC HOT WATER RETURN
- CD — CONDENSATE DRAIN (BELOW GRADE)
- CD — CONDENSATE DRAIN (ABOVE GRADE)
- ST — STORM SEWER (BELOW GRADE)
- ST — STORM SEWER (ABOVE GRADE)
- SEC — SECONDARY STORM SEWER
- GR — GREASE SEWER (BELOW GRADE)
- GR — GREASE SEWER (ABOVE GRADE)
- SCW — SOFT COLD WATER
- VENT
- G — GAS LINE (BELOW GRADE)
- G — GAS LINE (ABOVE GRADE)
- POINT OF CONNECTION NEW TO EXISTING
- POINT OF REMOVAL FOR DEMOLITION
- ΔT — DELTA T (TEMPERATURE DIFFERENCE)
- A / B — PHOTO DETAIL OR SECTION IDENTIFICATION TARGET
  A = DETAIL NUMBER.
  B = SHEET NUMBER ON WHICH DETAIL IS LOCATED.
- HB — HOSE BIBB
- FD — FLOOR DRAIN
- HD — HUB DRAIN
- TD — TRENCH DRAIN
- A — COMPRESSED AIR (BELOW GRADE)
- A — COMPRESSED AIR (ABOVE GRADE)
- FLOOR CLEANOUT
- CLEANOUT
- EXTERIOR CLEANOUT
- HORIZONTAL CLEANOUT
- PD — PAN DRAIN (FROM WATER HEATER)
- FW — FILTERED WATER
- SHOCK ABSORBER
- GD — GARBAGE DISPOSAL
- DW — DISHWASHER

NOTE:

SYMBOLS SHOWN ON THIS PLUMBING LEGEND ARE FOR REFERENCE PURPOSES ONLY. ALL OF THESE SYMBOLS MAY NOT BE USED FOR THIS PROJECT.

SPECIFICATIONS

PART 1 – GENERAL

1.1 SECTION INCLUDES
A. GENERAL PROVISIONS SPECIFICALLY APPLICABLE TO DIVISION 15 SECTIONS, IN ADDITION TO DIVISION 1 – GENERAL REQUIREMENTS.

1.2 SCOPE
A. THE WORK SHALL INCLUDE THE PROVISIONS OF SYSTEMS, EQUIPMENT AND MATERIALS SPECIFIED IN THIS DIVISION AND AS CALLED FOR ON THE DRAWINGS. WORK SHALL ALSO INCLUDE SUPERVISION, OPERATION, METHODS AND LABOR FOR THE FABRICATION, START–UP AND TESTS FOR A COMPLETE OPERATIONAL PLUMBING INSTALLATION.

B. DRAWINGS FOR THE WORK ARE DIAGRAMMATIC IN NATURE AND ARE INTENDED TO CONVEY THE SCOPE OF THE INSTALLATION AND TO INDICATE THE GENERAL ARRANGEMENT AND LOCATIONS OF THE WORK. BECAUSE OF THE SCALE OF THE DRAWINGS, CERTAIN BASIC ITEMS SUCH AS PIPE FITTINGS, ACCESS PANELS, AND SLEEVES MAY NOT BE SHOWN. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR SELECTING THE EQUIPMENT TO FIT THE SPACE PROVIDED. THE LOCATION AND SIZES FOR PIPE FITTINGS, SLEEVES, INSERTS, FIRE AND/OR SMOKE DAMPERS, AND OTHER BASIC ITEMS REQUIRED BY CODE AND OTHER SECTIONS SHALL BE COORDINATED AND INCLUDED FOR THE PROPER INSTALLATION OF THE WORK.

C. EQUIPMENT SPECIFICATIONS MAY NOT DEAL INDIVIDUALLY WITH MINUTE ITEMS REQUIRED SUCH AS COMPONENTS, PARTS, CONTROLS AND DEVICES WHICH MAY BE REQUIRED TO PRODUCE THE EQUIPMENT PERFORMANCE SPECIFIED OR AS REQUIRED TO MEET THE EQUIPMENT WARRANTIES. WHERE SUCH ITEMS ARE REQUIRED, THEY SHALL BE INCLUDED BY THE INSTALLER OF THE EQUIPMENT, WHETHER OR NOT SPECIFICALLY INDICATED IN THE CONTRACT DOCUMENTS WITH NO ADDITIONAL COST INCURRED.

D. WHERE NOTED ON THE DRAWINGS OR INDICATED IN OTHER SECTIONS OF THE SPECIFICATION, THE CONTRACTOR FOR THIS DIVISION SHALL INSTALL PLUMBING EQUIPMENT FURNISHED BY OTHERS, AND SHALL MAKE ALL FINAL CONNECTIONS. CONTRACTOR SHALL INSTALL EQUIPMENT AND SYSTEMS IN STRICT ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.

E. COORDINATE WITH ALL TRADES IN SUBMITTAL OF SHOP DRAWINGS. TIGHT SPACE CONDITIONS SHALL BE DETAILED TO THE SATISFACTION OF ALL TRADES, SUBJECT TO THE REVIEW AND FINAL ACCEPTANCE OF THE ARCHITECT/ENGINEER. IN THE EVENT THAT THE CONTRACTOR INSTALLS HIS WORK BEFORE COORDINATING WITH OTHER TRADES OR SO AS TO CAUSE ANY INTERFERENCE WITH THE WORK OF THE OTHER TRADES THIS CONTRACTOR SHALL MAKE ALL REQUIRED CHANGES TO CORRECT THE CONDITION AT NO ADDITIONAL COST TO THE PROJECT.

F. CONTRACTOR SHALL VERIFY ALL EQUIPMENT CONNECTION SIZES PRIOR TO INSTALLATION OF ANY SYSTEMS. THIS CONTRACTOR SHALL ADJUST PIPING SYSTEM SIZES AS REQUIRED TO MATCH EQUIPMENT CONNECTIONS. UTILIZE REDUCERS WHERE EQUIPMENT CONNECTIONS ARE SMALLER THAN PIPE SIZES INDICATED ON PLANS, NO PIPING SHALL BE DECREASED IN SIZE (IN THE DIRECTION OF FLOW).

1.3 EXAMINATION OF BIDDING DOCUMENTS:
A. EACH BIDDER SHALL EXAMINE THE BIDDING DOCUMENTS CAREFULLY AND NOT LATER THAN TEN (10) DAYS PRIOR TO THE DATE FOR RECEIPT OF BIDS, SHALL MAKE WRITTEN REQUEST TO THE ENGINEER FOR INTERPRETATION OR CORRECTION OF ANY AMBIGUITY, INCONSISTENCY OR ERROR THEREIN. ANY INTERPRETATION OR CORRECTION WILL BE ISSUED AS AN ADDENDUM BY THE ENGINEER. ONLY A WRITTEN INTERPRETATION OR CORRECTION TO BID DOCUMENTS BY ADDENDUM SHALL BE BINDING. NO BIDDER SHALL RELY UPON ANY INTERPRETATION OR CORRECTION GIVEN BY ANY OTHER METHOD.

1.4 SUBSTITUTIONS:
A. EXCEPT AS PROVIDED BELOW, EACH BIDDER REPRESENTS THAT HIS BID IS BASED UPON THE MATERIALS AND EQUIPMENT DESCRIBED IN THE BIDDING DOCUMENTS.

B. NO SUBSTITUTIONS FOR OTHER MATERIALS AND EQUIPMENT WILL BE CONSIDERED UNLESS WRITTEN REQUEST HAS BEEN SUBMITTED TO THE ENGINEER FOR APPROVAL AT LEAST TEN (10) DAYS PRIOR TO THE DATE FOR RECEIPT OF BIDS. EACH SUCH REQUEST SHALL INCLUDE A COMPLETE DESCRIPTION OF THE PROPOSED SUBSTITUTE, THE NAME OF THE MATERIAL OR EQUIPMENT FOR WHICH IT IS TO BE SUBSTITUTED, DRAWINGS, CUTS, PERFORMANCE AND TEST DATA OR INFORMATION NECESSARY FOR A COMPLETE EVALUATION.

C. IF THE ENGINEER APPROVES ANY PROPOSED SUBSTITUTION, SUCH APPROVAL WILL BE ISSUED AS AN ADDENDUM FORWARDED TO ALL PARTICIPATING BIDDERS.

D. IF ANY BIDDER IS UNABLE TO PROCURE WRITTEN APPROVAL OF ANY SUBSTITUTION FROM THE ENGINEER PRIOR TO THE OPENING OF BIDS, THEN HE SHALL BASE HIS BID ON ITEMS AND SYSTEMS AS SPECIFIED IN BID DOCUMENTS.

E. SUBSTITUTIONS REQUESTED ON THE BID PROPOSAL FORM WHICH ARE PRIOR APPROVED BY THE ENGINEER WILL BE INCORPORATED INTO THE CONTRACT WITH THE SUCCESSFUL BIDDER.

F. REQUESTS FOR ANY SUBSTITUTIONS NOT SUBMITTED AND APPROVED IN ACCORDANCE WITH THE ABOVE INSTRUCTIONS WILL BE DENIED BY THE ENGINEER.

1.5 REGULATORY REQUIREMENTS:
A. ALL INSTALLATIONS AND EQUIPMENT SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE STATUTES, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION.
B. CONFORM TO THE LATEST EDITION OF THE INTERNATIONAL PLUMBING CODE.
C. CONFORM TO THE LATEST EDITION OF THE INTERNATIONAL FIRE PREVENTION CODE.
D. CONFORM TO THE LATEST EDITION OF THE INTERNATIONAL BUILDING CODE.

1.6 CUTTING AND PATCHING:
A. SUBMIT WRITTEN REQUEST IN ADVANCE OF CUTTING OR ALTERING ELEMENTS.

B. EMPLOY SKILLED AND EXPERIENCED INSTALLER TO PERFORM CUTTING AND PATCHING WHICH EFFECT:
B.1 STRUCTURAL INTEGRITY OF ELEMENT.
B.2 INTEGRITY OF WEATHER.
B.3 EFFICIENCY, MAINTENANCE, OR SAFETY OF ELEMENT.
B.4 VISUAL QUALITIES OF SIGHT.
B.5 WORK OF OWNER OR SEPARATE CONTRACTOR.

PART 2 – PRODUCTS

2.1 PIPE HANGERS AND SUPPORTS
A. MANUFACTURERS:
A.1 B–LINE
A.2 OTHER ACCEPTABLE MANUFACTURERS OFFERING EQUIVALENT PRODUCTS.
A.2.1 MICHIGAN HANGER
A.2.2 PHD

2.2 PIPING INSULATION:
A. COMMERCIAL SPACE:
A.A. ALL HOT WATER PIPING = R–4 MINIMUM
A.B. HOT WATER RETURN PIPING = R–4.
C. ALL PIPING WITHIN THE ATTIC OR UNCONDITIONED SPACE SHALL BE INSULATED.

D. MANUFACTURERS:
A.1 OWENS CORNING
A.2 JOHNS MANVILLE
A.3 KNAUF
E. ASTM C547, RIGID MOLDED NON–COMBUSTIBLE FIBERGLASS INSULATION. 'K' VALUE .024 @ 75 DEGREES F.
F. VAPOR BARRIER JACKET, KRAFT PAPER WITH GLASS FIBER YARN AND BONDED TO ALUMINUM FILM. CLOSURE SYSTEM SHALL BE UL 181.

2.3 PIPING: DRAINAGE, WASTE & VENT PIPING
A. PVC: ASTM D2665 SCHEDULE 40 PVC SOLID WALL PIPING.
A.1 FITTINGS: ASTM D2665 SCHEDULE 40 PVC DWV FITTINGS.
A.2 JOINTS: ASTM D2564 SOLVENT CEMENT. JOINTS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2855.
B. FIRE WRAPPED PVC OR CAST IRON PIPING TO BE USED IN ALL PLENUM SPACES.
C. FOAM CORE SCHEDULE 40 DWV PIPE IS NOT AN ACCEPTABLE ALTERNATE TO STANDARD SCHEDULE 40 PVC.

2.4 PIPING: WATER PIPING
A. COPPER PIPING: ASTM B88 TYPE 'L' HARD DRAWN.
A.1 FITTINGS: ASME 16.18 CAST BRONZE OR ASME B16.22 WROUGHT COPPER OR BRONZE.
A.2 JOINTS: ASTM B32 SOLDER, ASTM 95–5 TA MINIMUM, FLUX ASTM B813. JOINTS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM B828.
A.3 SUBSTITUTIONS: CPVC IS AN ACCEPTABLE ALTERNATIVE TO COPPER ONLY IF APPROVED BY BUILDING OWNER.
B. CPVC PIPING: ASTM F441/F441M–15 CHLORINATED POLY PLASTIC PIPE. SCHEDULE 40 AND 80 HOT AND COLD WATER DISTRIBUTION PIPING. IS AN ACCEPTABLE ALTERNATE UPON APPROVAL OF ENGINEER, BUILDING OWNER AND PROJECT OWNER.
B.A. IT IS NOT ACCEPTABLE TO ROUTE CPVC PIPING BELOW GRADE OR WITHIN CONCRETE.
C. PEX PIPING: ASTM F877–18 CROSSLINKED POLYETHYLENE HOT AND COLD WATER DISTRIBUTION PIPING. IS AN ACCEPTABLE ALTERNATE UPON APPROVAL OF ENGINEER, BUILDING OWNER AND PROJECT OWNER

2.5 PIPING: GAS PIPING
A. STEEL PIPE: ASTM A 53/A 53M; TYPE E OR S; GRADE B; BLACK. WALL THICKNESS OF WROUGHT–STEEL PIPE SHALL COMPLY WITH ASME B36.10M.
A.1 MALLEABLE–IRON THREADED FITTINGS: ASME B16.3, CLASS 150, STANDARD PATTERN, WITH THREADED ENDS ACCORDING TO ASME B1.20.1.
A.2 STEEL THREADED FITTINGS: ASME B16.11, FORGED STEEL WITH THREADED ENDS ACCORDING TO ASME B1.20.1.
A.3 STEEL WELDING FITTINGS: ASME B16.9, WROUGHT STEEL OR ASME B16.11, FORGED STEEL.
A.4 UNIONS: ASME B16.39, CLASS 150, MALLEABLE IRON WITH BRASS–TO–IRON SEAT, GROUND JOINT, AND THREADED ENDS ACCORDING TO ASME B1.20.1.
A.5 CAST–IRON FLANGES AND FLANGED FITTINGS: ASME B16.1, CLASS 125.
A.6 JOINT COMPOUND AND TAPE: SUITABLE FOR NATURAL GAS.
A.7 STEEL FLANGES AND FLANGED FITTINGS: ASME B16.5.
A.8 GASKET MATERIAL: THICKNESS, MATERIAL, AND TYPE SUITABLE FOR NATURAL GAS.

2.5 CONDENSATE PIPING
A. ALL PIPING RECEIVING CONDENSATE OR DRAINAGE FROM ANY TYPE OF EVAPORATOR PRODUCING COLD WATER SHALL BE INSULATED.

PART 3 – INSTALLATION

3.1 INSTALL IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

3.2 PROVIDE NON–CONDUCTING DIELECTRIC CONNECTIONS WHEREVER JOINTING DISSIMILAR METALS.

3.3 ROUTE PIPING IN ORDERLY MANNER AND MAINTAIN GRADIENT.

3.4 INSTALL PIPING TO CONSERVE BUILDING SPACE AND NOT INTERFERE WITH USE OF SPACE.

3.5 GROUP PIPING WHENEVER PRACTICAL AT COMMON ELEVATIONS.

3.6 INSTALL PIPING TO ALLOW FOR EXPANSION AND CONTRACTION WITHOUT STRESSING PIPE, JOINTS, OR CONNECTED EQUIPMENT.

3.7 PROVIDE CLEARANCE FOR INSTALLATION OF INSULATION AND ACCESS TO VALVES AND FITTINGS.

3.8 PROVIDE ACCESS WHERE VALVES AND FITTINGS ARE NOT EXPOSED. COORDINATE SIZE AND LOCATION OF ACCESS DOORS WITH APPROPRIATE ARCHITECTURAL SECTION.

3.9 ESTABLISH ELEVATIONS OF BURIED PIPING OUTSIDE THE BUILDING TO ENSURE PROPER SLOPE AND COVER.

3.10 ESTABLISH ELEVATIONS OF EXISTING BURIED PIPING FOR CONNECTION TO NEW WORK TO ENSURE PROPER SLOPE AND COVER.

3.11 WHERE PIPE SUPPORT MEMBERS ARE WELDED TO STRUCTURAL BUILDING FRAMING, SCRAPE, BRUSH CLEAN, AND APPLY ONE COAT OF ZINC RICH PRIMER TO WELDING.

3.12 EXTEND CLEANOUTS TO FINISHED FLOOR OR WALL SURFACE. LUBRICATE THREADED CLEANOUT PLUGS WITH MIXTURE OF GRAPHITE AND LINSEED OIL. ENSURE CLEARANCE AT CLEANOUT FOR RODDING OF DRAINAGE SYSTEM.

3.13 RESET SPRINKLER HEADS FROM UPRIGHT POSITION TO DOWN POSITION TO CENTER OF NEW CEILING TILE.

3.14 TORQUE ALL HUBLESS CAST IRON COUPLING IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. UTILIZE COUPLING MANUFACTURER'S PRE–SET TORQUE WRENCH.

3.15 INSTALL WATER HAMMER SHOCK ARRESTORS AT EACH FIXTURE OR BATTERY OF FIXTURES WHERE QUICK CLOSING VALVES ARE UTILIZED. . ARRESTORS SHALL BE FACTORY FABRICATED AND CONFORM TO ASSE 1010. INSTALL ARRESTORS AND SIZE PER PLUMBING AND DRAINAGE INSTITUTE STANDARD P.D.I. WH–201. ACCEPTABLE MANUFACTURERS ARE ZURN, JOSAM, SIOUX CHIEF. PPP INC. FOR 1–11 FU'S PROVIDE PDI–A, FOR 12–32 FU'S PDI–B, 33–60 FU'S PDI–C, 61–113 FU'S PDI–D. INSTALL PER MANUFACTURER'S INSTRUCTIONS.

3.16 ALL CONTRACTORS ARE RESPONSIBLE FOR PROPERLEY FIRE SEALING ALL FIRE RATED PENETRATIONS WITH AN APPROVE UL FIRE RATED PENETRATION INSTALLATION METHOD.

GENERAL NOTES

1. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY FITTINGS AS REQUIRED BY ALL APPLICABLE CODES AND GOVERNING AUTHORITIES.
2. CONTRACTOR SHALL VERIFY AND CORRECT AS REQUIRED TO MEET ALL CODES AND REGULATIONS ANY POSSIBLE DISCREPANCIES BETWEEN TYPE AND SIZE OF CONNECTION SPECIFIED IN PLUMBING FIXTURE SCHEDULE AND FIXTURES ACTUALLY INSTALLED ON THE SITE.
3. ALL DRAINAGE PIPING 3" AND LARGER SHALL HAVE A MINIMUM $\frac{1}{8}$" PER FOOT SLOPE. ALL DRAINAGE PIPING 2$\frac{1}{2}$" AND SMALLER SHALL HAVE A MINIMUM $\frac{1}{4}$" PER FOOT SLOPE, UNLESS OTHERWISE NOTED.
4. VENT PIPING SHOWN ON FLOOR PLANS IS ONLY INDICATIVE EXCEPT FOR VTR LOCATIONS.
5. VALVES AND FITTINGS SHALL BE OF SAME SIZE OF LINE ON WHICH THEY ARE LOCATED, UNLESS OTHERWISE INDICATED ON DRAWINGS.
6. CONTRACTOR SHALL COORDINATE ALL WORK WITH OTHER TRADES.
7. CONTRACTOR SHALL FIELD VERIFY ALL GIVEN MEASUREMENTS PRIOR TO LAYING AND CONNECTING ALL SANITARY AND WASTE PIPING AND NOTIFY ARCHITECT OF ANY DISCREPANCIES.
8. AIR CHAMBERS SHALL NOT BE CONSIDERED AN EQUAL TO WATER ARRESTORS AS SPECIFIED.
9. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING FIRE RATING AND WEATHERPROOFING INTEGRITY OF ALL PIPING AND PENETRATIONS.
10. ALL WATER SUPPLY AND SANITARY LINES SHALL BE RUN AS CLOSE TO PLANS AS POSSIBLE WITH NO CHANGES IN SIZING.
11. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY SUPPORTING DEVICES FOR ALL FIXTURES INCLUDED IN CONTRACT OR HEREIN SPECIFIED OR OTHERWISE.
12. CHANGES IN THE DIRECTION OF SANITARY PIPING SHALL NOT BE MADE WITH FITTINGS WHICH WILL CAUSE EXCESSIVE REDUCTION IN THE VELOCITY OF FLOW OR CREATE ANY OTHER ADVERSE EFFECT UNLESS PHYSICALLY IMPOSSIBLE (IE: USE OF SANITARY TEE IN A HORIZONTAL CONNECTION, USE OF A DOUBLE SANITARY TEE IN A VERTICAL STACK, IN GENERAL, USE OF SHORT–RADIUS FITTINGS FOR BRANCH TO HOUSE DRAIN OR STACK CONNECTION).
13. ALL DRAINAGE PIPING SHALL BE MARKED WITH THE SEAL OF APPROVAL OF THE NATIONAL SANITATION FOUNDATION.
14. DO NOT PENETRATE FOUNDATIONS WITH PIPING, COORDINATE WITH GENERAL CONTRACTOR TO DROP FOUNDATIONS AS REQUIRED TO CLEAR PLUMBING SERVICES WHERE ABSOLUTELY NECESSARY. ALL PIPING PENETRATING A BEARING WALL OR FOOTING MUST BE SLEEVED AND LOCATION APPROVED BY STRUCTURAL ENGINEER.
15. ROUTE ALL PIPING CONCEALED ABOVE CEILINGS, WITHIN WALLS, OR IN CHASES. PIPING EXPOSED SHALL BE SLOPED AND PAINTED TO MATCH ARCHITECTURAL FINISHES. PIPING IN MECHANICAL ROOMS MAY BE EXPOSED.
16. PROVIDE ACCESS PANELS TO ALL VALVES WITHIN CHASES OR ABOVE NON–ACCESSIBLE CEILINGS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
17. SEE ARCHITECTURAL DRAWINGS FOR EXACT LOCATIONS OF PLUMBING FIXTURE MOUNTING HEIGHTS, AND DIMENSIONS.
18. CONTRACTOR SHALL VERIFY INVERT ELEVATIONS OF SEWERS TO WHICH NEW SEWER LINES ARE TO BE CONNECTED BEFORE INSTALLATION OF NEW SEWER LINE.
19. ALL VENTS THROUGH ROOF SHALL BE MINIMUM OF 10'–0" FROM ANY AIR INTAKES.
20. CONTRACTOR SHALL INSTALL DIELECTRIC UNIONS AT CONNECTIONS OF DISSIMILAR METALS.
21. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS (INCLUDING PIPE ROUTING AND EQUIPMENT LOCATIONS) TO ARCHITECT/ENGINEER FOR REVIEW AND APPROVAL PRIOR TO THE INSTALLATION OR PURCHASING OF ANY PIPING AND/OR EQUIPMENT.
22. PROVIDE $\frac{3}{4}$" C.W. SUPPLY WITH ANGLE STOP AND FLEXIBLE SUPPLY TO REFRIGERATORS WITH ICE MAKERS AT HEIGHT REQUIRED BY MANUFACTURER OF EQUIPMENT INSTALLED.
23. PROVIDE $\frac{3}{4}$" H.W. SUPPLY WITH ANGLE STOP AND FLEXIBLE SUPPLY TO DISHWASHER MACHINE, AT HEIGHT REQUIRED BY MANUFACTURER OF EQUIPMENT INSTALLED.
24. ALL WATER PIPING INSTALLED IN EXTERIOR WALLS SHALL BE PLACED ON THE INTERIOR SIDE OF THE WALL, SO THAT WALL INSULATION CAN BE PLACED ON THE EXTERIOR SIDE OF THE PIPING.
25. FIELD VERIFICATION OF EXISTING PIPING: ALL EXISTING PIPING SHOWN ON THE CONSTRUCTION DOCUMENTS IS BASED OFF OF VISUAL SITE INVESTIGATION AND AS BUILTS DRAWINGS OF THE EXISTING SITE AND BUILDING CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE LICENSED PLUMBING CONTRACTOR TO FIELD VERIFY ALL EXISTING PIPING LOCATIONS, TYPES, SIZES, ELEVATIONS AND INVERTS. NOTIFY ENGINEER IF THE CONDITIONS ARE NOT AS SHOWN ON THE PLANS OR AS STATED IN THE SPECIFICATIONS PRIOR TO THE INITIATION OF ANY WORK. IDENTIFICATION AND VERIFICATION OF EXISTING PIPING TO BE ACCOMPLISHED BY THE FOLLOWING MEANS:
    - MANDATORY DYE TESTING OF ALL EXISTING SANITARY, STORM AND GREASE WASTE PIPING FOR SYSTEM IDENTIFICATION.
    - SNAKE ALL SANITARY, STORM AND GREASE WASTE PIPING FOR A DISTANCE OF 100 FEET AND REPORT ANY BLOCKAGES.
    - TEST WATER PRESSURE TO INSURE MINIMUM PSI MATCHES MOST DEMANDING EQUIPMENT SUPPLIED OR TO BE INSTALLED.
    - ALL IDENTIFICATION AND VERIFICATION RESULTS SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER FOR REVIEW PRIOR TO THE INITIATION OF ANY WORK.
26. IF NO PLUMBING ELEVATION OR INVERT IS NOTED ON PLANS THE MINIMUM DEPTH OF THE PLUMBING TO CIVIL CONNECTION SHALL BE CALCULATED BASED ON THE FURTHERS POSSIBLE PLUMBING FIXTURE DISTANCE TIMES 1%. TOTAL LINE LENGTH*1%=DEPTH B.F.F. AT CIVIL POINT OF CONNECTION.

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2015 These documents and their contents are the property of FUGLEBERG KOCH - ARCHITECTS, and are issued only for the specific project listed on these drawings. Any reproduction, alteration, or modification of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00



THE MADISON
HUNTSVILLE, AL

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722

SYMBOL LEGEND & GENERAL NOTES PLUMBING

CHP0.01

PLUMBING FIXTURE UNIT CALCULATION


TYPE OF SERVICE	WATER	SANITARY
FIXTURE UNIT COUNT TOTAL	45	31
TOTAL GALLONS PER MINUTE	48	--
SIZE OF SERVICE CONNECTION	2"	4"

GENERAL NOTES:

1. WHERE A HORIZONTAL DRAINAGE PIPE HAS A CHANGE OF HORIZONTAL DIRECTION GREATER THAN 45 DEGREES, A CLEANOUT SHALL BE INSTALLED AT THE CHANGE OF DIRECTION. WHERE MORE THAN ONE CHANGE OF HORIZONTAL DIRECTION GREATER THAN 45 DEGREES OCCURS WITHIN 40 FEET OF DEVELOPED LENGTH OF PIPING, THE CLEANOUT INSTALLED FOR THE FIRST CHANGE OF DIRECTION SHALL SERVE AS THE CLEANOUT FOR ALL CHANGES IN DIRECTION WITHIN THAT 40 FEET OF DEVELOPED LENGTH OF PIPING.
2. ALL SHUT-OFF VALVES SHALL BE FULLY ACCESSIBLE. SEE ARCHITECTURAL DRAWINGS FOR RATED WALLS AND CEILINGS, AND PROVIDE RATED ACCESS PANELS.
3. SEE SHEET CHP2.03 FOR RISER DIAGRAMS.
4. PROVIDE TRAP PRIMER VALVES TPV-1 WITH SHUT OFF VALVE AND ¾" CW SUPPLY TO EACH FLOOR DRAIN. ALL VALVES SHALL BE FULLY ACCESSIBLE.
5. INSTALL WATER HAMMER SHOCK ARRESTORS AT ICE MAKERS, DISHWASHERS. WASHER BOXES, AND AT ALL QUICK CLOSING SOLENOID VALVES. SIZE SHOCK ARRESTORS PER PLUMBING AND DRAINAGE INSTITUTE STANDARD P.D.I. WH-201. SHOCK ARRESTORS SHALL CONFORM TO ASSE 1010. ACCEPTABLE MANUFACTURERS – SIOUX CHIEF, PRECISION PLUMBING PRODUCTS INC., FOR 1-11 F.U.'S PROVIDE PDI-A, 12-32 F.U.'S PDI-B, 33-60 F.U.'S PDI-C. INSTALL PER MANUFACTURER'S INSTRUCTIONS.
6. ALL FREEZE PROOF WALL HYDRANTS/HOSE BIBS TO BE COORDINATED WITH WALL THICKNESS TO ENSURE PROPER INSTALLATION DEPTH PRIOR TO CONSTRUCTION.
7. PROVIDE ASSE 1024 DUAL CHECK VALVE BACKFLOW PREVENTER AT DISHWASHER, COFFEE, ICE AND TEA MACHINES. WATTS NO. SD-2.
8. PROVIDE LEAD-FREE POINT OF USE THERMOSTATIC MIXING VALVES TMV-1 ASSE 1070 AT HAND SINKS AND/OR PUBLIC LAVATORIES TO TEMPER HOT WATER TO 110°F.
9. ALL COMMERCIAL WATER HEATERS ARE REQUIRED TO HAVE A MIXING VALVE FOR MEANS OF TEMPERING WATER PRIOR TO DISTRIBUTION TO FIXTURES.

REFERENCE NOTES: ⓧ

1. TERMINATE WATER HEATER DRAIN PAN PIPING ABOVE GROUND AT EXTERIOR.
2. ¾" CONDENSATE DRAIN CONNECTION TO AC UNIT. ¾" CONDENSATE DRAIN DOWN.
3. TERMINATE CONDENSATE DRAIN PIPING ABOVE GRADE AT EXTERIOR WITH SCREENED WEATHERPROOF FITTING, SEE DETAIL.



K2 CLUBHOUSE - SANITARY FLOOR PLAN - PLUMBING
1/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project cited on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

ALABAMA No. 33985 PROFESSIONAL ENGINEER

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	04/15/2022
Project #:	5722


THE MADISON
HUNTSVILLE, AL

CLUBHOUSE SANITARY PLUMBING

CHP2.01

REFERENCE NOTES: ⓧ

1. 2" POTABLE CW SUPPLY BELOW GRADE, FOR CONTINUATION SEE CIVIL DRAWINGS.
2. SHUT-OFF VALVE AND WATER METER IN CAST IRON ACCESS BOX FLUSH WITH PAVEMENT.
3. ELECTRIC WATER HEATER, SEE SCHEDULE & DETAIL.
4. HOT WATER RECIRCULATION PUMP, SEE SCHEDULE & DETAIL.
5. ¾" CW & HW DOWN TO THERMOSTATIC MIXING VALVE TMV-2, ¾" 140°F TEMPERED WATER TO PLUMBING FIXTURES.
6. SHUT-OFF VALVE WITHIN RATED ACCESS PANEL, TYPICAL.



K2 CLUBHOUSE - DOMESTIC WATER FLOOR PLAN - PLUMBING

1/4" = 1'-0"

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project cited on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00


ALABAMA No. 33985 PROFESSIONAL ENGINEER

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	04/15/2022
Project #:	5722


THE MADISON
HUNTSVILLE, AL

CLUBHOUSE
DOMESTIC WATER
PLUMBING

CHP2.02



1 CLUBHOUSE - DOMESTIC WATER ISOMETRIC - PLUMBING
NTS



2 CLUBHOUSE - SANITARY ISOMETRIC - PLUMBING
NTS

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www. fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co
Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

BLS/AJB No. 73885 PROFESSIONAL ENGINEER ALABAMA

THE MADISON
HUNTSVILLE, AL

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	04/15/2022
Project #:	5722

CLUBHOUSE ISOMETRIC PLUMBING

CHP2.03

© 2015 These documents and their contents are the property of FUGLEBERG KOCH - AA26002105, and are issued only for the specific project noted on these drawings. Any reproductions, versions, or modifications of these documents without the expressed written consent of Fuglebergh Koch is prohibited by law.

GENERAL NOTES:

A. ALL PLUMBING FIXTURES MUST BE REVIEWED AND APPROVED BY THE ARCHITECT/OWNER/BRAND PRIOR TO ORDERING.

B. CONTRACTOR TO VERIFY ALL BATHTUB AND SHOWER SIZES, INCLUDING DRAIN LOCATIONS, WITH ARCHITECT PRIOR TO ORDERING.

C. CONTRACTOR TO VERIFY LAVATORY AND SINK SIZES ARE COORDINATED WITH COUNTERTOPS BEING INSTALLED PRIOR TO ORDERING.

D. CONTRACTOR TO VERIFY ALL PLUMBING EQUIPMENT SELECTED FITS WITHIN DESIGNATED SPACE SHOWN ON PLUMBING PLANS AND PROVIDES REQUIRED CLEARANCE AS LISTED BY MANUFACTURER.

E. CONTRACTOR SHALL COORDINATE VOLTAGE AND PHASE OF EACH PIECE OF EQUIPMENT WITH THE ELECTRICAL CONTRACTOR PRIOR TO ORDERING.

PLUMBING SPECIALTIES SCHEDULE - CLUBHOUSE

MARK	FIXTURE	WASTE	TRAP	VENT	COLD WATER	HOT WATER	MANUFACTURER /MODEL #	DESCRIPTION
AAV–1	AIR ADMITTANCE VALVE	–	–	–	–	–	STUDOR TEC–VENT	AUTOMATIC AIR ADMITTANCE VALVE WITH VENTED ACCESS PANEL. LOCATE FULLY ACCESSIBLE.
SA	SHOCK ARRESTOR	–	–	–	–	–	SIOUX CHIEF 650 SERIES	SIZE PER MANUFACTURER'S RECOMMENDATIONS. PDI CERTIFIED. WHA–1: SIZE "A", WHA–2: SIZE "B". SIZE PER PDI METHOD.
WCO–1	WALL CLEANOUT	SEE DWG.	–	–	–	–	ZURN Z1446	CLEANOUT TEE, DURA–COATED CAST IRON BODY, GAS AND WATERTIGHT ABS TAPERED THREAD PLUG, AND ROUND, SMOOTH STAINLESS STEEL WALL ACCESS COVER WITH SECURING SCREW.
ECO–1	EXTERIOR CLEANOUT	SEE DWG.	–	–	–	–	ZURN ZS1400–VP	"LEVEL–TROL" ADJUSTABLE FLOOR CLEANOUT, DURA–COATED CAST IRON BODY WITH GAS AND WATERTIGHT ABS TAPERED THREAD PLUG AND ROUND SECURED STAINLESS STEEL ADJUSTABLE TO FINISHED FLOOR WITH VANDALPROOF SCREWS.
FCO–1	FLOOR CLEANOUT	SEE DWG.	–	–	–	–	ZURN ZS1400–VP	"LEVEL–TROL" ADJUSTABLE FLOOR CLEANOUT, DURA–COATED CAST IRON BODY WITH GAS AND WATERTIGHT ABS TAPERED THREAD PLUG AND ROUND SECURED STAINLESS STEEL ADJUSTABLE TO FINISHED FLOOR WITH VANDALPROOF SCREWS.
HB–1	HOSE BIBB – BUILDING FREEZE PROOF						ZURN Z1320XL WITH BOX	FREEZE PROOF ANTI–SIPHON WALL FAUCET WITH EXTERNAL VACUUM BREAKER, ALL BRONZE INTERIOR COMPONENTS, VANDAL–RESISTANT OPERATING STEM, ROUGH BRONZE EXTERIOR AND ¾" MALE HOSE CONNECTION, LOOSE KEY HANDLE AND 3⅛" DEEP BOX.
FD–1	FLOOR DRAIN	SEE DWG.	–	–	–	–	ZURN ZN415S–HD–P	DURA–COATED CAST IRON BODY WITH BOTTOM OUTLET, COMBINATION INVERTIBLE MEMBRANE CLAMP AND ADJUSTABLE COLLAR WITH SEEPAGE SLOTS AND "TYPE S" POLISHED NICKEL BRONZE, SQUARE HEAVY–DUTY STRAINER AND ½" TRAP PRIMER CONNECTION.
TPV–1	TRAP PRIMER VALVE	–	–	–	1/2"	–	PRECISION PLUMBING PRODUCTS PR–500	PROVIDE FULLY ACCESSIBLE SHUT OFF VALVE TO EACH PRIMER VALVE.
TMV–1	MIXING VALVE	–	–	–	1/2"	1/2"	SYMMONS 7–225–CK	THERMOSTATIC CONTROLLER, CHECK STOPS, REMOVABLE CARTRIDGE WITH STRAINER, S.S. PISTON, THERMAL MOTOR. MIN FLOW RATE .5 GPM.
TMV–2	MIXING VALVE	–	–	–	3/4"	3/4"	WATTS LF1170	THERMOSTATIC CONTROLLER, LEAD FREE CAST COPPER SILICON ALLOY BODY CONSTRUCTION, SOLID WAX HYDRAULIC PRINCIPLE THERMOSTAT, INTEGRAL FILTER WASHERS AND CHECK VALVES, ADJUSTMENT CAP WITH LOCKING FEATURE. MIN FLOW RATE .5 GPM.
PRV–1	PRESSURE REGULATING VALVE	–	–	–	SIZE/ SEE DWG.	–	CLA–VAL 90–01	BRONZE BODY AND COVER, ANSI B16.24, GLOBE TPYE, BRONZE DISC GUIDE, SEAT & COVER, BUNA–N RUBBER DISC, NYLON REINFORCED BUNA–N RUBBER DIAPHRAGM, STAINLESS STEEL STEM NUT AND SPRING, STAINLESS STEEL PILOT SYSTEM.

NOTES:

1. ALL PLUMBING FIXTURES SHALL BE SUPPLIED WITH ANGLE STOP SUPPLY RISERS. THIS SHALL INCLUDE ALL WASHING MACHINES, DISHWASHERS & ICE MAKERS.
2. PROVIDE FULLY ACCESSIBLE SHOCK ARRESTORS ON SUPPLIES TO WASHING MACHINES, DISHWASHERS & ICE MAKERS.

PLUMBING FIXTURE SCHEDULE - CLUBHOUSE

MARK	FIXTURE	WASTE	TRAP	VENT	COLD WATER	HOT WATER	MANUFACTURER /MODEL #	DESCRIPTION
WC–1	WATER CLOSET – ADA TYPE	3"	INTEG	2"	1"	–	AMERICAN STANDARD 3351.511 ZURN Z1201–N_3 ZURN Z1201–ND3	WALL MOUNT, FLUSH VALVE – RIM 17" AFF, VITREOUS CHINA, WATER SAVER 1.1 GPF, SIPHON JET, ELONGATED BOWL, BOLT CAPS. COORDINATE FINISH WITH ARCHITECT. AMERICAN STANDARD FLUSH VALVE. SOLID PLASTIC OPEN FRONT ELONGATED SEAT (WHITE) W/S,S, CHECK HINGES. PROVIDE WALL CARRIER. EZCARRY ADJUSTABLE HORIZONTAL HIGH PERFORMANCE SIPHON JET NO–HUB WATER CLOSET CARRIER SYSTEM EZCARRY ADJUSTABLE HORIZONTAL HIGH PERFORMANCE BACK–TO–BACK SIPHON JET NO–HUB WATER CLOSET CARRIER SYSTEM
L–1	LAVATORY – ADA WALL HUNG	2"	1–1/4"	1–1/2"	1/2"	1/2"	AMERICAN STANDARD LUCERNE 0355.012 MOEN ADLER 84603 ZURN Z1231EZ	20"x18" WALL HUNG, VITREOUS CHINA, 4" CENTERS WITH FRONT OVERFLOW. TWO HANDLE LAVATORY FAUCET, 1.2 GPM, POP UP WASTE, P–TRAP AND WALL ARM. BRASSCRAFT ℄ TURN ANGLE STOP SUPPLIES W/SUPPLY TUBES AND ESCUTCHEONS. UNIVERSAL CONCEALED ARM CARRIER SYSTEM WITH ADJUSTABLE UPRIGHTS AND HEADER PLATES.
S–1	SINK (SINGLE BOWL)	2"	1–1/2"	1–1/2"	1/2"	1/2"	AMERICAN STANDARD COLONY 22SB.6252283S.075 MOEN ADLER 87233	25"x22"x6" SINGLE BOWL, 20 GAUGE STAINLESS STEEL, TOP MOUNT SINK. SINGLE LEVER HANDLE PULL DOWN SPRAYER, 1.5 GPM, STAINLESS STEEL FINISH. STAINLESS STEEL STRAINER DRAIN AND TAILPIECE, P–TRAP AND WALL ARM. BRASSCRAFT ℄ TURN ANGLE STOP SUPPLY TUBES & ESCUTCHEONS.
EWC–1	ELECTRIC WATER COOLER HIGH/LOW – INDOOR NO BOTTLE FILLER	2"	1–1/2"	1–1/2"	1/2"	–	ELKAY EZSTL8LC	WALL MOUNTED ADA BI–LEVEL NON–FILTERED REFRIGERATED, LIGHT GRAY GRANITE WATER COOLER. CHILLING CAPACITY OF 8.0 GPH WITH ELECTRONIC FRONT BUBBLER PUSHBAR ACTIVATION. 120V, 5 FLA, 370 WATTS POWER REQUIRED.
MS–1	MOP SINK	3"	3"	1–1/2"	1/2"	1/2"	FIAT MSB 830–AA 832–AA 889–CC TSB–100	24x24 TERRAZZO MOP BASIN. PROVIDE SERVICE FAUCET WITH VACUUM BREAKER, HOSE AND HOSE BUCKET, MOP HANGER AND STAINLESS STEEL DRAIN ASSB.

NOTES:

1. CONTRACTOR TO VERIFY IF THIS PROJECT HAS I.D. DRAWINGS. IF THERE ARE I.D. DRAWINGS THE PLUMBING FIXTURES SELECTED IN THE I.D. PACKAGE OVERRIDE THIS PLUMBING SCHEDULE.
2. COLOR/FINISH OPTIONS SHALL BE SUBMITTED TO THE ARCHITECT/I.D./OWNER PRIOR TO PURCHASE AND INSTALLATION.
3. REFER TO ARCHITECTURAL DRAWINGS FOR MOUNTING HEIGHTS OF ALL FIXTURES.
4. ALL PLUMBING FIXTURES SHALL BE SUPPLIED WITH ANGLE STOP SUPPLY RISERS. THIS SHALL INCLUDE ALL FAUCETS AND TOILETS.

ELECTRIC WATER HEATER SCHEDULE - CLUBHOUSE

MARK	TYPE	GALLONS	INPUT KW	GPH REC. @ 90°F RISE	VOLTAGE/PHASE	OPERATING WEIGHT (LBS.)	DIMENSIONS	SELECTION BASED ON: MANUFACTURER	SELECTION BASED ON: MODEL #	UNIFORM ENERGY FACTOR	NOTES
EWH–1	ELECTRIC	38	4.5	21	208/1ø	418	32"H x 23"ø – LOW BOY	A.O. SMITH OR EQUAL	ENLB–40	.92	1. & 2.

NOTES:
1. PROVIDE T & P VALVE, EXPANSION CONTROL DEVICE, AND 24 GAUGE 1½" DEEP WATER HEATER DRAIN PAN WITH 1" DRAIN CONNECTION. REFER TO DETAIL.
2. COORDINATE WATER HEATER LOCATION AND PIPING WITH MECHANICAL PLANS.

PUMP SCHEDULE - CLUBHOUSE

MARK	LOCATION	GPM	FT HEAD	CONN. SIZE OUTLET	MOTOR DATA HP/WATT	MOTOR DATA VOLTAGE/PHASE	SELECTION BASED ON: MANUFACTURER	SELECTION BASED ON: MODEL	NOTES
CP–1	CLUBHOUSE CIRCULATING PUMP	5	12	3/4"	1/25 HP	120/1ø	GRUNDFOS	UP15–42B7	1. & 2.

NOTES:
1. CIRCULATING PUMP SHALL OPERATE PER FBCE C404.6. PUMP SHALL START ON FLOW OF DEMAND HOT WATER AND BASED ON MAINTAINING LOOP TEMPERATURE OF 104°F.
2. PROVIDE WITH AQUASTAT AND FLOW CONTROL.

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT

Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE, SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

BRANDON L. SMITH No. 73885 STATE OF FLORIDA PROFESSIONAL ENGINEER


THE MADISON
HUNTSVILLE, AL

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approved:	BLS/AJB
Date:	04/15/2022
Project #:	5722


CLUBHOUSE SCHEDULE PLUMBING

CHP2.04


© 2019 These documents and their contents are the property of FUGLEBERG KOCH - AA26002105, and are issued only for the specific project noted on these drawings. Any reproductions, versions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.




7 NTS FLOOR CLEANOUT




6 NTS WALL CLEANOUT




5 NTS CONDENSATE DRAIN TERMINATION DETAIL




4 NTS TWO-WAY CLEANOUT



3 NTS HOT WATER RECIRCULATING PUMP DETAIL



2 NTS FREEZEPROOF WALL HYDRANT



1 NTS ELECTRIC WATER HEATER DETAIL

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT

ISSUE HISTORY

No.	Date	Description
1	04/15/22	Permit Submission

REVISION HISTORY

No.	Date	Description

© 2015 These documents and their contents are the property of FUGLEBERG KOCH - AA26002103, and are issued only for the specific project noted on these drawings. Any reproductions, revisions, or modifications of these documents without the expressed written consent of Fugleberg Koch is prohibited by law.

FUGLEBERG KOCH
2555 Temple Trail, Winter Park, FL 32789 (407) 629-0595
www.fuglebergkoch.com AA26002103

CONSULTANT
Joseph, Lawrence & Co Consulting Engineers
1180 HARWOOD AVE. SUITE 3000
ALTAMONTE SPRINGS, FLORIDA 32714
TEL: 321.972.4466
WWW.JLCENG.COM
CA NO. 4050 - E

JLC 22.0023.00

ALABAMA LICENSED PROFESSIONAL ENGINEER No. 33985 PROFESSIONAL ENGINEER

Drawn:	MJR/SMB
Checked:	BLS/AJB
Approval:	BLS/AJB
Date:	04/15/2022
Project #:	5722

THE MADISON
HUNTSVILLE, AL

CLUBHOUSE DETAIL PLUMBING

CHP2.05