





- GENERAL NOTES - THIS SHEET

1. ALL 120V RECEPTACLES ARE TO BE TAMPER RESISTANT.
2. ALL RECEPTACLES ON 20 AMP CIRCUIT TO BE 20 AMP RECEPTACLES.
3. COORDINATE EXACT LOCATION OF WH, AH, & HP W/ P.C. & M.C. BEFORE BEGINNING WORK.
4. E.C. TO CONFIRM ALL APPLIANCE LOCATIONS W/ARCH PRIOR TO BEGINNING WORK.
5. PROVIDE EXTRA BRACING FOR ANY CEILING FAN.
6. CONTRACTOR SHALL VERIFY THE EXACT LOCATIONS AND MOUNTING HEIGHTS FOR ALL OUTLETS BEFORE STARTING "ROUGH-IN" WORK. CONTRACTOR SHALL NOT "ROUGH-IN" ANY OUTLET, FIXTURE OR DEVICE OF ANY KIND WITHOUT FIRST OBTAINING THE WALK THRU CHECK OF EACH APARTMENT UNIT WITH THE OWNER AND GENERAL CONTRACTOR FOR COORDINATION OF FINAL LOCATIONS.
7. UNIT PANELS ARE TO BE INSTALLED SO THAT NO TRIM LATCH ON BREAKER IS GREATER THAN 48" AFF.
8. SEE BUILDING PLANS FOR RATING OF UNIT DEMISING WALLS & FLOOR CEILING ASSEMBLIES.
9. COORDINATE VENTILATION OF ANY IMPAIRED UNIT DESIGNATIONS WITH G.C. AND ARCH PRIOR TO BID.
10. NOTIFICATION DEVICES SHALL COMPLY WITH 2017 FLORIDA ACCESSIBILITY CODE 809.5.5.

- TAGGED NOTES - THIS SHEET

1. PROVIDE A SIMPLEX RECEPTACLE FOR MICROWAVE UNIT, MOUNT RECEPTACLE AT BACK OF UPPER CABINET; MICROWAVE UNIT IS MOUNTED OVER RANGE. COORDINATE EXACT LOCATION W/ G.C..
2. PROVIDE CHANNEL VISION BRAND STRUCTURED WIRING ENCLOSURE FOR NETWORKING PURPOSES WITHIN APARTMENT FOR MODULAR PUSH AND LOCK TELEPHONE, VIDEO, DATA, AND POWER MODULES. THE CABLE TV COAX AND TELEPHONE/DATA CAT 5 FROM THE LOWER LEVEL DATA ROOM(S) SHALL TERMINATE AT THIS BOX IN EACH APARTMENT, THEN FROM THIS BOX SPIT OUT TO FEED EACH DATA/TELEPHONE/CABLE TV OUTLET WITHIN EACH APARTMENT. USE 1" MODEL C-0119E IN THE 4BR AND 3BR UNITS AND USE 1/2" MODEL C-0112WE IN THE 2BR AND 1BR UNITS. USE 1/2" MODEL C-0112WE IN THE ADA COMPLIANT LOCATION. PROVIDE IN EACH STRUCTURED WIRING ENCLOSURE PROVIDE A DUPLEX ELECTRICAL POWER RECEPTACLE ON CIRCUIT NOTED.
3. CONFIRM EXACT LOCATION OF TV OUTLET W/ OWNER.
4. PROVIDE POWER FOR WATER METER COORD. LOCATION W/ P.C..
5. PROVIDE COUNTER TOP AIR SWITCH. NEXT TO SINK FOR GARBAGE DISPOSAL. CONFIRM EXACT LOCATION W/ OWNER.
6. HOOD LIGHTS AND CONTROLS TO BE SWITCHED SEPARATELY. SWITCHES TO BE COORDINATE IN AN ADA COMPLIANT LOCATION. COORDINATE WITH G.C..
7. PROGRAMMABLE EXHAUST FAN SWITCH PROVIDED BY M.C.. INSTALLED BY AND PROGRAMMED/DIALS SET BY M.C.. SEE MECH PLAN.
8. PROVIDE (2) GFI RECEPTACLES FOR DISHWASHER AND GARBAGE DISPOSAL TO BE LOCATED BELOW SINK IN READILY ACCESSIBLE LOCATION.
9. MECHANICAL CLOSET IS A RETURN PLENUM. ALL MATERIALS IN PLENUM ARE TO BE PLENUM RATED OR WRAPPED W/ PLENUM WRAP.




5711 SIX FORKS ROAD, SUITE 100
RALEIGH NC 27609
website www.planworx.com

Oasis at Surfside - Phase II

Zimmer Development Company

Cape Coral, Florida

PERMIT SET



ENGINEERING, PLLC
708 ST. MARYS ST
RALEIGH, NC 27605 LIC.#: P-009
P:919-341-4247 F:919-890-37
PLUMBING MECHANICAL ELECTRICAL

PROJECT NO:		002221	
DRAWN BY:		NITY	
CHECKED BY:		ZLT	
SHEET TITLE:			